## **Processing Materials**

- Work copies of applicant-submitted information
- Deficiency letter
- Deficiency response
- Correct & complete determination
- Any correspondence with the applicant after application receipt and prior to sending the Draft PD

# Processing Materials

### THE MONTANA DEPARTMENT OF NATURAL RESOURCES AND CONSERVATION

**GOVERNOR GREG GIANFORTE** 



DNRC DIRECTOR AMANDA KASTER

DNRC 2273 Boot Hill Ct, STE 110 Bozeman, MT 59715

November 14, 2025 Barnard Construction, Inc. 3520 Royal Wolf Way Bozeman, MT 59718

Subject: Correct and Complete Application for Beneficial Water Use Permit No. 41H 30165312

**Dear Applicant:** 

The Department of Natural Resources and Conservation (Department) has determined that your application is correct and complete pursuant to ARM 36.12.1601. Please remember that correct and complete <u>does not</u> <u>mean that your application will be granted.</u> The purpose of this letter is to indicate that the Department has enough information to analyze your water right application.

The Department will issue a Draft Preliminary Determination within 60 days of the date of this letter per §85-2-307(2)(b), MCA.

Following issuance of the Draft Preliminary Determination, you (Applicant) will have 15 business days to request an extension of time to submit additional information, if desired pursuant to §85-2-307(3)(a), MCA.

If no extension of time is requested and the Draft Preliminary Determination decision is to grant your application or grant your application in modified form, the Department will prepare a notice of opportunity to provide public comment, per §85-2-307(4)(a), MCA.

If no extension of time is requested and the Draft Preliminary Determination decision is to deny your application, the Department will adopt the Draft Preliminary Determination as the final determination per §85-2-307(3)(d)(ii), MCA.

If you have any questions or concerns about the application process, please contact me.

Sincerely,

Kendrew Ellis

Water Resources Specialist

**Bozeman Water Resources Office** 

Water Resources Division

CC, via email: Pat Thomson, pthomson@waterenvtech.com





#### Outlook

#### [EXTERNAL] RE: Correct and Complete Permit Application 41H 301165312

From Pat Thomson <pthomson@waterenvtech.com>

Date Fri 11/14/2025 10:17 AM

To Ellis, Kendrew < Kendrew. Ellis@mt.gov>

Cc Strasheim, Kerri <kstrasheim@mt.gov>; Reynolds, Lyra <Lyra.Reynolds@mt.gov>; Rasmussen, Derek <Derek.Rasmussen@mt.gov>

#### Thank you Kindrew. Have a great weekend.

From: Ellis, Kendrew < Kendrew. Ellis@mt.gov> Sent: Friday, November 14, 2025 10:07 AM

To: Pat Thomson <pthomson@waterenvtech.com>

Cc: Strasheim, Kerri <kstrasheim@mt.gov>; Reynolds, Lyra <Lyra.Reynolds@mt.gov>; Rasmussen, Derek

<Derek.Rasmussen@mt.gov>

Subject: Correct and Complete Permit Application 41H 301165312

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

#### Hi Pat-

The Department of Natural Resources and Conservation (Department) has determined that Permit Application No. 41H 30165312 is correct and complete pursuant to ARM 36.12.1601. The Department will issue a Draft Preliminary Determination within 60 days of the date of this letter, by 1/13/2026, per §85-2-307(2)(b), MCA. The correct and complete letter is attached to this email and was sent to the Applicant today, 11/14/25.

Please let me know if you have any guestions.

Best, Kendrew



Kendrew Ellis (she/her) | Water Resource Specialist

Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation

2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

DESK: 406-556-4538 EMAIL: kendrew.ellis@mt.gov

Website | Facebook [facebook.com] [facebook.com] [twitter.com]X [twitter.com](T [twitter.com]witter [twitter.com]) | Instagram [instagram.com]

How did we do? Let us know here: <u>[forms.office.com]Feedback Survey</u> [forms.office.com]

# **Application Materials**

- Application
- Any information submitted with Application including maps

# Application Materials



# APPLICATION FOR BENEFICIAL WATER USE PERMIT

§ 85-2-302, MCA

Form No. 600 (02/2025)

#### **FILING FEE**

\$2900/\$1600 – Inside a Basin Closure Area, Controlled Groundwater Area or Compact Closure; without/with filing fee reduction.

\$2500/\$1200 – Outside a Basin Closure Area; Controlled Groundwater Area or Compact Closure; without/with filing fee reduction.

#### **INFORMATION**

An application will be eligible for a filing fee reduction and expedited timelines if the applicant completes a preapplication meeting with the Department (ARM 36.12.1302(1)), which includes submitting any follow-up information identified by the Department (ARM 36.12.1302(3)(c)) and receiving either Department-completed technical analyses or Department review of applicant-submitted technical analyses (ARM 36.12.1302(4) and (5)). An application for the proposed project also must be submitted within 180 days of delivery of Department technical analyses or scientific credibility review and no element on the submitted application can be changed from the completed preapplication meeting form (ARM 36.12.1302(6)). If application is eligible for a filing fee reduction, \$500 paid for Form 600P-B will be credited toward filing fees shown above.

#### For Department Use Only

Application #	Basin	
Priority Date	Time	AM/PM
Rec'd By		
Fee Rec'd \$	Check #	
Deposit Receipt#		
Payor		
Refund \$	Date	

1

Applicant information: Add		•			
Applicant Name					
Mailing Address		City		State	Zip
Phone Numbers: Home					
Email Address					
Applicant Name					
Mailing Address		City		State	Zip
Phone Numbers: Home		Work		Cell	
Email Address					
Applicant Name					
Mailing Address		City		State	Zip
Phone Numbers: Home		Work		Cell	
Email Address					
Contact/Representative Inf	ormation: <i>Ad</i>	d more as nece	essary.		
Contact/Representative is:	Applicant	Consultant	Attorney	Other	
Contact/Representative Nam			j		
Mailing Address			/	State	Zip
Phone Numbers: Home		Work	·	<u> </u>	·
Email Address					

**NOTE:** If a contact person is identified as an attorney, all communication will be sent only to the attorney unless the attorney provides written instruction to the contrary (ARM 36.12.122(2)). If a contact person is identified as a consultant, employee, or lessee, the individual filing the water right form or objection form will receive all correspondences, and a copy may be sent to the contact person (ARM 36.12.122(3)).



Form 600

Answer every question and applicable follow-up questions. Use the checkboxes to denote yes ("Y"), no ("N"), or not applicable ("NA"). Questions that require items to be submitted to the Department have a submitted ("S") checkbox, which is marked when the required item is attached to the Application. Label all submitted items with the question number for which they were submitted. Narrative responses that are larger than the space provided can be answered in an attachment. If an attachment is used, specify "see attachment" on this form, and label the attachment with the question number. Constrain narrative responses to the specific question as is asked on the form; do not respond to multiple questions in one narrative. Responses in the form of a table may be entered into the table provided on this form or in an attachment. If an attachment is used, the table must have the exact headings found on this form, and "see attachment" must be entered as a response to the relevant question. Clearly label all units in tables and narrative responses.

#### PREAPPLICATION AND TECHNICAL ANALYSES INFORMATION

1. □ Y □ N	Do you elect for Department technical analyses to be used for criteria assessment?
	Did you have a preapplication meeting AND complete a Permit Preapplication Meeting Form Part B (Form 600P-A and 600P-B)?
IF QUE	ESTION 2 IS NO, answer 2.a and 2.b:
2.a. □ S	Submit the Technical Analyses Addendum (Form 600-TAA).
	NA Submit the technical analyses, if you elected in question 1 for Applicant technical es to be used for criteria assessment. Select "NA" if you elected for Departmental technical es.
IF QUE	ESTION 2 IS YES, answer 2.c, 2.d, and 2.e:
	N Has any element of the project described in this application changed from the story elements of the project described in the completed form 600P? If yes: Please explain.
2.c.ii. [	□ <b>S</b> Submit the Technical Analyses Addendum (Form 600-TAA).
comple	<b>N</b> Are the technical analyses to be used for criteria assessment exactly the same as those eted during the preapplication process? <b>If no:</b> Please explain.
2.d.ii. l	□ S Submit the Technical Analyses Addendum (Form 600-TAA).
	N Did you elect in Question 1 for Department technical analyses to be used for criteria sment? If no:



**2.e.i.** □ **S** Submit the technical analyses.

#### **APPLICATION ADDENDA AND REVIEW**

3. ☐ S ☐ NA If your application is for groundwater, not surface water, and one or more of your points of diversion are in a Basin Closure Area, then submit the Basin Closure Area Addendum (Form 600-BC/	
<ul> <li>4. □ S □ NA If your application is for groundwater and one or more points of diversion are in a Basin Closure Area, then your project must have a Hydrogeologic Report that conforms with MCA 85-2-361 to comply with the requirements of § 85-2-360, MCA. A Hydrogeologic Report Addendum (Form 600-HRA) or Department Technical Analyses may be used to meet these requirements. Please mark the box below that best applies, then select "S" if submitting a Hydrogeologic Report or "NA" if one is not required. This question does not apply to surface water points of diversion in a Basin Closure Area.</li> <li>□ If you elected to conduct Technical Analyses, you must submit the Hydrogeologic Report Addendum (Form 600-HRA).</li> <li>□ If you elected for DNRC to conduct Technical Analyses but did not have a preapplication meeting the submit the Hydrogeologic Report Addendum (Form 600-HRA).</li> </ul>	•
AND complete a Form 600P Permit Preapplication Meeting Form (or changes have occurred since the completed Form 600P), you must submit the Hydrogeologic Report Addendum (Form 600-HRA).	
☐ If you elected for DNRC to conduct Technical Analyses, had a preapplication meeting, complete a Form 600P, and the Technical Analyses remain unchanged since the preapplication meeting, you do not need to submit Form 600-HRA because the Department's Technical Analyses meet the report requirements of § 85-2-360 and § 85-2-361, MCA.	,
<b>5.</b> □ <b>S</b> □ <b>NA</b> If the project is for one or more groundwater points of diversion located in a Controlled Groundwater Area, then submit the Controlled Groundwater Area Addendum (Form 600-CGWA).	
6. ☐ S ☐ NA If the project involves an appropriation that is greater than 5.5 CFS and 4,000 acre-feet, then submit a Criteria Addendum Application for Beneficial Water Use Permit for Appropriations Great than 5.5 CFS and 4,000 AC-FT (Form 600-B).	
7. ☐ S ☐ NA If the project involves out-of-state water use, then submit the Out-of-State Use Addendur (Form 600/606-OSA).	m
8. ☐ S ☐ NA If you require mitigation water to meet the criteria of issuance, then submit a Mitigation Purpose Addendum (Form 600/606-MIT).	
9. ☐ S ☐ NA If the proposed purposes include marketing or selling water, (not marketing for mitigation aquifer recharge), then submit the Marketing Purpose Addendum (Form 600/606-WMA).	1/
<b>10.</b> □ <b>S</b> □ <b>NA</b> If the project involves one or more places of storage, then submit a Permit Storage Addendum (Form 600-SA). This does not include reservoirs, pits, pit-dams, or ponds with a capacity less than 0.1 AF; water tanks; or cisterns (ARM 36.12.113(6)).	
<b>11.</b> □ <b>S</b> □ <b>NA</b> If the project is in designated sage grouse habitat, then submit a review letter from the Montana Sage Grouse Habitat Conservation Program.	
<b>12.</b> □ <b>S</b> □ <b>NA</b> If the project includes a point of diversion and/or place of use on State of Montana Trust Land, submit documentation of consent from the DNRC Trust Lands Management Division.	ŧ
<b>13.</b> □ <b>S</b> □ <b>NA</b> You must provide a written notice of the application to each owner of an appropriation risharing a point of diversion or means of conveyance (e.g., canal, ditch, flume, pipeline, or constructed	

waterway) pursuant to §85-2-302(4)(c), MCA. Submit a copy of this notice and the recipient list.



#### **PURPOSE AND DIVERSION INFORMATION**

		e proposed use tern will the appropria	. ,	?				
•		source surface wat						
16. What is the			· ·					
corners; to unique Poi use; all pro unique Sto map may b 18. Fill out the	wnshi int of I opose orage oe sub table	map utilizing an ae p and range; north Diversion (POD) ID d conveyance facili ID number; and play mitted, if necessary below. Means of d f diversion for grou	arrow; sca number ar ities and or ices of use by to clearly iversion for	le bar; all pr nd, if applica routes; all p (POU) for a convey all r surface wat	opos ble, ( ropo ll ove equi	sed points of diver GWIC number; all sed places of sto erlapping water rig red information.	rsion labeled will proposed pla rage labeled wights. More that pump, dam, a	vith a ces of vith a n one
				·				
Purpose		Means of Diversion	Acres Irrigated (if appl.)	Period o Diversio (Month/Da Month/Da	n <i>y -</i>	Period of Use (Month/Day - Month/Day)	Flow Rate ☐ GPM ☐ CFS	Volume (Acre- Feet)
			To	tal Flow Pata	and '	Volume Required		
						·		
19. ☐ Y ☐ N domestic,		s the proposed use or irrigation? If yes						ultiple
Purpose		uested Informatio	n		Res	sponse		
Domestic or multiple domestic	Num	ber of dwellings						
Stock	Num	ber of animal units	<u> </u>					
Irrigation	Meth and bord	nod of irrigation typ subtype (if flood: le er, furrow, contour nkler: center pivot, v	e (sprinkler evel border, ditch, or otl	graded <sup>′</sup> her; if				
Irrigation (flood only)		gn slope	,	,				

#### **POINT(S) OF DIVERSION**

**20.** Describe the proposed location of the point(s) diversion to the nearest 1/4 1/4 1/4 Section. Label each POD with the POD ID number used for the project map (question 17).

POD #	1/4	1/4	1/4	Sec.	Twp.	Rge.	County	Lot	Block	Tract	Subdivision	Gov. Lot

#### **PLACE OF USE**

21. What are the geocodes of the place of use?

**22.** Describe the legal land description for the proposed place of use and, if applying for an irrigation or lawn and garden purpose, list the number of irrigated acres.

Acres	Gov. Lot	Block	1/4	1/4	1/4	Sec.	Twp.	Rge.	County

#### **SUPPLEMENTAL AND OVERLAPPING WATER RIGHTS**

•	ourpose(s).	lemental and proposed v	vater rights will l	pe operated as a whole
	use (MM/DD-MM/DD),	g water right, please list t flow rate (GPM or CFS),		
Water Right #	Average Period of Diversion	Average Period of Use	Flow Rate	Volume Contribute
. □ Y □ N W other source?		ement contract water from	m a Federal Pro	oject, ditch company, o
other source?		ement contract water from	m a Federal Pro	oject, ditch company, o
other source?		ement contract water from	m a Federal Pro	oject, ditch company, o
other source?		ement contract water from	m a Federal Pro	oject, ditch company, o
other source?  25.a. If yes, ex	kplain.	ement contract water from	m a Federal Pro	pject, ditch company, o
other source?  25.a. If yes, ex	kplain.	ement contract water from	m a Federal Pro	pject, ditch company, o
other source?  25.a. If yes, ex	cplain.	ement contract water from		pject, ditch company, o
other source?  25.a. If yes, ex	cplain.			pject, ditch company, o
other source?  25.a. If yes, ex	cplain.			pject, ditch company, o



Describe any plans you have for ensuring existing water rights will be satisfied during times of water shortage.
□ Y □ N Are you aware of any calls that have been made on the source of supply or, if groundwate on nearby surface water sources?  28.a. If yes, explain
<ul> <li>☐ Y ☐ N Does a water commissioner distribute water or oversee water distribution on your propose source?</li> <li>29.a. If yes, list the source(s).</li> </ul>
□ Y □ N Do other water rights share any of the proposed points of diversion?  30.a. If yes, describe how the proposed project will not adversely affect these water rights.
□ Y □ N Do other water rights share any conveyance infrastructure associated with the proposed project?  31.a. If yes, describe how the proposed project will not adversely affect these water rights.

#### **ADEQUATE MEANS OF DIVERSION AND OPERATION**

32.	□ S Submit a diagram of how you will operate your system from all proposed points of diversion to all proposed places of use.  Diagrams include both distribution lines from wells to building and building to injection wells, and mechanical for heat exchange components (see attached)
33.	Describe specific information about the capacity of all proposed diversionary structures. This may include, where applicable: pump curves and total dynamic head calculations, headgate design specifications, and dike or dam height and length.
34.	Describe the size, materials, capacity, and configuration of infrastructure to convey water from all proposed points of diversion to all proposed places of use. This may include but is not limited to, pipelines and ditches. Include a description of any losses related to the proposed conveyance. Ditch conveyance losses may be estimated numerous ways, which include a ditch loss rate or Department standard methods.
35.	Describe how the proposed diversion and conveyance infrastructure can provide the required flow and volume, for the purposes plus any conveyance losses and storage, throughout the proposed period of diversion.

	ovide a plan of operations, which includes specific information about how water is delivered within the ace of use. This may include, where applicable, the range of flow rates needed for a pivot.
	Y □ N Does the proposed conveyance require easements?  .a. If yes, explain.
	Y □ N Do you own the land where all proposed points of diversion are located?  a. □ S If no, submit documentation to show you have the right to use all points of diversion located on each property you do not own. This may include, but is not limited to, a well agreement, an easement, or permission of the party that owns the property where the proposed point(s) of diversion are located.
9. □	Y □ N Will your system be designed to discharge water from the project?
39	IF YES,  .a. Explain the wastewater disposal method.
39	.b. □ Y □ N □ NA Have the necessary permits been obtained to comply with §§ 75-5-410 and 85 2-364, MCA?
0. □	Y □ N Do you have any plans to measure your diversion and use?
40	.a. If yes, describe the plan and the type of measurements you will take.

<b>41.</b> □ <b>Y</b> □ <b>N</b> Is th	e means of diversion for any proposed point of diversion a well?
IF YES,	
41.a. □ Y □ N	Have all wells been drilled?
<b>41.b.</b> For all well their license	s that have been drilled, what is the name of the well driller and, if available, what is number?
41.c. □ Y □ N	For all wells yet to be drilled, will a licensed well driller construct the wells?
41.d. □ S □ NA	Submit any well logs not yet submitted to the Department.
BENEFICIAL USE	
purposes for whi	s the Department have a volume, period of diversion, or period of use standard for the ch water is proposed? Department standards can be found in the DNRC Water e, ARM 36.12.112, and ARM 36.12.115.
42.a. □ Y □ N	If yes, do all proposed beneficial uses fall within Department standards?
	rtment standard exists, or if any proposed beneficial use falls outside of Department explain how the requested flow rate and volume are reasonable for the purpose.
<del></del>	
	<del>-</del>
<del></del>	
	<del></del>
	your proposed project be subject to DEQ requirements for a public water supply (PWS) cate of Subdivision Approval (COSA)?
44.a. □ Y □ N 44.a.i. □ S □	you proposing to use surface water for in-house domestic use?  If yes, does a COSA exist for the proposed place of use?  NA If yes, please submit the COSA.  N If no, have you researched or consulted with DEQ regarding their requirements?



#### **POSSESSORY INTEREST**

	□ Y □ N Do you meet one of the exceptions to possessory interest requirements, pursuant to ARM 36.12.1802? Exceptions include cases where the application is for sale, rental, distribution, or is a municipal use, or in any other context in which water is being supplied to another and it is clear that the ultimate user will not accept the supply without consenting to the use of water on the user's place of use.
	<b>45.a.</b> If yes, explain.
	☐ Y ☐ N ☐ NA Do you own all proposed places of use? Mark "NA" if you meet one of the exceptions to the possessory interest requirement.
	IF NO,
	<b>46.a.</b> □ <b>S</b> Explain and submit documentation that shows you either have possessory interest or written permission of the parties with possessory interest of the place of use.
	<b>46.b.</b> □ <b>Y</b> □ <b>N</b> Would you like the water right to be appurtenant to the land? Please note that if your water right is not appurtenant to land it will not transfer by default with the conveyance of the property, pursuant to § 85-2-403, MCA.
	46.b.i. If no, explain.
PRC	POSED COMPLETION PERIOD
	How much time will be needed to complete this project and to submit to the DNRC a Project Completion Notice (Form 617)?
48.	Please describe why this amount of time is needed to complete this project.
,	



#### **AFFIDAVIT & CERTIFICATION**

Read carefully before you sign and review with legal counsel if you have any questions. All owners (or trustees) must sign the form. \*\*If the owner is a business or trust, include the title of the representative(s) signing the form (i.e., president, trustee, managing partner, etc.) and provide documentation that establishes the authority of the representative to sign the application.

I affirm the information provided for this application is to the best of my knowledge true and correct. If a preapplication meeting form was submitted, I am aware that my application for this project will not qualify for a discounted filing fee and expedited timelines if upon submittal of the application to the Department, I changed any element of the proposed application from the preapplication meeting form and follow-up materials (ARM 36.12.1302(6)(a)).


I affirm I have possessory interest, or the written consent of the person with the possessory interest, in the property where the water is to be put to beneficial use, unless this application meets an exception to the possessory interest requirements in ARM 36.12.1802(1)(b).

I understand that making a false statement under oath or affirmation in this application and official proceedings throughout the examination of my application may subject me to prosecution under § 45-7-202, MCA, a misdemeanor punishable by a jail term not to exceed 6 months or a fine not to exceed \$500, or both. I have read this Affidavit and understand the terms and conditions.

I declare under penalty of perjury and under the laws of the state of Montana that the foregoing is true and correct.

Printed Name		
Applicant Signature	Date:	
Printed Name		
Applicant Signature	Date:	
Printed Name		
Applicant Signature	Date:	

#### WATER RESOURCES REGIONAL OFFICES





Airport Industrial Park, 1371 Rimtop Dr Billings, MT 59105-9702

PHONE 406-247-4415 FAX 406-247-4416 EMAIL DNRCBillingsWater@mt.gov

Big Horn, Carbon, Carter, Custer, Fallon, Powder River, Prairie, Rosebud, Stillwater, Sweet Grass, Treasure, and Yellowstone Counties



#### **BOZEMAN**

2273 Boot Hill Court, Suite 110 Bozeman, MT 59715-7249

PHONE 406-586-3136 FAX 406-587-9726 EMAIL DNRCBozemanWater@mt.gov

Gallatin, Madison, and Park Counties



#### **GLASGOW**

222 6th Street South, PO Box 1269 Glasgow, MT 59230-1269

PHONE 406-228-2561

EMAIL DNRCGlasgowWater@mt.gov

Daniels, Dawson, Garfield, McCone, Phillips, Richland, Roosevelt, Sheridan, Valley, and Wibaux Counties



#### **HAVRE**

210 6th Ave., PO Box 1828 Havre, MT 59501-1828

PHONE 406-265-5516

EMAIL DNRCHavreWater@mt.gov

Blaine, Chouteau, Glacier, Hill, Liberty, Pondera, Teton, and Toole Counties



#### **HELENA**

1424 9th Ave., PO Box 201601, Helena, MT 59620-1601

PHONE 406-444-6999 FAX 406-444-9317 EMAIL DNRCHelenaWater@mt.gov

Beaverhead, Broadwater, Deer Lodge, Jefferson, Lewis and Clark, Powell, and Silver Bow Counties



#### **KALISPELL**

655 Timberwolf Parkway, Suite 4 Kalispell, MT 59901-1215

PHONE 406-752-2288

EMAIL DNRCKalispellWater@mt.gov

Flathead, Lake, Lincoln, and Sanders Counties



#### **LEWISTOWN**

613 Northeast Main St., Suite E Lewistown, MT 59457-2020

PHONE 406-538-7459

EMAIL DNRCLewistownWater@mt.gov

Cascade, Fergus, Golden Valley, Judith Basin, Meagher, Musselshell, Petroleum, and Wheatland Counties



#### **MISSOULA**

2705 Spurgin Rd. Bldg. C, PO Box 5004 Missoula, MT 59806-5004

PHONE 406-721-4284 FAX 406-542-5899 EMAIL DNRCMissoulaWater@mt.gov

Granite, Mineral, Missoula, and Ravalli Counties



#### THE MONTANA DEPARTMENT OF NATURAL RESOURCES AND CONSERVATION

**GOVERNOR GREG GIANFORTE** 



DNRC DIRECTOR AMANDA KASTER

DNRC 2273 Boot Hill Ct, STE 110 Bozeman, MT 59715 406-556-4500

October 14, 2025

Barnard Construction, Inc. 3520 Royal Wolf Way Bozeman, MT 59718

Subject: Deficiency Letter for Beneficial Water Use Permit Application No. 41H 30165312

#### Dear Applicant:

The Department of Natural Resources and Conservation (DNRC or Department) has begun reviewing your application. This letter is to notify you of the deficiencies in your application as required in ARM 36.12.1501(1) and §85-2-302(5)(b), MCA. An Applicant is required to submit substantial and credible information addressing the rules and statutes that are relative to your application. You must provide the information specified below for your application to be considered correct and complete. "Correct and complete" means all of the information provided is substantial and credible and provides all of the information as required by applicable rules and statutes. The application as submitted contains deficiencies in the following section(s):

#### **APPLICATION DETAILS – ARM 36.12.1304**

- □ 2.b. Submit the technical analyses, if you elected in question 1 for Applicant technical analyses to be used for criteria assessment. Select "NA" if you elected for Departmental technical analyses.
  - Applicant elected for Department technical analysis. Please clarify the answer.
- 2.c. Has any element of the project described in this application changed from the mandatory elements of the project described in the completed form 600P?
  - Question not answered. Please answer the question.
- □ 2.d. Are the technical analyses to be used for criteria assessment exactly the same as those completed during the preapplication process?
  - Question not answered. Please answer the question.
- ☐ 2.e. Did you elect in Question 1 for Department technical analyses to be used for criteria assessment?
  - Question not answered. Please answer the question.



- □ 20. Describe the proposed location of the point(s) diversion to the nearest ¼ ¼ ¼ Section. Label each POD with the POD ID number used for the project map (question 17).
  - o Information in the Table shows the legal land descriptions for the injection wells. Please update the table for the extraction well legal land descriptions.
- 22. Describe the legal land description for the proposed place of use and, if applying for an irrigation or lawn and garden purpose, list the number of irrigated acres.
  - The information submitted does not include all POUs that are also listed on the Preapplication Meeting Form (600P). Please update the table to include all of the legal land descriptions of the proposed place of use.

#### BENEFICIAL USE- ARM 36.12.1801

- □ 42. Does the Department have a volume, period of diversion, or period of use standard for the purposes for which water is proposed? Department standards can be found in the DNRC Water Calculation Guide, ARM 36.12.112, and ARM 36.12.115.
  - O The Department does not have a volume, period of diversion, or period of use standard for the Geothermal purpose proposed. Please update the question and explain how the requested flow rate and volume are reasonable for the purpose.

As stated above, the information submitted to address the rules and statutes listed in this deficiency letter must be substantial credible information to be acceptable at the correct and complete determination. §§85-2-102(9) and (26), MCA.

Please submit the information specified above to the Bozeman Regional Office by February 11, 2026. <u>This is the only deficiency letter that will be sent</u>. An application not corrected or completed within 120 days from the date of this letter is terminated per ARM 36.12.1501(2) and §85-2-302(6)(a), MCA.

Please let me know if you have any questions.

Best,

Kendrew Ellis

Water Resources Specialist

Lendrew XE in

Bozeman Water Resources Office

Water Resources Division

Cc, via email: Pat Thomson, pthomson@waterenvtech.com





Form No. 600 (02/2025)

#### **FILING FEE**

\$2900/\$1600 – Inside a Basin Closure Area, Controlled Groundwater Area or Compact Closure; without/with filing fee reduction.

\$2500/\$1200 – Outside a Basin Closure Area; Controlled Groundwater Area or Compact Closure; without/with filing fee reduction.

#### **INFORMATION**

An application will be eligible for a filing fee reduction and expedited timelines if the applicant completes a preapplication meeting with the Department (ARM 36.12.1302(1)), which includes submitting any follow-up information identified by the Department (ARM 36.12.1302(3)(c)) and receiving either Department-completed technical analyses or Department review of applicant-submitted technical analyses (ARM 36.12.1302(4) and (5)). An application for the proposed project also must be submitted within 180 days of delivery of Department technical analyses or scientific credibility review and no element on the submitted application can be changed from the completed preapplication meeting form (ARM 36.12.1302(6)). If application is eligible for a filing fee reduction, \$500 paid for Form 600P-B will be credited toward filing fees shown above.

For Department Use Only

#### **RECEIVED**

#### **SEP 23 2025**

#### **DNRC**

#### **BOZEMAN WATER RESOURCES**

Application #	_ Basin	
Priority Date	Time	_ AM/PM
Rec'd By		
Fee Rec'd \$	Check #	
Deposit Receipt#		
Payor		
Refund \$	_ Date	

Applicant Information: Add more as ne				
Applicant Name				
Mailing Address	City_		State	Zip
Phone Numbers: Home	Work			
Email Address				
Applicant Name				
Mailing Address			State	Zip
Phone Numbers: Home				
Email Address				
Applicant Name				
Mailing Address	City		State	Zip
Phone Numbers: Home	Work		Cell	
Email Address				
Contact/Representative Information: A	dd more as neces	ssary.		
Contact/Representative is: Applicant	Consultant	Attorney	Other	
Contact/Representative Name		•		
Mailing Address			State	Zip
Phone Numbers: Home			 Cell	
Email Address				

**NOTE:** If a contact person is identified as an attorney, all communication will be sent only to the attorney unless the attorney provides written instruction to the contrary (ARM 36.12.122(2)). If a contact person is identified as a consultant, employee, or lessee, the individual filing the water right form or objection form will receive all correspondences, and a copy may be sent to the contact person (ARM 36.12.122(3)).



Form 600

Answer every question and applicable follow-up questions. Use the checkboxes to denote yes ("Y"), no ("N"), or not applicable ("NA"). Questions that require items to be submitted to the Department have a submitted ("S") checkbox, which is marked when the required item is attached to the Application. Label all submitted items with the question number for which they were submitted. Narrative responses that are larger than the space provided can be answered in an attachment. If an attachment is used, specify "see attachment" on this form, and label the attachment with the question number. Constrain narrative responses to the specific question as is asked on the form; do not respond to multiple questions in one narrative. Responses in the form of a table may be entered into the table provided on this form or in an attachment. If an attachment is used, the table must have the exact headings found on this form, and "see attachment" must be entered as a response to the relevant question. Clearly label all units in tables and narrative responses.

#### PREAPPLICATION AND TECHNICAL ANALYSES INFORMATION

1. □ Y □ N	Do you elect for Department technical analyses to be used for criteria assessment?
	Did you have a preapplication meeting AND complete a Permit Preapplication Meeting Form Part B (Form 600P-A and 600P-B)?
IF QUE	ESTION 2 IS NO, answer 2.a and 2.b:
2.a. □ S	Submit the Technical Analyses Addendum (Form 600-TAA).
	NA Submit the technical analyses, if you elected in question 1 for Applicant technical es to be used for criteria assessment. Select "NA" if you elected for Departmental technical es.
IF QUE	ESTION 2 IS YES, answer 2.c, 2.d, and 2.e:
	N Has any element of the project described in this application changed from the story elements of the project described in the completed form 600P? If yes: Please explain.
2.c.ii. [	□ <b>S</b> Submit the Technical Analyses Addendum (Form 600-TAA).
comple	<b>N</b> Are the technical analyses to be used for criteria assessment exactly the same as those eted during the preapplication process? <b>If no:</b> Please explain.
2.d.ii. l	□ S Submit the Technical Analyses Addendum (Form 600-TAA).
	N Did you elect in Question 1 for Department technical analyses to be used for criteria sment? If no:



**2.e.i.** □ **S** Submit the technical analyses.

#### **APPLICATION ADDENDA AND REVIEW**

3. ☐ S ☐ NA If your application is for groundwater, not surface water, and one or more of your points of diversion are in a Basin Closure Area, then submit the Basin Closure Area Addendum (Form 600-BC/	
<ul> <li>4. □ S □ NA If your application is for groundwater and one or more points of diversion are in a Basin Closure Area, then your project must have a Hydrogeologic Report that conforms with MCA 85-2-361 to comply with the requirements of § 85-2-360, MCA. A Hydrogeologic Report Addendum (Form 600-HRA) or Department Technical Analyses may be used to meet these requirements. Please mark the box below that best applies, then select "S" if submitting a Hydrogeologic Report or "NA" if one is not required. This question does not apply to surface water points of diversion in a Basin Closure Area.</li> <li>□ If you elected to conduct Technical Analyses, you must submit the Hydrogeologic Report Addendum (Form 600-HRA).</li> <li>□ If you elected for DNRC to conduct Technical Analyses but did not have a preapplication meeting the submit the Hydrogeologic Report Addendum (Form 600-HRA).</li> </ul>	•
AND complete a Form 600P Permit Preapplication Meeting Form (or changes have occurred since the completed Form 600P), you must submit the Hydrogeologic Report Addendum (Form 600-HRA).	
☐ If you elected for DNRC to conduct Technical Analyses, had a preapplication meeting, complete a Form 600P, and the Technical Analyses remain unchanged since the preapplication meeting, you do not need to submit Form 600-HRA because the Department's Technical Analyses meet the report requirements of § 85-2-360 and § 85-2-361, MCA.	,
<b>5.</b> □ <b>S</b> □ <b>NA</b> If the project is for one or more groundwater points of diversion located in a Controlled Groundwater Area, then submit the Controlled Groundwater Area Addendum (Form 600-CGWA).	
6. ☐ S ☐ NA If the project involves an appropriation that is greater than 5.5 CFS and 4,000 acre-feet, then submit a Criteria Addendum Application for Beneficial Water Use Permit for Appropriations Great than 5.5 CFS and 4,000 AC-FT (Form 600-B).	
7. ☐ S ☐ NA If the project involves out-of-state water use, then submit the Out-of-State Use Addendur (Form 600/606-OSA).	m
8. ☐ S ☐ NA If you require mitigation water to meet the criteria of issuance, then submit a Mitigation Purpose Addendum (Form 600/606-MIT).	
9. ☐ S ☐ NA If the proposed purposes include marketing or selling water, (not marketing for mitigation aquifer recharge), then submit the Marketing Purpose Addendum (Form 600/606-WMA).	1/
<b>10.</b> □ <b>S</b> □ <b>NA</b> If the project involves one or more places of storage, then submit a Permit Storage Addendum (Form 600-SA). This does not include reservoirs, pits, pit-dams, or ponds with a capacity less than 0.1 AF; water tanks; or cisterns (ARM 36.12.113(6)).	
<b>11.</b> □ <b>S</b> □ <b>NA</b> If the project is in designated sage grouse habitat, then submit a review letter from the Montana Sage Grouse Habitat Conservation Program.	
<b>12.</b> □ <b>S</b> □ <b>NA</b> If the project includes a point of diversion and/or place of use on State of Montana Trust Land, submit documentation of consent from the DNRC Trust Lands Management Division.	ŧ
<b>13.</b> □ <b>S</b> □ <b>NA</b> You must provide a written notice of the application to each owner of an appropriation risharing a point of diversion or means of conveyance (e.g., canal, ditch, flume, pipeline, or constructed	

waterway) pursuant to §85-2-302(4)(c), MCA. Submit a copy of this notice and the recipient list.



#### **PURPOSE AND DIVERSION INFORMATION**

		e proposed use tern will the appropria	. ,	?				
•		source surface wat						
16. What is the			· ·					
corners; to unique Poi use; all pro unique Sto map may b 18. Fill out the	wnshi int of I opose orage oe sub table	map utilizing an ae p and range; north Diversion (POD) ID d conveyance facili ID number; and play mitted, if necessary below. Means of d f diversion for grou	arrow; sca number ar ities and or ices of use by to clearly iversion for	le bar; all pr nd, if applica routes; all p (POU) for a convey all r surface wat	opos ble, ( ropo ll ove equi	sed points of diver GWIC number; all sed places of sto erlapping water rig red information.	rsion labeled will proposed pla rage labeled wights. More that pump, dam, a	vith a ces of vith a n one
				·				
Purpose		Means of Diversion	Acres Irrigated (if appl.)	Period o Diversio (Month/Da Month/Da	n <i>y -</i>	Period of Use (Month/Day - Month/Day)	Flow Rate ☐ GPM ☐ CFS	Volume (Acre- Feet)
			To	tal Flow Pata	and '	Volume Required		
						·		
19. ☐ Y ☐ N domestic,		s the proposed use or irrigation? If yes						ultiple
Purpose		uested Informatio	n		Res	sponse		
Domestic or multiple domestic	Num	ber of dwellings						
Stock	Num	ber of animal units	<u> </u>					
Irrigation	Meth and bord	nod of irrigation typ subtype (if flood: le er, furrow, contour nkler: center pivot, v	e (sprinkler evel border, ditch, or otl	graded <sup>′</sup> her; if				
Irrigation (flood only)		gn slope	,	,				

#### **POINT(S) OF DIVERSION**

**20.** Describe the proposed location of the point(s) diversion to the nearest 1/4 1/4 1/4 Section. Label each POD with the POD ID number used for the project map (question 17).

POD #	1/4	1/4	1/4	Sec.	Twp.	Rge.	County	Lot	Block	Tract	Subdivision	Gov. Lot

#### **PLACE OF USE**

21. What are the geocodes of the place of use?

**22.** Describe the legal land description for the proposed place of use and, if applying for an irrigation or lawn and garden purpose, list the number of irrigated acres.

Acres	Gov. Lot	Block	1/4	1/4	1/4	Sec.	Twp.	Rge.	County

#### **SUPPLEMENTAL AND OVERLAPPING WATER RIGHTS**

•	ummarize how the supp ourpose(s).	lemental and proposed v	vater rights will	be operated as a whole
	use (MM/DD-MM/DD),	g water right, please list t flow rate (GPM or CFS),		
Vater Right #	Average Period of Diversion	Average Period of Use	Flow Rate	Volume Contribute
. □ Y □ N W other source?		ement contract water fro	m a Federal Pro	oject, ditch company, o
other source?		ement contract water fro	m a Federal Pro	oject, ditch company, o
other source?		ement contract water fro	m a Federal Pro	oject, ditch company, o
other source?		ement contract water fro	m a Federal Pro	oject, ditch company, o
other source?  25.a. If yes, ex	oplain.	ement contract water from	m a Federal Pro	oject, ditch company, o
other source?  25.a. If yes, ex	oplain.	ement contract water from	m a Federal Pro	oject, ditch company, o
other source?  25.a. If yes, ex	cplain.	ement contract water from		pject, ditch company, o
other source?  25.a. If yes, ex	cplain.			pject, ditch company, o
other source?  25.a. If yes, ex	cplain.			pject, ditch company, o



Describe any plans you have for ensuring existing water rights will be satisfied during times of water shortage.								
☐ Y ☐ N Are you aware of any calls that have been made on the source of supply or, if groundwaten nearby surface water sources?  8.a. If yes, explain.								
☐ Y ☐ N Does a water commissioner distribute water or oversee water distribution on your proposource?  19.a. If yes, list the source(s).								
☐ Y ☐ N Do other water rights share any of the proposed points of diversion?  ■ O.a. If yes, describe how the proposed project will not adversely affect these water rights.								
☐ Y ☐ N Do other water rights share any conveyance infrastructure associated with the proposed project?								
<b>1.a.</b> If yes, describe how the proposed project will not adversely affect these water rights.								

#### **ADEQUATE MEANS OF DIVERSION AND OPERATION**

32.	□ S Submit a diagram of how you will operate your system from all proposed points of diversion to all proposed places of use.  Diagrams include both distribution lines from wells to building and building to injection wells, and mechanical for heat exchange components (see attached)							
33.	Describe specific information about the capacity of all proposed diversionary structures. This may include, where applicable: pump curves and total dynamic head calculations, headgate design specifications, and dike or dam height and length.							
34.	Describe the size, materials, capacity, and configuration of infrastructure to convey water from all proposed points of diversion to all proposed places of use. This may include but is not limited to, pipelines and ditches. Include a description of any losses related to the proposed conveyance. Ditch conveyance losses may be estimated numerous ways, which include a ditch loss rate or Department standard methods.							
35.	Describe how the proposed diversion and conveyance infrastructure can provide the required flow and volume, for the purposes plus any conveyance losses and storage, throughout the proposed period of diversion.							

	ovide a plan of operations, which includes specific information about how water is delivered within the ace of use. This may include, where applicable, the range of flow rates needed for a pivot.
	Y □ N Does the proposed conveyance require easements? .a. If yes, explain.
	Y □ N Do you own the land where all proposed points of diversion are located?  a. □ S If no, submit documentation to show you have the right to use all points of diversion located on each property you do not own. This may include, but is not limited to, a well agreement, an easement, or permission of the party that owns the property where the proposed point(s) of diversion are located.
9. □	Y □ N Will your system be designed to discharge water from the project?
39	IF YES,  .a. Explain the wastewater disposal method.
39	.b. □ Y □ N □ NA Have the necessary permits been obtained to comply with §§ 75-5-410 and 85 2-364, MCA?
0. □	Y □ N Do you have any plans to measure your diversion and use?
40	.a. If yes, describe the plan and the type of measurements you will take.

<b>41.</b> □ <b>Y</b> □ <b>N</b> Is th	ne means of diversion for any proposed point of diversion a well?								
IF YES	,								
<ul> <li>41.a. □ Y □ N Have all wells been drilled?</li> <li>41.b. For all wells that have been drilled, what is the name of the well driller and, if available, what their license number?</li> <li>41.c. □ Y □ N For all wells yet to be drilled, will a licensed well driller construct the wells?</li> </ul>									
								41.d. □ S □ NA	Submit any well logs not yet submitted to the Department.
								BENEFICIAL USE	
purposes for wh	es the Department have a volume, period of diversion, or period of use standard for the ich water is proposed? Department standards can be found in the DNRC Water de, ARM 36.12.112, and ARM 36.12.115.								
42.a. □ Y □ N	If yes, do all proposed beneficial uses fall within Department standards?								
	rtment standard exists, or if any proposed beneficial use falls outside of Department xplain how the requested flow rate and volume are reasonable for the purpose.								
<del></del>									
	<del></del>								
	your proposed project be subject to DEQ requirements for a public water supply (PWS) icate of Subdivision Approval (COSA)?								
44.a. □ Y □ N 44.a.i. □ S [	you proposing to use surface water for in-house domestic use?  If yes, does a COSA exist for the proposed place of use?  ■ NA If yes, please submit the COSA.  ■ N If no, have you researched or consulted with DEQ regarding their requirements?								



#### **POSSESSORY INTEREST**

46.a. □ S written  46.b. □ Y I water ri propert	
to the poss  IF  46.a. □ S  written  ————  46.b. □ Y I  water ri propert	Explain and submit documentation that shows you either have possessory interest or
to the poss  IF  46.a. □ S  written  ————  46.b. □ Y I  water ri propert	Explain and submit documentation that shows you either have possessory interest or
46.a. □ S written  ——————————————————————————————————	Explain and submit documentation that shows you either have possessory interest or
written  46.b. □ Y I  water ri propert	•
water ri propert	
46.b.i.	□ <b>N</b> Would you like the water right to be appurtenant to the land? Please note that if your ight is not appurtenant to land it will not transfer by default with the conveyance of the ty, pursuant to § 85-2-403, MCA.
	If no, explain.
PROPOSED (	COMPLETION PERIOD
	time will be needed to complete this project and to submit to the DNRC a Project Completio
<b>48.</b> Please des	scribe why this amount of time is needed to complete this project.



#### **AFFIDAVIT & CERTIFICATION**

Read carefully before you sign and review with legal counsel if you have any questions. All owners (or trustees) must sign the form. \*\*If the owner is a business or trust, include the title of the representative(s) signing the form (i.e., president, trustee, managing partner, etc.) and provide documentation that establishes the authority of the representative to sign the application.

I affirm the information provided for this application is to the best of my knowledge true and correct. If a preapplication meeting form was submitted, I am aware that my application for this project will not qualify for a discounted filing fee and expedited timelines if upon submittal of the application to the Department, I changed any element of the proposed application from the preapplication meeting form and follow-up materials (ARM 36.12.1302(6)(a)).


I affirm I have possessory interest, or the written consent of the person with the possessory interest, in the property where the water is to be put to beneficial use, unless this application meets an exception to the possessory interest requirements in ARM 36.12.1802(1)(b).

I understand that making a false statement under oath or affirmation in this application and official proceedings throughout the examination of my application may subject me to prosecution under § 45-7-202, MCA, a misdemeanor punishable by a jail term not to exceed 6 months or a fine not to exceed \$500, or both. I have read this Affidavit and understand the terms and conditions.

I declare under penalty of perjury and under the laws of the state of Montana that the foregoing is true and correct.

Printed Name		
Applicant Signature	Date:	
Printed Name		
Applicant Signature	Date:	
Printed Name		
Applicant Signature	Date:	

#### WATER RESOURCES REGIONAL OFFICES





Airport Industrial Park, 1371 Rimtop Dr Billings, MT 59105-9702

PHONE 406-247-4415 FAX 406-247-4416 EMAIL <a href="mailto:DNRCBillingsWater@mt.gov">DNRCBillingsWater@mt.gov</a>

Big Horn, Carbon, Carter, Custer, Fallon, Powder River, Prairie, Rosebud, Stillwater, Sweet Grass, Treasure, and Yellowstone Counties



#### **BOZEMAN**

2273 Boot Hill Court, Suite 110 Bozeman, MT 59715-7249

PHONE 406-586-3136 FAX 406-587-9726 EMAIL DNRCBozemanWater@mt.gov

Gallatin, Madison, and Park Counties



#### **GLASGOW**

222 6th Street South, PO Box 1269 Glasgow, MT 59230-1269

PHONE 406-228-2561

EMAIL DNRCGlasgowWater@mt.gov

Daniels, Dawson, Garfield, McCone, Phillips, Richland, Roosevelt, Sheridan, Valley, and Wibaux Counties



#### **HAVRE**

210 6th Ave., PO Box 1828 Havre, MT 59501-1828

PHONE 406-265-5516

EMAIL DNRCHavreWater@mt.gov

Blaine, Chouteau, Glacier, Hill, Liberty, Pondera, Teton, and Toole Counties



#### **HELENA**

1424 9th Ave., PO Box 201601, Helena, MT 59620-1601

PHONE 406-444-6999 FAX 406-444-9317 EMAIL DNRCHelenaWater@mt.gov

Beaverhead, Broadwater, Deer Lodge, Jefferson, Lewis and Clark, Powell, and Silver Bow Counties



#### **KALISPELL**

655 Timberwolf Parkway, Suite 4 Kalispell, MT 59901-1215

PHONE 406-752-2288

EMAIL DNRCKalispellWater@mt.gov

Flathead, Lake, Lincoln, and Sanders Counties



#### **LEWISTOWN**

613 Northeast Main St., Suite E Lewistown, MT 59457-2020

PHONE 406-538-7459

EMAIL DNRCLewistownWater@mt.gov

Cascade, Fergus, Golden Valley, Judith Basin, Meagher, Musselshell, Petroleum, and Wheatland Counties



#### **MISSOULA**

2705 Spurgin Rd. Bldg. C, PO Box 5004 Missoula, MT 59806-5004

PHONE 406-721-4284 FAX 406-542-5899 EMAIL DNRCMissoulaWater@mt.gov

Granite, Mineral, Missoula, and Ravalli Counties







Form No. 600-TAA (Revised 02/2025)

## APPLICATION FOR BENEFICIAL WATER USE PERMIT TECHNICAL ANALYSES ADDENDUM

ARM 36.12.1303

Answer every question and applicable follow-up questions. Use the checkboxes to denote yes ("Y") or no ("N"). Questions that require items to be submitted to the Department have a submitted ("S") checkbox, which is marked when the required item is attached to the Technical Analyses Addendum. Label all submitted items with the question number for which they were submitted. Narrative responses that are larger than the space provided can be answered in an attachment. If an attachment is used, mark the see attachment ("A") checkbox on this form and label the attachment with the question number. If no attachment is needed, leave the see attachment ("A) checkbox blank. Constrain narrative responses to the specific question as is asked on the form; do not respond to multiple questions in one narrative. Responses in the form of a table may be entered into the table provided on this form or in an attachment. If an attachment is used, the table must have the exact headings found on this form, and the see attachment ("A") checkbox on this form must be marked. Label all units in narrative responses and tables. Light gray checkbox cells denote a narrative or table response is required. Dark gray checkbox cells denote no response is needed because the question directs you to answer subsequent questions or provides you with information.

#### **APPLICATION DETAILS**

Questions, Narrative Responses, and Tables	Check- boxes
1. Did you have a preapplication meeting AND complete a Permit Preapplication Meeting Form (Form 600P)?	☑Y□N
a. If no, complete the remainder of Form 600-TAA. Skip to question 2.	
b. If yes,	
i. Do the technical analyses submitted with Form 600 remain unchanged from those completed during the preapplication meeting process?	☑Y□N
<ol> <li>If yes, has any element of the project described in Form 600 changed from the mandatory elements of the project described in Forms 600P-A and/or 600P-B?</li> </ol>	□Y☑N
a. If yes, complete the remainder of Form 600-TAA. Skip to question 2.	
b. If no, Form 600-TAA is complete.	
2. If no,	
a. Are you submitting new technical analyses with Form 600 to replace the technical analyses completed during the preapplication meeting process?	□Y□N
i. If yes, complete the remainder of Form 600-TAA. Skip to question 2.	
ii. If no, are you correcting the technical analyses in response to a Departmental scientific credibility review completed during the preapplication meeting process?	□Y□N



1. If yes, does every element of the project described in Form 600 remain unchanged from the mandatory elements of the project described in Forms 600P-A and/or 600P-B AND do the corrected technical analyses analyze the project exactly as proposed on Form 600 and Form 600P-A/600P-B?								□ Y □ N			
			а	. If yes, Form 6	00-TAA	is complete	Э.				
b. If no, complete the remainder of Form 600-TAA. Skip to question 2.											
SURFACE WATER											
Questions, Narrative Responses, and Tables								Check- boxes			
	2. Is the p	ropos	ed source surfac	e water?							$\square$ Y $\square$ N
	a. If y	es, m	ove on to questic	n 3.							
b. If no, skip to question 16.											
3. What is the flow rate (GPM or CFS), volume (AF), period of diversion start date and end date (MM/DD-MM/DD) at each point of diversion? Use the same POD # as the project map (Form 600) to label each point of diversion.								ПΑ			
_	POD#	,						ne			
	Diversion Start Diversion End			nd							
		(MM	I/DD-MM/DD)	(MM/DD-MM/	/DD)	Flow Rate	e GP	М	CFS	(AF)	
	1							]			
	2							]			
								]			
								]			
								]			
Total											
4. Is the source type of the diversion perennial or intermittent, ephemeral, lake, or other?							ПΑ				
	Perenni		Answer	Ephemeral	Answe		Lake		nswer	Other	Answer
Intermittent		tent	questions 5 to 8		questi	on 9		qu	estion		questions 11 to 14
					1			110	,		111017

## Surface Water Analysis: Perennial or Intermittent ☐ Applicable ☐ Not Applicable

5. Are stream gage data available?	$\square$ Y $\square$ N
a. If yes, answer question 6.	
b. If no, answer question 7.	
6. Stream gage data are available.	
a. Is one stream gage located above the most upstream POD and one stream gage located below the most upstream POD?	□Y□N
i. If no, is only one stream gage located near the most upstream POD?	$\square$ $Y$ $\square$ $N$
If yes, is the stream gage located upstream or downstream of the POD?	
b. List the gage name(s). Write "N/A" for Gage 2 if one gage is available.  Gage 1:  Gage 2:	
c. What is the distance between the gage(s) and the most upstream POD? Write "N/A" for Gage 2 if only one gage is available.  Gage 1:  Gage 2:	
d. Is there a limiting or controlling factor on the source between the stream gage(s) and the most upstream POD? This includes dams that control the flow and streams with large gaining and/or losing reaches.	□Y□N
i. If yes, explain.	ПΑ
e. How long is the period of record? Write "N/A" for Gage 2 if one gage is available.  Gage 1:  Gage 2:	
f. Who operates and maintains the gage(s)? Write "N/A" for Gage 2 if one gage is available.  Gage 1:  Gage 2:	

g. Is each available stream gage operated and maintained by USGS or DNRC?	$\square$ Y $\square$ N
i. If yes, skip to question 6.h.	
<ul><li>ii. If no, answer the following questions for each gage not operated and maintained by USGS or DNRC.</li></ul>	
How frequently are stage data recorded? Write "N/A" for Gage 2 if only one gage is not operated or maintained by USGS.  Gage 1:  Gage 2:	
2. If data gaps were to occur, are they identified and left unfilled or estimated using interpolation, ice correction, or indirect discharge measurements methods?	
a. Gage 1.	□Y□N
b. Gage 2. Write "N/A" on the line instead of answering yes or no, if only one gage is not operated or maintained by USGS or DNRC.	□Y□N
3. Was the rating curve established and maintained throughout the duration of the period of record using measurements taken near the reference gage and stage recorder according to USGS protocols?	
a. Gage 1.	□Y□N
b. Gage 2. Write "N/A" on the line instead of answering yes or no, if only one gage is not operated or maintained by USGS or DNRC.	□Y□N
Were requirements established and followed for maintaining a permanent gage datum and meeting specified accuracy limits?	
a. Gage 1.	□Y□N
b. Gage 2. Write "N/A" on the line instead of answering yes or no, if only one gage is not operated or maintained by USGS or DNRC.	□Y□N
h. Do the data for one or more available stream gages meet the Department's standard to be sufficient to calculate the median of the mean monthly flow rate and volume during the proposed months of diversion? See the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual.	□Y□N
<ul> <li>i. If yes, record how many meet the standard, then skip to question 39 because this section is complete.</li> <li>Driller is Bridger Drilling, Tyler Sampson Driller, Lic. No. WWC-165</li> </ul>	
ii. If no, answer question 7.	
7. If no gage data are available or if available gage data do not meet the Department's standard to be sufficient to calculate the median of the mean monthly flow rate and volume during the proposed months of diversion, is the source otherwise measured?	□Y□N
a. If no, the Department requires gage data and/or measurements that meet the requirements of ARM 36.12.1702 or, in combination with an approved variance request, are sufficient to complete any necessary technical analyses or scientific credibility reviews and to evaluate the applicable criteria. Skip to question 8.	

b. If yes,	
i. Submit available measurements to the Department.	□S
ii. Who collected the measurements?	□А
iii. With what method were the data collected?	□А
iv. What is the period of record?	
v. What is the frequency of measurement?	
vi. Are there gaps in the data?	□Y□N
If yes, what is the nature of the gaps and how are gaps handled to ensure data quality?	□A
vii. Is there a process for maintaining the data and meeting specified accuracy limits?	□Y□N
1. If yes, explain.	□A
viii. Do available measurement data meet the Department's standard to be sufficient to calculate the median of the mean monthly flow rate and volume during the proposed months of diversion? See the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual.	□Y□N
1. If yes, this section is complete. Skip to question 39.	
2. If no, answer question 8.	

8. Do the available measurement data, gage and/or otherwise measured, meet the Department's standard of including a minimum of high, moderate, and low flows to be sufficient to use for validation of a Department-accepted estimation technique? If the Department finds that your measurements are not sufficient to validate an estimation technique or that no estimation technique is appropriate for the source characteristics, further measurements may be required. Refer to the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual for more information.	□Y□N
a. If yes,	
i. Describe how the measurements are representative of high, moderate, and low flows.	□A
ii. Describe the estimation technique.	□A
b. If no, but a Department-accepted estimation technique will be appropriate for the source:	
i. Submit Form 653 if you want to request a variance from the requirements of ARM 36.12.1702(1)(b). The Department's technical analyses or scientific credibility review of your technical analyses cannot commence until the Department receives measurements that meet the requirements of ARM 36.12.1702(1) or, in combination with an approved variance request, are sufficient to complete any necessary technical analyses or scientific credibility reviews and to evaluate the applicable criteria.	□S
<ul> <li>c. If no, because no Department-accepted estimation technique will be appropriate for the source:</li> </ul>	
i. Describe why no Department-accepted estimation technique is appropriate for the source characteristics.	□A
ii. Do the available measurement data, gage and/or otherwise measured, meet the Department's standard for monthly measurements throughout the proposed period of diversion pursuant to ARM 36.12.1702(4)? Refer to the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual for more information.	□ Y □ N
1. If no, submit Form 653 if you want to request a variance from the requirements of ARM 36.12.1702(4). The Department's technical analyses or scientific credibility review of your technical analyses cannot commence until the Department receives measurements that meet the requirements of ARM 36.12.1702(4) or, in combination with an approved variance request, are sufficient to complete any necessary technical analyses or scientific credibility reviews and to evaluate the applicable criteria.	□ Y □ N

# Surface Water Analysis: Ephemeral ☐ Applicable ☐ Not Applicable

9. Did you elect for the Department to conduct the Technical Analyses?	$\Box$ Y $\Box$ N
a. If yes, do you have climate or drainage area data you would like the Department to	$\Box$ Y $\Box$ N
consider during Technical Analyses?	
i. If yes, submit this information to the Department.	□S
b. If no,	
<ul> <li>i. What estimation technique did you use to estimate physical availability at the point of diversion?         The pump curve for the pumps installed in wells EX-1 and EX-2 allow for a maximum flow of &gt;275 gpm required during peak demand periods anticipated during the cooling season. The system will operate at significantly less flows     </li> </ul>	□ A
ii. What is the net annual precipitation? Include the source of this information.  ———————————————————————————————————	ΠA
iii. What is the drainage area upstream of the point of diversion and how was this figure calculated?  ———————————————————————————————————	□A
Surface Water Analysis: Lake  □ Applicable □ Not Applicable  10. What is the lake volume? Submit documentation explaining how the volume was quantified.	□S
Volume must be quantified by a qualified entity based on bathymetric data.	
Surface Water Analysis: Other  ☑ Applicable ☑ Not Applicable	
11. Explain why the source type is "other"	□А
12. Submit measurements of the source to the Department.	□Y□N
13. With what method was the measurement data collected?	□A

14. What is th	ne measurement interv	val?				
a. Does	the interval meet the D	Department's sta	ndard for monthly mea	asurements thro	oughout	
· · · · · · · · · · · · · · · · · · ·	pposed period of divers					
Al re m wi te	no, submit Form 653 if RM 36.12.1702(4). The view of your technical easurements that mee ith an approved varian chnical analyses or so iteria.	e Department's to analyses canno et the requirement ce request, are	technical analyses or set to commence until the lents of ARM 36.12.1702 sufficient to complete set.	scientific credib Department rec 2(4) or, in comb any necessary	ility ceives oination	□S
Area of Pote	ential Impact Analy	<u>/sis</u>				
All informatio	n for area of potentia	al impact analy	sis was collected in	previous ques	stions.	
GROUNDV	VATER					
Questions,	Narrative Respons	es, and Tables	S			Check- boxes
15. Is the pro	posed source ground	water?				□Y□N
a. If yes,	move on to question	16.				
b. If no, s	skip to question 39.					
<u> 3roundwate</u>	er Analysis for Per	<u>mits</u>				
16. What is th	ne type of groundwate	r diversion?				
Well/Pit	Answer questions 17 to 20	Developed Spring	Answer questions 21 to 24	Pond	Answer of 25 to 27	questions
Groun	dwater Analysis for l □ Applicable	Permits: Well/F □ Not Applica	. •			
17. Submit A	quifer Test Data Form	(Form 633).				□S
18. Submit the Aquifer Testing Addendum (Form 600/606-ATA) and associated materials (e.g., well logs).					s (e.g.,	□S
19. Are you r	equesting a variance f	rom ARM 36.12	.121?			□Y□N
a. If yes,	submit Form 653.					□S
20. Have all p	proposed wells/pumpir	ng pits been con	structed?			□Y□N
a. If no, a	answer the following q	uestions:				
i. Su	ا/الbmit a list of all wells	oumping pits lab	eled with the same PC	DD # as the pro	ject map	□S

(Form 600) and mark whether they have or have not been constructed.

ii. When will all proposed wells/pumping pits be constructed?	□А
iii. Is the requested volume for each proposed well/pumping pit known?	□Y□N
If yes, list the flow rate and volume requested for each proposed well/pumping pit. Label with the same POD # as the project map (Form 600).  ——————————————————————————————————	□А
If no, what is the total requested volume (AF) and the number of proposed wells/pumping pits?  ———————————————————————————————————	
Groundwater Analysis for Permits: Developed Spring  ☐ Applicable ☐ Not Applicable	
21. Submit your measurements of the flow rate and volume of the source.	□S
22. With what method were measurements collected?	ΠA
23. What is the interval of measurements?	
24. Is the interval of measurements sufficient to comply with ARM 36.12.1703(1)? Please note technical analyses or scientific credibility review cannot commence until the Department has measurement data that meets the requirements of ARM 36.12.1703(1). Variances from ARM 36.12.1703(1) are not allowed.	DYDN
Groundwater Analysis for Permits: Pond  ☐ Applicable ☐ Not Applicable	
25. Submit Form 653 to apply for a variance from ARM 36.12.121 for the Aquifer Test.	□S
26. Submit pond bathymetry data, survey, or engineering plans to the Department.	□S
27. Is the pond fed or drained by surface water?	□Y□N
a. If yes,	
i. Explain.	Α



	inf	low a	and outf	low me	asurements.					
Surface	e Wat	<u>er D</u>	epleti	on Ana	<u>alysis</u>					
28. Is th	ne type	e of g	roundw	vater div	ersion for your	proposed project a	deve	loped spring? If	yes,	ΠΥΠΝ
skip t	to ques	stion	33 bec	ause th	is section is co	mplete. If no, move	onto	question 29.		
29. Is th	ne type	e of g	roundw	∕ater di\	ersion for your	proposed project a	pond	l? If yes, answer		
ques	tion 29	a, th	nen skip	to que	stion 33 becau	se this section is co	mplet	e. If no, move or	nto	
	tion 30									
a. \	Will an	y of t	the pon	ds have	e diversions for	out-of-pond use that	at diffe	er from, if year-ro	ound	
					•	he number of days				
i	rrigatio	n/lav	wn and	garden	use, the 80% of	dry year net irrigatio	n requ	uirement (IWR, N	NRCS	
2	2003)?									
	•					rsions for out-of-por				□A
					ne project map	(Form 600). Attach	any a	dditional schedu	les with	
		)D #	labeled	l						
POD #						T =				
Month Diversions for Out-of-Pond Use Volume (AF)  Month Diversions for Out-of-Pond Use Volume (AF)							Use			
lanua	r) /	USE	volun	1e (AF)		July	VOIL	ime (AF)		
Janua Februa						August				
March						September				
April	•					October				
May						November				
June						December				
	'						•			
30. Wh	at are	the fl	ow rate	(GPM	or CFS), volum	ne (AF), and period	of div	ersion required		□А
(MM/	DD-MI	M/DE	) at ea	ch well/	pumping pit? V	Vhat is the well/pum	nping	pit depth (FT), if		
availa	able, o	r esti	imated	well/pur	mping pit depth	ı (FT). Please use tl	ne sar	ne POD # as the	)	
proje	ct map	(Fo	rm 600)	) to mat	ch this informa	tion with the location	n infoi	mation.		
POD	Flow	'	GPM	CFS	Volume	Period of Diversi	on	Well Depth	Measu	
#	Rate				(AF)	(MM/DD-MM/DD)		(FT)	Estima	ted

ii. Submit measurements of the connected surface water source. These may include

 $\square$  S

31. Will any of the <i>new</i> wells/pumping pits have a monthly pumping schedule that differs from, if year-round use, an allocation of diverted volume by the number of days in the month, or, if									
•	•			•	•				
irrigation/lawn and garden use, the 80% dry year net irrigation requirement (IWR, NRCS									
2003)?									
a. If yes, provide the alternative pumping schedule(s) in the table below. Use the same POD								□A	
# as	the project m	ap (Form 600	)). Attach any a	dditional pum	ping schedu	les with POD a	#		
labe	labeled.								
POD#									
Month Volume Month Volume Month Volume Month Vol							olume		
	(AF)		(AF)		(AF)		(/	AF)	
January		July		January		July			

Month	Volume (AF)	Month	Volume (AF)	Month	Volume (AF)	Month	Volume (AF)
January		July		January		July	
February		August		February		August	
March		September		March		September	
April		October		April		October	
May		November		May		November	
June		December		June		December	

32. Will one or more existing wells/pumping pits be used for the proposed project?	$\square Y \square N$
a. If yes, will any of the existing wells/pumping pits have a monthly pumping schedule,	$\square$ $Y$ $\square$ $N$
before or after the proposed project, that differs from an allocation of diverted volume by	
the number of days in the month (if year-round use) or the 80% dry year net irrigation	
requirement (if irrigation/lawn and garden use) (IWR, NRCS 2003)?	
i. If yes, provide the pumping schedules before and after the proposed project in the	□А
table below. Use the same POD # as the project map (Form 600). Attach any	
additional pumping schedules with POD # and before/after proposed project labeled.	

Before pro	posed proje	ct: POD #		After propo	posed project: POD #			
Month	Volume (AF)	Month	Volume (AF)	Month	Volume (AF)	Month	Volume (AF)	
January		July		January		July		
February		August		February		August		
March		September		March		September		
April		October		April		October		
May		November		May		November		
June		December		June		December		

## **Surface Water Analysis of Depleted Surface Water**

33. If you submitted Technical Analyses with this application, list the hydraulically connected
surface water sources and answer questions 34 to 38 one time per source. Use the "Additional Hydraulically Connected Source (600-TAA)" sheet for each additional source. If you have elected for the Department to conduct the Technical Analyses after application submittal, write "N/A" and skip to question 39 because the information required to answer questions 34 to 38 is not yet available. If measurements are required to determine physical or legal availability of depleted surface water sources, the Department will not have the information necessary to complete all necessary technical analyses or to evaluate the applicable criteria. If the type of groundwater diversion for your proposed project is a developed spring, write "NA" and skip to question 39 because this section is complete.

34. Name the hydraulically connected surface water source for which you are answering questions 35 to 38.	
35. Are stream gage data available?	
a. If yes, answer question 36.	
b. If no, answer question 37.	
36. Stream gage data are available.	
a. Is one stream gage located above and one stream gage located below the start of the	
depleted reach?	□Y□N
i. If no, is only one stream gage located near the start of the depleted reach?	$\square$ $Y$ $\square$ $N$
If yes, is the stream gage located upstream or downstream?  ———————————————————————————————————	
b. List the gage name(s). Write "N/A" for Gage 2 if one gage is available.  Gage 1:	
Gage 2:	
c. What is the distance between the gage(s) and the start of the depleted reach? Write "N/A" for Gage 2 if one gage is available.	
Gage 1:	
Gage 2:	
d. Is there a limiting or controlling factor on the source between the stream gage(s) and the start of the depleted reach? This includes dams that control the flow and streams with large gaining and/or losing reaches.	□Y□N
i. If yes, explain.	□A
<del> </del>	
e. How long is the period of record? Write "N/A" for Gage 2 if one gage is available.  Gage 1:	
Gage 2:	
f. Who operates and maintains the gage(s)? Write "N/A" for Gage 2 if one gage is available.	
Gage 1:	
Gage 2:	
g. Is each available stream gage operated and maintained by USGS or DNRC?	
i. If yes, skip to question 36.h. ii. If no, answer the following questions for each gage not operated and maintained by	
USGS or DNRC.	
1. How frequently are stage data recorded? Write "N/A" for Gage 2 if only one gage	
is not operated or maintained by USGS.	
Gage 1:	
Gage 2:	

2. If data gaps were to occur, are they identified and left unfilled or estimated using interpolation, ice correction, or indirect discharge measurements methods?	
a. Gage 1.	□Y□N
b. Gage 2. Write "N/A" on the line instead of answering yes or no, if only one gage is not operated or maintained by USGS or DNRC.	□Y□N
3. Was the rating curve established and maintained throughout the duration of the period of record using measurements taken near the reference gage and stage recorder according to USGS protocols?	
a. Gage 1.	$\square Y \square N$
b. Gage 2. Write "N/A" on the line instead of answering yes or no, if only one gage is not operated or maintained by USGS or DNRC.	□Y□N
Were requirements established and followed for maintaining a permanent gage datum and meeting specified accuracy limits?	
a. Gage 1.	$\square$ $Y$ $\square$ $N$
b. Gage 2. Write "N/A" on the line instead of answering yes or no, if only one gage is not operated or maintained by USGS or DNRC.	□Y□N
h. Do the data for one or more available stream gages meet the Department's standard to be sufficient to calculate the median of the mean monthly flow rate and volume during the months with net depletions? See the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual.	□Y□N
i. If yes, record how many meet the standard, then skip to question 39 because this section is complete.	
ii. If no, answer question 37.	
37. If no gage data are available or if available gage data do not meet the Department's standard to be sufficient to calculate the median of the mean monthly flow rate and volume during the months with net depletions, is the source otherwise measured?	□Y□N
a. If no, the Department requires gage data and/or measurements that meet the requirements of ARM 36.12.1702 or, in combination with an approved variance request, are sufficient to complete any necessary technical analyses or scientific credibility reviews and to evaluate the applicable criteria. Skip to question 38.	
b. If yes,	
i. Submit available measurements to the Department.	□S
ii. Who collected the measurements?	□A
iii. With what method were the data collected?	ΠA
iv. What is the period of record?	

1. If yes, what is the nature of the gaps and how are gaps handled to ensure data quality?  vii. Is there a process for maintaining the data and meeting specified accuracy limits?  1. If yes, explain.  viii. Do available measurement data meet the Department's standard to be sufficient to calculate the median of the mean monthly flow rate and volume during the months with net depletions? See the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual.  1. If yes, this section is complete. Skip to question 39.  2. If no, answer question 38.	v. What is the frequency of measurement?	
1. If yes, what is the nature of the gaps and how are gaps handled to ensure data quality?  vii. Is there a process for maintaining the data and meeting specified accuracy limits?  1. If yes, explain.  viii. Do available measurement data meet the Department's standard to be sufficient to calculate the median of the mean monthly flow rate and volume during the months with net depletions? See the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual.  1. If yes, this section is complete. Skip to question 39.  2. If no, answer question 38.  38. Do the available measurement data, gage and/or otherwise measured, meet the Department's standard of including a minimum of high, moderate, and low flows to be sufficient to use for validation of a Department-accepted estimation technique? If the Department finds that your measurements are not sufficient to validate an estimation technique or that no estimation technique is appropriate for the source characteristics, further measurements may be required. Refer to the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual for more information.  a. If yes,  i. Describe how the measurements are representative of high, moderate, and low flows.		
viii. Is there a process for maintaining the data and meeting specified accuracy limits?  1. If yes, explain.  viii. Do available measurement data meet the Department's standard to be sufficient to calculate the median of the mean monthly flow rate and volume during the months with net depletions? See the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual.  1. If yes, this section is complete. Skip to question 39.  2. If no, answer question 38.  38. Do the available measurement data, gage and/or otherwise measured, meet the Department's standard of including a minimum of high, moderate, and low flows to be sufficient to use for validation of a Department-accepted estimation technique? If the Department finds that your measurements are not sufficient to validate an estimation technique or that no estimation technique is appropriate for the source characteristics, further measurements may be required. Refer to the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual for more information.  a. If yes,  i. Describe how the measurements are representative of high, moderate, and low flows.	vi. Are there gaps in the data?	
Viii. Do available measurement data meet the Department's standard to be sufficient to calculate the median of the mean monthly flow rate and volume during the months with net depletions? See the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual.  1. If yes, this section is complete. Skip to question 39.  2. If no, answer question 38.  38. Do the available measurement data, gage and/or otherwise measured, meet the Department's standard of including a minimum of high, moderate, and low flows to be sufficient to use for validation of a Department-accepted estimation technique? If the Department finds that your measurements are not sufficient to validate an estimation technique or that no estimation technique is appropriate for the source characteristics, further measurements may be required. Refer to the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual for more information.  a. If yes,  i. Describe how the measurements are representative of high, moderate, and low flows.		
Viii. Do available measurement data meet the Department's standard to be sufficient to calculate the median of the mean monthly flow rate and volume during the months with net depletions? See the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual.  1. If yes, this section is complete. Skip to question 39.  2. If no, answer question 38.  38. Do the available measurement data, gage and/or otherwise measured, meet the Department's standard of including a minimum of high, moderate, and low flows to be sufficient to use for validation of a Department-accepted estimation technique? If the Department finds that your measurements are not sufficient to validate an estimation technique or that no estimation technique is appropriate for the source characteristics, further measurements may be required. Refer to the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual for more information.  a. If yes,  i. Describe how the measurements are representative of high, moderate, and low flows.	vii. Is there a process for maintaining the data and meeting specified accuracy limits?	
calculate the median of the mean monthly flow rate and volume during the months with net depletions? See the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual.  1. If yes, this section is complete. Skip to question 39.  2. If no, answer question 38.  38. Do the available measurement data, gage and/or otherwise measured, meet the Department's standard of including a minimum of high, moderate, and low flows to be sufficient to use for validation of a Department-accepted estimation technique? If the Department finds that your measurements are not sufficient to validate an estimation technique or that no estimation technique is appropriate for the source characteristics, further measurements may be required. Refer to the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual for more information.  a. If yes,  i. Describe how the measurements are representative of high, moderate, and low flows.	1. If yes, explain.	
2. If no, answer question 38.  38. Do the available measurement data, gage and/or otherwise measured, meet the Department's standard of including a minimum of high, moderate, and low flows to be sufficient to use for validation of a Department-accepted estimation technique? If the Department finds that your measurements are not sufficient to validate an estimation technique or that no estimation technique is appropriate for the source characteristics, further measurements may be required. Refer to the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual for more information.  a. If yes,  i. Describe how the measurements are representative of high, moderate, and low flows.	calculate the median of the mean monthly flow rate and volume during the months with net depletions? See the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual.	□Y□N
38. Do the available measurement data, gage and/or otherwise measured, meet the Department's standard of including a minimum of high, moderate, and low flows to be sufficient to use for validation of a Department-accepted estimation technique? If the Department finds that your measurements are not sufficient to validate an estimation technique or that no estimation technique is appropriate for the source characteristics, further measurements may be required. Refer to the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual for more information.  a. If yes,  i. Describe how the measurements are representative of high, moderate, and low flows.	1. If yes, this section is complete. Skip to question 39.	
Department's standard of including a minimum of high, moderate, and low flows to be sufficient to use for validation of a Department-accepted estimation technique? If the Department finds that your measurements are not sufficient to validate an estimation technique or that no estimation technique is appropriate for the source characteristics, further measurements may be required. Refer to the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual for more information.  a. If yes,  i. Describe how the measurements are representative of high, moderate, and low flows.	2. If no, answer question 38.	
i. Describe how the measurements are representative of high, moderate, and low flows.	Department's standard of including a minimum of high, moderate, and low flows to be sufficient to use for validation of a Department-accepted estimation technique? If the Department finds that your measurements are not sufficient to validate an estimation technique or that no estimation technique is appropriate for the source characteristics, further measurements may be required. Refer to the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual for more information.	□Y□N
	* :	
ii. Describe the estimation technique.	Describe now the measurements are representative of high, moderate, and low flows.	ПΑ
	ii. Describe the estimation technique.	□A

<ul> <li>b. If no, but a Department-accepted estimation technique will be appropriate for the hydraulically connected surface water source:</li> </ul>	
i. Submit a request to deviate from the Department's standard of including a minimum of high, moderate, and low flows to be sufficient to use for calibration of a Department-accepted estimation technique. The Department's technical analyses or scientific credibility review of your technical analyses cannot commence until the Department receives measurements that meet Department measurement standards, or in combination with a request to deviate, are sufficient to complete any necessary technical analyses or scientific credibility reviews and to evaluate the applicable criteria.	□S
<ul> <li>c. If no, because no Department-accepted estimation technique will be appropriate for the source:</li> </ul>	
i. Describe why no Department-accepted estimation technique is appropriate for the source characteristics.	ДΑ
ii. Do the available measurement data, gage and/or otherwise measured, meet the Department's standard for monthly measurements throughout the months with net depletions? Refer to the "Department Standard Practice for Determining Physical Surface Water Availability" in the Permit Manual for more information.	□Y□N
1. If no, submit a request to deviate from the Department's standard for monthly measurements throughout the months with net depletions. The Department's technical analyses or scientific credibility review of your technical analyses cannot commence until the Department receives measurements that meet Department measurement standards, or in combination with a request to deviate, are sufficient to complete any necessary technical analyses or scientific credibility reviews and to evaluate the applicable criteria.	□S

## **Area of Potential Impact Analysis of Depleted Surface Water**

All information for area of potential impact of depleted surface water was collected in previous questions.

## PROJECT-SPECIFIC QUESTIONS

## **Controlled Groundwater Areas and Basin Closures**

Questions, Narrative Responses, and Tables	Check- boxes
39. Does the project include one or more groundwater points of diversion located in the East	
Valley Controlled Groundwater Area (EVCGWA)?	
a. If yes, is the use over 35 GPM or 10 AF per year?	$\Box$ Y $\Box$ N
i. If no, this is the incorrect form. Use instead Form 600-EVCGWA: East Valley Controlled Groundwater Area Permit Application.	
ii. If yes, how does this project meet the specific requirements of the East Valley Controlled Groundwater Area? Include any relevant documentation.	ПА
h If no akin to quantian 40	
b. If no, skip to question 40.	
40. Does the project include one or more groundwater points of diversion located in the Yellowstone Controlled Groundwater Area (YCGA)?	
a. If yes, is the proposed flow rate and volume over 35 GPM or 10 AF per year?	$\square$ $Y$ $\square$ $N$
i. If no, this is the incorrect form. Use instead Form 600-YCGA: Yellowstone Controlled Groundwater Area Permit Application.	
ii. If yes, submit Form 600 YCGA: Yellowstone Controlled Groundwater Area Addendum Over 35 gallons per minute.	□S
<ul> <li>41. Is the project for surface water or groundwater and subject to one or more of the following areas listed on the Department's website (<a href="https://dnrc.mt.gov/Water-Resources/Water-Rights/Basin-Closures-Stream-Depletion-Controlled-Ground-Water-Areas">https://dnrc.mt.gov/Water-Resources/Water-Rights/Basin-Closures-Stream-Depletion-Controlled-Ground-Water-Areas</a>)?</li> <li>Controlled Groundwater Areas, not mentioned in questions 39 to 40</li> <li>Basin Closures or Stream Depletion Zones</li> </ul>	□Y□N
a. If yes, identify each area and describe how the proposed project meets its requirements.  An application must meet the specific requirements of the Controlled Groundwater Area or closure to be accepted by the Department.	□A





## APPLICATION FOR BENEFICIAL WATER USE PERMIT BASIN CLOSURE ADDENDUM

§§ 85-2-360, 85-2-361, 85-2-362, MCA ARM 36.12.120

The Department cannot process an application located in a basin closure area unless it qualifies as a basin closure exception. The Department will determine whether an application in a basin closure area can be processed based on the information received from the applicant and will document its findings before it will review the application to determine whether it is correct and complete. You will be required to mitigate the net depletion of water that may create an adverse effect to groundwater and hydraulically connected surface water rights.

Answer every question and applicable follow-up questions. Use the checkboxes to denote yes ("Y") or no ("N"). Questions that require Applicant to submit items to the Department have a submitted ("S") checkbox, which is marked when the required item is attached to the Basin Closure Addendum. Label all submitted items with the question number for which they were submitted. Responses that are larger than the space provided can be answered in an attachment. If an attachment is used, specify "see attachment" on this form. Label all attachments with the question number.

1.	. □ Y ■ N For groundwater applications filed pursuant to § 85-2-360, MCA, did the Hydrogeologic Assessment Report indicate that the proposed groundwater use will affect a surface water source? If yes, continue through the addendum. If no, this addendum is complete		
2.	What surface water source will be affected by the groundwater use?		
3.	$\square$ S Submit a map showing the location of the effect on surface water. Create the map on an aerial photograph or topographic map and include the following: section corners, township and range, scale bar, and north arrow.		
4.	What amount of effect will occur to surface water? □ GPM -or- □ CFS □ Acre-Feet		
5.	<ul> <li>What is your plan to mitigate the amount of water identified in question 4?</li> <li>a. □ One or more Applications to Change a Water Right (Form 606) to mitigate the adverse effect created. Applications to Change a Water Right must be submitted with the Application for Beneficial Water Use (Form 600).</li> <li>b. □ Alternative mitigation plan, in lieu of an Application to Change a Water Right, to mitigate the adverse effect created. Submit your alternative mitigation plan with Form 600/606-MIT.</li> <li>c. □ A mitigation plan is not required.</li> </ul>		
	i ΠS Submit all documentation to show a mitigation plan is not required		



).	proposed project, such as areas of subsidence? If yes, describe a plan to mitigate any of those conditions or impacts.				

NOTE: Information required for the hydrogeologic assessment may not be sufficient to meet applicable criteria under § 85-2-311, MCA, including but not limited to adverse effect to a prior appropriator. The applicant for a beneficial water use permit pursuant to § 85-2-311, MCA, is responsible for providing sufficient evidence to meet all applicable criteria.





## **Groundwater Permit Technical Analyses Report - Part A**

## **Department of Natural Resources and Conservation (DNRC) Water Resources Division**

Evan Norman, Groundwater Hydrologist, Water Sciences Bureau (WSB)

Application No.	41H 30165312	Point of Diversion Legal Land Description	Section 27 and 22, Township 01 South, Range 5 West
Applicant	Barnard Construction		

#### **Overview**

This report is Part A of a two-part publication which analyzes data submitted by the Applicant in support of the above-mentioned water right application. This report provides technical analyses as required under the Administrative Rules of Montana (ARM) 36.12.1303 in support of the water rights criteria assessment as required in §85-2-311, Montana Code Annotated (MCA). For applications in closed basins, this report fulfills the requirements of MCA 85-2-361.

This Groundwater Permit Technical Analyses Report – Part A contains the following sections:

Overview	1
1.0 Executive Summary	2
2.0 Hydrogeologic Setting	3
3.0 Aquifer Test Summary	4
4.0 Aquifer Test Analysis	7
5.0 Drawdown and Yield Test	12
6.0 Modeling Inputs	13
7.0 Adequacy of Diversion Analysis	13
8.0 Physical Availability Analysis	17
9.0 Adverse Effect Analyses	19
9.1 Groundwater - Drawdown in Existing Wells	19
9.2 Surface Water - Net Depletion	19
Review	1
References	1
Appendix A: Groundwater Rights Within Area of Potential Impact	

Appendix B: 1-foot-Contour Water Rights



## 1.0 Executive Summary

#### **Application Details**

The Applicant requests to divert 550.0 gallons per minute (gpm) and up to 298.40 acre-feet (AF) of groundwater from two points of diversion (wells) for geothermal cooling purposes. The two Extraction Wells, Montana Bureau of Mines and Geology (MBMG) Groundwater Information Center (GWIC) IDs 335313 and 335315, would each divert water at a rate of 275.0 gpm. Two injection Wells, GWIC IDs 335309 and 335811, would each inject water at a rate of 275.0 gpm back into the aquifer via an open-loop geothermal cooling system.

#### Recommended and Approved Variances from ARM 36.12.121

The required variances, rationale, and recommended action to grant the variance requests were sent in an Aquifer Testing Addendum Review checklist to the Bozeman Regional Office on April 7, 2025. Variances from aquifer test requirements found in ARM 36.12.121: 3(a), 3(g), 3(h), and 3(e)(iii) were approved by the Bozeman Regional Office on April 14, 2025.

### **WSB Technical Analyses Findings**

Based on information submitted, the WSB estimated aquifer properties, evaluated the extraction well(s) available water column, quantified the water available in the source aquifer, and evaluated potential impacts to existing groundwater and surface water rights. These technical analyses are in support of the following criteria assessment: adequacy of diversion, physical availability, and adverse effect. A summary of WSB findings described in subsequent sections are listed below.

#### **TECHNICAL ANALYSES FINDINGS**

AQUIFER TEST ANALYSIS	Using the Cooley-Case (1973) solution, saturated thickness (b) of 218 feet (ft), and submitted 72.2-hour aquifer testing data for GWIC ID 335315, estimates of aquifer properties include a Transmissivity (T) of 873 ft $^2$ /day and Storativity (S) of 1.1 x 10 $^{-4}$ .
MODELING INPUTS	The following aquifer properties were used to complete adequacy of diversion, physical availability and adverse effect technical analyses: T of 873 ft <sup>2</sup> /day, S of 1.1 x $10^{-4}$ . The estimated leakage parameter (r/B; $\beta$ ), storage ratio in aquitard (S'/Sy), and dimensionless height of capillary fringe (L/b') are identified in figures below. Pumping schedules and boundaries used to model each criterion are identified within the document.
ADEQUACY OF DIVERSION	The aquifer adjacent to GWIC ID 335313 and 335315 would experience 54.20 and 58.90 ft of drawdown after the first year, leaving approximately 134 ft and 159 ft of available water column above the bottom of the perforated intervals, respectively.
PHYSICAL AVAILABILITY	The model predicted the 0.01-foot drawdown contour, or zone of influence (ZOI), has a width of approximately 14,000 ft in the predominate direction of groundwater flow. The northeastern and eastern extent of the ZOI was





truncated to the East Gallatin River. The total flux through the ZOI is equal to 1,024 AF/year. There are 152 existing groundwater rights with a status of active and severed within the ZOI. (**Appendix A**).

### ADVERSE EFFECT (DRAWDOWN IN EXISTING WELLS)

The 1-foot drawdown contour extends out approximately 4,100 ft from GWIC ID 335313 and 335315 at the end of July of the fifth year of pumping. 13 water rights are predicted to experience drawdown equal to or greater than 1-foot (**Appendix B**).

## ADVERSE EFFECT (NET DEPLETION TO SURFACE WATER)

The East Gallatin River is identified as being hydraulically connected to the source aquifer. There would be no consumed volume associated with the proposed geothermal purpose, and therefore no net depletion to hydraulically connected surface waters.


## 2.0 Hydrogeologic Setting

As identified in **Figure 1**, the Production Wells GWIC ID 335313 and 335315 (Extraction Wells 1 & 2) were completed to 202 and 232 ft below ground surface (bgs) in Section 27 and 22, Township 01 South, Range 05 East, Gallatin County, respectively. Both wells are completed in the Tertiary aged valley-fill sediments (120SDMS) with perforated interval lengths of 35 ft. The wells, GWIC IDS 335309 and 335811 (Reinjection Wells 1 & 2) are completed to 300 and 215 ft bgs, respectively, in Section 22, Township 01 South, Range 05 East, Gallatin County. The injection wells are also completed in the source aquifer 120SDMS with perforated interval lengths of 144 and 100 ft. Well logs near the project location primarily describe alternating lenses of sand and gravel, clay-bound gravels, and clay which may act as localized leaky-confining units.

The surficial geology is mapped as Quaternary braided plain alluvium deposits of cobbles, boulders, sand, silt and clay up to 30 ft thick (Vuke et al., 2014). The Quaternary sediments are underlain by Tertiary Madison Valley member silt, siltstone, sandstone and conglomerates, in some parts of the valley up to 300 ft thick (Vuke et al., 2014).

The Gallatin Valley Quaternary and Tertiary aquifer system contains shallow unconfined, semiconfined (leaky confined), confined, and possibly even perched groundwater (English, 2018). Generally, groundwater and surface water flows from southeast to northwest across the valley and is recharged by irrigation, stream losses, and ditch leakage ultimately discharging to the Gallatin River (Hackett et al., 1960). The wells are on the edge of the Bozeman hydrogeologic subarea (Fan) adjacent to the Upper East Gallatin and Belgrade hydrogeologic subareas mapped by Hackett et al. (1960). Recent studies suggest that recharge from the surrounding bedrock aquifer and leakage from canals and ditches are the two largest components of groundwater recharge to the Gallatin Valley Aquifer (Michalek and Sutherland, 2020).





**Figure 1:** Map of the Applicant's aquifer test location and nearby T values derived from aquifer tests (**Table 4**).

## 3.0 Aquifer Test Summary

DNRC requires two different types of tests: "Aquifer Tests" and "Drawdown and Yield Tests." which aid DNRC in analyzing different application criteria.

- An "aquifer test" is a pumping test that is meant to provide data to model aquifer properties. The minimum duration of these tests is either 24-hours or 72-hours, depending on the proposed flow rate and volume (AMR 36.12.121(3)(e)), and DNRC only requires one of these tests per application. Aquifer Tests must include observation well data and pre-test monitoring data as well as post-test recovery data.
- A "drawdown and yield test" is a pumping test that is meant to evaluate well construction
  and the ability of the aquifer to yield water to the well. This is also known as
  demonstrating "adequacy of diversion." The minimum duration of these tests is 8 hours,
  and every well that is a part of the application, that did not have an aquifer test, must be



Groundwater Permit Technical Analyses Report-Part A
Application No. 41H 30165312
Bozeman Regional Office
Gallatin County

tested for at least 8 hours. Observation wells, pre-test background data, and post-test recovery data are not required for Drawdown and Yield Tests.

#### **Field Methods and Equipment**

A 72.2-hour aquifer test was conducted on the Production Well, GWIC ID 335315. Water pressure was collected using an In-situ LevelTROLL 400 water level logger and corrected using a BaroTROLL 400 data logger in the Production Well and Observation Wells (GWIC ID 335313 and 304409). Manual water level measurements were collected using a Geotech water level meter. Observation Wells GWIC ID 335313 and 304409 are 163 and 430 ft from the Production Well and completed in the same source aquifer. The discharge was measured with a Blue-White Brand F-300 flow meter attached to a 4-inch discharge pipe.

#### **Background Data**

A variance for ARM 36.12.121 was granted for 3(g) and therefore, limited background data was collected as part of the 72.2-hour aquifer test. Background level trends did not appear to affect the drawdown and recovery data.

#### **Drawdown Data**

The 72.2-hour aquifer test started on July 23, 2024, at 12:00 P.M. on the Production Well and is considered (t = 0) for the computation of drawdown. The average pumping rate was 269.5 gpm. The pumping rate varied during the test beyond a margin of 5% of the average discharge (+/- 5% average discharge). The additional drawdown and yield test was submitted to meet the total requested flow rate of 550.0 gpm.







Figure 2: Measured discharge for Production Well GWIC ID 335315 during the 72.2-hour test.

The maximum drawdown in the Production Well was 87.86 ft below the static water level (swl) of 16.05 ft below top of casing (btc) leaving approximately 130 ft of available water column above the bottom of the perforated interval. Observation Well, GWIC ID 335313, experienced a maximum drawdown of 24.22 ft below the swl of 14.94 ft btc leaving approximately 165 ft of available water column above the bottom of the perforated interval. Observation Well, GWIC ID 304409, did not have observable drawdown as a result of the aquifer testing. A plot of drawdown and recovery for the Production and Observation Wells with measured drawdown is shown in **Figure 3**.

#### **Recovery Data**

Recovery groundwater level data was monitored for 72-hours in the Production Well GWIC ID 335315 and Observation Well GWIC ID 335313. At the end of the recovery period the Production and Observation Wells were both -0.05 ft from pre-test swls, respectively.





**Figure 3:** Drawdown and recovery data for Production and Observation Wells during the 72.2-hour aquifer test.

## 4.0 Aquifer Test Analysis

#### **Methods**

The DNRC utilized AQTESOLV® (HydroSOLVE, Inc., 2007) to analyze drawdown data from the aquifer test and obtain estimates of aquifer properties. Aquifer properties were used in forward modeling to evaluate the available water column in the well, quantity of water available in the source aquifer, and potential impacts to groundwater and surface water rights. AQTESOLV® is an analytical modeling software that uses image-well theory and the principle of superposition to simulate aquifer stress tests. Drawdown data and measured flow rates from the aquifer test, and the spatial location of each well are input into the model. Using this compilation of data, aquifer properties including T and S are identified based on a best-fit visual and statistical match between the observed and theoretical drawdown data.

### **Analyses**

Analytical groundwater solutions were matched to Production and Observation Well drawdown data to generate estimates of aquifer properties for the source aquifer. As identified in **Figure 4** through **Figure 6**, theoretical AQTESOLV® predicted derivatives (red line) were compared to the




Groundwater Permit Technical Analyses Report-Part A
Application No. 41H 30165312
Bozeman Regional Office
Gallatin County

calculated derivatives from the observed drawdown (black triangles) and predicted drawdown (blue line) compared to the observed drawdown (black squares).

For estimation of aquifer properties, the Production and Observation Wells were assumed to be fully penetrating, and a saturated thickness (b) of 218 ft was used, which is length between the bottom of the perforated interval and the swl for the Production Well. Drawdown data and measured flow rates from the aquifer test, and the relative location of the Production Well and Observation Wells were input into AQTESOLV®. As shown in **Figure 4** and **Figure 5**, the Cooper-Jacob (1946) solution was used to perform a preliminary analysis of T and S using the Production and Observation Wells. The drawdown data for the Production Well and Observation Well show slight declines in the derivative throughout the aquifer testing, indicative of leaky-confined aquifer conditions.


The Cooley-Case (1973) solution for leaky-confined aquifers with a water-table aquitard was used to analyze T, S, and the leakage parameters for Observation Well GWIC ID 335313 based on the best-fit visual and statistical match between the observed and theoretical drawdown (**Figure 6**). The Cooley-Case (1973) model assumes a homogenous, isotropic leaky confined aquifer with instantaneous drainage at the water table from storage. **Table 3** lists the aquifer test analyses for the Production and Observation wells. The recommended aquifer T and S to be used in forward modeling is  $873 \, \text{ft}^2/\text{day}$  and  $1.1 \, \text{x} \, 10^{-4}$  from the Cooley-Case (1973) solution for Observation Well GWIC ID 335313. The estimated parameters are supported by existing hydrogeologic data below and the conceptual model of the project location described in the hydrogeologic setting above.






**Figure 4:** Cooper-Jacob (1946) time-drawdown and derivative analysis for the Production Well GWIC ID 335315.





**Figure 5:** Cooper-Jacob (1946) time-drawdown and derivative analysis for the Observation Well GWIC ID 335313.





**Figure 6:** Cooley-Case (1973) time-drawdown and derivative analysis for the Observation Well GWIC ID 335313.

**Table 3:** Aquifer test analyses for 72.2-hour test completed on the Production Well.

Production Well (GWIC ID, Phase)	Well Analyzed (GWIC ID)	Analysis Solution	T (ft²/day)	S
335315, Drawdown	335315	Cooper-Jacob (1946)	998	NA
335315, Drawdown	335313	Cooper-Jacob (1946)	1,134	1.1 x 10 <sup>-4</sup>
335315, Drawdown & Recovery	335313	Cooley-Case (1973)	873	1.1 x 10 <sup>-4</sup>



**Table 4:** Nearby Aquifer Tests and estimates of T and S when available.

Water Right No.	GWIC ID	Well Completion Depth (ft)	Distance from Proposed Project (miles)	Aquifer Test Length (hours)	Pumping Rate (gpm)	T (ft²/day)	S
41H 30127867	304056	155	1.2	72	240	1,704	1.0E-3
41H 30109060	292561	178	1.7	76	397	28,000	0.1
41H 30109060	292562	158	1.7	72	388	34,000	0.1
41H 30115127	296973	280	2.6	72	206	5,545	4.0E-4
41H 30000136	205719	146	2.6	24	250	1,265	0.1
41H 30010803	215306	140	3.4	72	200	4,680	
41H 30009188	183089	282	4.5	72	583	179	
41H 30048037	95855	171	4.6	72	583	940	0.2

The Quaternary and Tertiary sediments of the Bozeman fan have T ranges of 602 to 8,689 ft²/day and 40 to 361 ft²/day, respectively (Hackett et al. 1960). Further, Custer et al. (1991) provided a T range for the Quaternary and Tertiary sediments of 214 ft²/day to 10,694 ft²day. The reported S range of  $4.0 \times 10^{-4}$  to 0.2 in **Table 4**, supports the confined to unconfined conditions of the Quaternary and Tertiary aquifer system introduced by English (2018). The range of values shown from the aquifer test data in **Table 4**; published literature values; and findings that the Tertiary sediments in the Bozeman Fan subarea are generally less conductive than surrounding basin-fill and sedimentary rock aquifer subareas (Sutherland, 2023), support the recommended property values shown **Figure 6** and **Table 3**.

#### 5.0 Drawdown and Yield Test

An 8.0-hour drawdown and yield test was conducted on the Production Well, GWIC ID 335313. Water levels during the test were collected using an In-situ Leveltroll 400 transducer. The discharge rate was measured with a 4-inch diameter discharge pipe and averaged 275 gpm. Per ARM 36.12.121 and Form 633, background level and recovery data are not required for drawdown and yield tests on additional Production Wells. However, the data was collected and is found in submitted Form No. 633 for GWIC ID 335313 as part of Application No. 41H 30165312.



#### **Drawdown Data**

The 8.0-hour drawdown and yield test started on August 12, 2024, at 09:46 A.M. on the Production Well and is considered (t = 0) for the computation of drawdown. The maximum drawdown in the Production Well was 73.69 ft below the static water level (swl) of 16.06 ft below top of casing (btc), leaving approximately 114 ft of available water column above the bottom of the perforated interval adjusting for the well casing stick-up height of 2-ft.

### **6.0 Modeling Inputs**

Technical analyses in support of the following criteria assessment: adequacy of diversion, physical availability, and adverse effect (drawdown in existing wells) were modeled in AQTESOLV® (HydroSOLVE INC., 2007) using the following inputs:

- Cooley-Case (1973) solution for fully penetrating wells in an isotropic aquifer
- Well radius of 0.33 ft
- $T = 873 \text{ ft}^2/\text{day}$
- $S = 1.1 \times 10^{-4}$
- r/B;  $1/B = 1.7 \times 10^{-4}$ ;  $5.0 \times 10^{-4}$
- $\beta$ ;  $\beta/r = 7.8 \times 10^{-5}$ ;  $2.4 \times 10^{-4}$
- S'/Sy = 0.001
- L/b' = 0.001

The leakage parameters used to forward model multiple wells were adjusted from r/B and  $\beta$  shown in **Figure 6** to account for the distance of the Observation Well GWIC ID 335313 used to derive aquifer properties from the Production Well 335315 (r = 163 ft). Leakage parameters used to forward model one well were adjusted from r/B and  $\beta$  shown in **Figure 6** to account for the radius of the modeled well (0.3 ft). The storage ratio in the aquitard (S'/S<sub>y</sub>) of 0.001 was taken from **Figure 6** and verified as a representative input using the above estimated parameters, and representative vertical hydraulic conductivity and thickness of the aquitard. The dimensionless height of the capillary fringe (L/b') was taken from **Figure 6**. Monthly pumping schedules and boundaries used to complete technical analyses are identified in subsequent criteria sections.

## 7.0 Adequacy of Diversion Analysis

An evaluation of the potentially available water column remaining in the proposed wells was modeled in FWD:SOLV (HydroSOLVE INC., 2007) using the following pumping schedule:

• The monthly pumping and injection schedule identified in column 4 and column 7 of **Table 5** for one year of pumping.

Predicted theoretical drawdown for the proposed wells was modeled for the period of diversion using the monthly pumping schedule for each well identified in **Table 5**. The Applicant requests



298.40 AF, which was apportioned evenly to each Extraction and Injection Well based on the monthly pumping schedule provided by the Applicant.

Table 5: Proposed monthly extraction and injection schedule for the Applicant's wells.

	Extraction Schedule			Injection Schedule			
Month	GWIC ID 335313 and 335315			GWIC ID 335309 and 335811			
	Volume	Flow Rate	Flow Rate	Volume	Flow Rate	Flow Rate	
	(AF)	(gpm)	(gpm/well)	(AF)	(gpm)	(gpm/well)	
January	19.2	140.0	70.0	-19.2	-140.0	-70.0	
February	17.3	140.0	70.0	-17.3	-140.0	-70.0	
March	19.2	140.0	70.0	-19.2	-140.0	-70.0	
April	18.6	140.0	70.0	-18.6	-140.0	-70.0	
May	21.2	154.5	77.2	-21.2	-154.5	-77.2	
June	28.0	210.9	105.4	-28.0	-210.9	-105.4	
July	46.9	342.2	171.1	-46.9	-342.2	-171.1	
August	45.3	330.3	165.2	-45.3	-330.3	-165.2	
September	25.7	193.7	96.9	-25.7	-193.7	-96.9	
October	19.4	141.9	71.0	-19.4	-141.9	-71.0	
November	18.6	140.0	70.0	-18.6	-140.0	-70.0	
December	19.2	140.0	70.0	-19.2	-140.0	-70.0	
Total	298.40			-298.40			



As identified in **Table 6**, total drawdown is the sum of interference drawdown and predicted drawdown with well loss. Two extraction and two injection wells are proposed; interference drawdown was calculated using the pumping and injection schedule for each well. Predicted drawdown with well loss is calculated by dividing the predicted theoretical maximum drawdown by a well efficiency value. Well efficiency is calculated by dividing the maximum modeled drawdown for the aquifer test by the maximum observed drawdown of the aquifer test.


The aquifer adjacent to extraction wells GWIC ID 335313 and GWIC ID 335315 would experience a predicted total drawdown of 54.20 ft and 58.90 ft at the end of the first year, respectively. The remaining available water columns for GWIC ID 335313 and 335315 are approximately 134 and 159 ft, respectively. The remaining available water column is equal to the available drawdown above the bottom of the perforations minus total drawdown including interference drawdown.

**Table 6:** The remaining available water column for extraction wells.

Drawdown Estimate	<b>GWIC ID 335313</b>	<b>GWIC ID 335315</b>
Total Depth at Bottom of Perforated Interval (ft btc) <sup>1</sup>	204	234
Pre-Test Static Water Level (ft btc)	16.06	16.05
Available Drawdown Above Bottom of Perforations (ft)	188	218
Aquifer Test Observed Drawdown (ft)	73.69	87.86
Modeled Drawdown Using Average Aquifer Test Rate (ft)	81.00	77.00
Well Efficiency (%)	100	88
Predicted Theoretical Maximum Drawdown from assumed monthly pumping schedule (ft)	52.00	52.00
Predicted Drawdown with Well Loss (ft)	52.00	59.33
Interference Drawdown (ft)	2.20	-0.40
Total Drawdown (ft)	54.20	58.90
Remaining Available Water Column (ft)	134	159


<sup>&</sup>lt;sup>1</sup>The total well depth measuring point (bgs) was adjusted to the top of well casing based on a 2-foot stickup reported on the well logs.





**Figure 7**: Cooley-Case (1973) time-drawdown plot of the predicted theoretical drawdown in the extraction wells at the end of the first year of the assumed monthly pumping schedule.





**Figure 8**: Cooley-Case (1973) time-drawdown plot of the predicted theoretical drawdown in GWIC ID 335313 (dotted line) and GWIC ID 335315 (solid line) including interference drawdown at the end of the first year of the assumed monthly pumping schedule.

## 8.0 Physical Availability Analysis

An evaluation of groundwater availability in the source aquifer for the purpose of evaluating physical and legal availability was done by calculating groundwater flux through a zone of influence (ZOI) corresponding to the 0.01-foot drawdown contour. The 0.01-foot drawdown contour was modeled in AQTESOLV<sup>®</sup> (HydroSOLVE INC., 2007) using the following pump schedule and boundaries:

 Constant pumping rate of 240.7 gpm and -240.7 gpm for the Extraction and Injection Wells, respectively, for one year of pumping.

The normalized pumping rate required to produce the adjusted annual volume for the Extraction and Injection Wells is 240.7 gpm and -240.7 gpm, respectively. As shown in **Figure 9**, the 0.01-foot drawdown has an average width of approximately 14,000 ft perpendicular to direction of



groundwater flow to the northwest and is truncated to the East Gallatin River. **Appendix A** provides a list of groundwater rights that are within the 0.01-foot drawdown contour.

The calculation for groundwater flux (Q) through the delineated area is given by Eq. 1 and is 122,220 ft<sup>3</sup>/day or 1,024 AF/year:


Q = TWi

where:

 $T = Transmissivity = 873 ft^2/day$ 

W = Width of Zone of Influence = 14,000 ft

i = Groundwater gradient (English (2018); Sutherland (2023)) = 0.01 ft/foot



**Figure 9:** 0.01-foot and 1-foot drawdown contour and water rights (active, severed) within each contour extent for Permit Application No. 41H 30165312.





## 9.0 Adverse Effect Analyses

Using the Applicant's proposed pump schedule and associated annual volume, potential impacts to existing water rights are evaluated by modeling drawdown in nearby wells and net depletions to surface water(s).

#### 9.1 Groundwater - Drawdown in Existing Wells

The drawdown in existing wells was modeled in AQTESOLV® (HydroSOLVE, Inc., 2007) using the following pump schedule and boundaries:

• The monthly pumping and injection schedule identified in column 4 and column 7 of **Table 5** assigned to the Extraction and Injection Wells for five years of pumping.

The drawdown is the largest at the end of July of the fifth year using the proposed pumping schedule. As identified in **Figure 9**, the 1-foot drawdown contour extends to a maximum of approximately 4,100 ft from the Extraction Wells at the end of July of the fifth year of pumping. The 1-foot drawdown contour includes 13 water rights that are predicted to experience drawdown equal to or greater than one foot (**Appendix B**).

#### 9.2 Surface Water - Net Depletion

Pursuant to *Montana Trout Unlimited v. DNRC*, 2006 MT 72, 331 Mont. 483, 133 P.3d 224, the DNRC recognizes the connection between surface water and groundwater, and the effect of <u>prestream capture</u> and <u>induced infiltration</u> on surface waters.

Net depletions to surface water depend on propagation of drawdown to areas of the aquifer from which water can be captured. Captured water consists of two possible sources – a reduction in the natural discharge (outflow) rate of groundwater from the aquifer (pre-stream capture) or an increase in the natural/artificial recharge (inflow) rate to the aquifer (e.g. induced infiltration). Two important assumptions are made when evaluating net depletions: first the stream and underlying aquifer remain hydraulically connected by a continuous saturated zone, and second, the stream does not become dry. In addition, net depletion is not a function of groundwater flow rate or direction (Theis, 1938; Leake, 2011) and drawdown from pumping can propagate through the entire thickness of the confining layer to overlying aquifers or surface waters (Konikow and Neuzil, 2007).

As such, net depletions are identified for hydraulically connected surface water sources, not including ditches or ephemeral streams. Net depletion is equal to consumption for proposed groundwater use and is described as the calculated volume, rate, timing, and location of reductions to surface water that are offset by return flows (non-consumed water). Net depletion is evaluated by 1) quantifying the consumed volume associated with the proposed use; 2) identifying hydraulically connected surface waters; and 3) calculating the monthly rate and timing of net depletions to affected surface water(s).



#### 1. Consumed Volume

Consumed groundwater does not return to the source aquifer. Consumed volume depends on the proposed use and its associated percentage of known consumption. Depletion is assumed to be equivalent to consumption on an annual basis unless return flows do not accrete to the potentially affected surface water.

Monthly consumption for irrigation, not including turf grass, can be calculated using ARM 36.12.115 irrigation standards and associated efficiency values or the net irrigation requirement (dry year 80% chance) calculated using the USDA Natural Resources Conservation Service (NRCS) IWR program with inputs consistent with DNRC consumptive use rules in ARM 36.12.1902. Monthly consumption for irrigation of turf grass (lawns) is calculated using either a minimum efficiency value of 70% and ARM 36.12.115 lawn and garden standards or the net irrigation requirement from IWR with inputs consistent with DNRC (2010) Consumptive Use Methodology for turf grass.

Consumption for other purposes are listed in **Table 7** and are based on the results of studies by Kimsey and Flood (1987), Vanslyke and Simpson (1974), Paul, Poeter, and Laws (2007), DNRC (2018), wastewater treatment method, operation of systems, or DNRC policy. Net evaporation is calculated using gridded monthly net evaporation values and methodologies associated with DNRC (2023).

**Table 7:** Percent consumption by purpose.

Purpose	Method of treatment/Use	Consumed
Domestic/Municipal*/Commercial/Institutional	Individual drainfields	10%
Domestic/Municipal*/Commercial/Institutional	Central treatment facility with minimal consumption	5%
Domestic/Municipal*/Commercial/Institutional	Evaporation basin or land application	100%
Municipal Use for Municipality	Variable	100%
Water Marketing/Agriculture Spraying/Stock Water/some Industrial Uses	Variable	100%
Geothermal	Open-loop geothermal cooling system with pumping and reinjection wells.	0%
Commercial/Industrial	Aggregate Washing – construction standard for moisture allowed in the finished aggregate product.	5%
Commercial	Snow Making – depends on time of day, machine, weather at time of operation, etc.	10-30%
Fisheries, Recreation, Storage for Irrigation	Net evaporation off reservoir surface, gridded monthly net evaporation values and	AF/acre

<sup>\*</sup>Municipal use for a non-municipality, such as a Water District.



#### **WSB Findings**

For the subject application, the proposed project includes an open-loop geothermal cooling system, and therefore, will have no consumed volume.

#### 2. Hydraulically Connected Surface Water(s) and Location of Net Depletion

Potentially affected surface waters in a net depletion evaluation are identified by their hydraulic connection, both direct and indirect, to the source aquifer of a proposed groundwater diversion. Hydraulic connection depends on the depth to groundwater beneath the beds of surface waters, connection between deep and overlying shallow aquifers, vertical gradients, and can vary along a reach and with time of year.

Procedures for evaluating hydraulic connection and identifying one or more potentially affected surface water(s) for a proposed well in an unconfined/confined aquifer or regional bedrock aquifer can be found in DNRC (2018) and DNRC (2019), respectively. Net depletion is apportioned between multiple potentially affected surface waters generally following procedures described in Section 3.2 of a guidance document developed by the Province of British Columbia (2016) for determining the effect of groundwater diversion on specific streams.

Following protocols in DNRC (2018) **Table 8** identifies published information used to assess hydraulically connected surface water(s). Not all data may be available for each project and is noted as "NA" when that occurs.

**Table 8:** Published information used to identify hydraulically connected surface water(s).

Published Information	Surface Water Source	
r abilistica illiottilation	East Gallatin River	
USGS National Hydrographic Dataset (NHD) <sup>1</sup>	Perennial	
USGS PROSPER Dataset <sup>2</sup>	Perennial (0.9+)	
MBMG GWIC wells, less than 50 ft deep, within 1,000 ft of surface water, static water levels above or within 10 ft of elevation of stream bed (DNRC, 2018) <sup>3</sup>	Mapped GWIC ID's 91805, 91796, 91789, 151869, 151868, 151867, 151871, 165050, 91779 (Figure 13)	
Published Water Table Maps, Publications, Previous Water Rights, etc. <sup>4</sup>	Sutherland (2023), Madison (2022), Provisional Permit No. 41H 30115965	
Gridded National Soil Survey Geographic Database <sup>5</sup>	Hydric conditions mapped along river (Figure 13)	
Aerial imagery	Wet channel (NAIP 2013-2024)	
Affidavits, photographs, etc.	NA	

<sup>&</sup>lt;sup>1</sup> Review NHD to identify perennial, intermittent, and ephemeral classifications for surface water sources most proximal to the proposed diversion(s).

<sup>&</sup>lt;sup>2</sup> USGS PROSPER probability of streamflow permanence (greater than 50 percent of the time it flows).

<sup>&</sup>lt;sup>3</sup> Per DNRC (2018) hydraulic connection of individual stream reaches to groundwater is evaluated by comparing streambed elevations to static ground water elevations measured in MBMG GWIC wells less than 50 ft deep and within 1,000 ft of surface water or from published water table maps. Surface water within that area is considered




hydraulically connected to the unconfined aquifer if static ground water elevations are above or within 10 ft of the elevation of the stream bed.

<sup>4</sup>No water table maps available.

#### **WSB Scientific Findings**

Based on the review of the published information in **Table 8**, the source aquifer is hydraulically connected to the East Gallatin River, a perennial surface water source. As identified in **Figure 13** the starting point of the depleted reach starts along the northern side of the NWSESW of Section 23, Township 01 South, Range 05 East, Gallatin County.



**Figure 13:** Information used to assess hydrologic connection and location of starting point of the depleted reach on the East Gallatin River for Permit Application No. 41H 30165312.

<sup>&</sup>lt;sup>5</sup> Review Gridded National Soil Survey Geographic Database to identify hydric soils or shallow water tables near surface water sources.





#### 3. Rate and Timing of Depletions

Evaluations of the rate and timing of depletions caused by pumping are based on the basic concept that groundwater pumping eventually is offset by an equivalent increase in recharge or decrease in discharge (Theis, 1940; Leake et al., 2008), a process defined as capture by Lohman (1972). Capture occurs as drawdown propagates to surface water and areas of phreatophyte vegetation (areas of groundwater discharge) that takes water directly from groundwater. In the absence of credible evidence to the contrary, capture of ET by phreatophytes is neglected and net depletion is assumed to equal total capture. This assumption is justified because published estimates for conditions common in Montana alluvial valleys indicate capture of ET generally is less than 10 percent of total capture (Xunhong, 2006). Capture of ET in ephemeral drainages may be significant and will be evaluated on an application-by-application basis.

The rate and timing of net depletion caused by pumping may be modeled using a variety of analytical and numerical models selected to fit site-specific conditions and needs. Simple models including the Alluvial Water Accounting System (AWAS), the Well Pumping Depletion Model (WPDM) or FWD:SOLV (HydroSOLVE, Inc. 2024) typically are used by DNRC to model depletions to one source with simple aquifer boundaries. Adjustments may be made for more complex conditions or multiple sources using methods like those described by Contor (2011), analytical models by Hunt (2003) and Butler et al. (2001) or a superposition numerical groundwater flow model.

Modeling may not be necessary in some situations such as where a proposed use is constant year-round, the source aquifer is confined, or the distance to potentially affected stream reaches is greater than one mile. Modeling net depletions can be simplified if the proposed place of use is located the same relative distance from the potentially affected surface water as the proposed wells and all non-consumed water infiltrates the source aquifer and returns to the potentially affected surface water as return flows. Under those simplifying assumptions, net depletion can be modeled based on withdrawal of the monthly consumed amounts. Otherwise, net depletion by the full withdrawals and return flows need to be modeled separately with net depletion calculated as depletion minus return flows.

The proposed use is geothermal, water will be extracted and injected simultaneously. There would be no consumed volume, and therefore, no timing of net depletions was completed as part of Application No. 41H 30165312.

#### Review

This document has been reviewed on June 30, 2025 in accordance with Category 7 of <u>DNRC's Water Sciences Bureau Minimum Standards of Review</u>, Version 2, February 2024.

#### References

Alluvial Water Accounting System (AWAS), 2003. Integrated Support System at Colorado State University, http://www.ids.colostate.edu/projects.php?project=awas.

Butler, J.J., Zlotnik, V.A., and Tsou, M.S. 2001. Drawdown and stream depletion produced by pumping in the vicinity of a partially penetrating stream. Ground Water 39 (5), 651–659.

Cooley, R.L. and C.M. Case, 1973. Effect of a water table aquitard on drawdown in an underlying pumped aquifer, Water Resources Research, vol. 9, no. 2, pp. 434-447.

Contor, B.A. 2011. Adaptation of the Glover/Balmer/Jenkins Analytical Stream-Depletion Methods for No-Flow and Recharge Boundaries, Idaho Water Resources Research Institute, Technical Completion Report, 15 p.

Cooper, H.H. and C.E. Jacob, 1946. A generalized graphical method for evaluating formation constants and summarizing well field history, Am. Geophysical Union Trans., vol. 27, pp. 526-534.

Custer, S.G., Donohue, D., Tanz, G., Nichols, T., Sill, W., and Wideman, C. 1991. Final report of research results: Ground water potential in the Bozeman-Fan Subarea, Gallatin County, Montana: Bozeman, Mont., Montana State University, 142 p.

DNRC, 2010. Consumptive Use Methodology – Turf Grass (New Projects). March 23, 2010.

DNRC, 2018. Technical Memorandum: Standard Practices for Net Surface Water Depletion from Ground Water Pumping. July 6, 2018.

DNRC, 2019. Technical Memorandum: Physical and Legal Availability of Ground Water, dated April 22, 2019.

DNRC, 2023. Technical Memorandum: Pond and Wetland Evaporation/Evapotranspiration, dated June 7, 2023.

English, A.R. 2018, Evaluation of potential high-yield groundwater development in the Gallatin Valley, Gallatin County, Montana: Montana Bureau of Mines and Geology Open-File Report 698, 22 p., 2 sheets.

Groundwater Information Center (GWIC), Montana Bureau of Mines and Geology, Accessed (2025). http://mbmggwic.mtech.edu/.

Hackett, O.M., Visher, F.N., McMurtrey, R.G., and Steinhilber, W.L., 1960, Geology and groundwater resources of the Gallatin Valley, Gallatin County, Montana: U.S. Geological Survey Water Supply Paper 1482, 282 p., plates 1–11, 11 p.





Harbaugh, A.W. 2000. MODFLOW-2000, the U.S. Geological Survey Modular Groundwater Model—User Guide to Modularization Concepts and the Groundwater Flow Process. U.S. Geological Survey Open File Report 00-92.

Hubbel, J.M., C.W. Bishop, G.S. Johnson, and J.G. Lucas, 1997. Numerical ground-water flow modeling of the Snake River Plain Aquifer using superposition technique, Ground Water, V. 35, N. 1, p. 59-66.

Hunt, B., 2003. Unsteady stream depletion when pumping from semi-confined aquifer. Journal of Hydrologic Engineering 8, no. 1: 12-19.

HydroSOLVE, Inc. 2007. AQTESOLV<sup>®</sup> for Windows, v.4.5. written by G.M. Duffield, http://www.aqtesolv.com/.

HydroSOLVE, Inc. 2024. FWD: SOLV Predictive Modeling Software v.2. written by G.M. Duffield. http://www.aqtesolv.com/fwdsolv.htm

Johnson, G.S. and D.M. Cosgrove, 1999. Application of steady state response ratios to the Snake River plain aquifer. Idaho Water Resources Research Institute, University of Idaho, Moscow, ID, 26 pp.

Kimsey, D.W. and P.K. Flood. 1987. Domestic consumptive use, technical memorandum to the Chief Engineer of the State of Colorado, 16 p.

Konikow, L. F. *and* C. E. Neuzil. 2007. A method to estimate groundwater depletion from confining layers, Water Resources Research., 43, *W07417*, *doi:*10.1029/2006WR005597.

Kruseman, G.P., and de Ridder, N.A. 1990. Analysis and Evaluation of Pumping Test Data. Publication 47. International Institute for Land Reclamation and Improvement, Wageningen, The Netherlands.

Leake, S. A., Pool, D. R., and Leenhouts, J. M. 2008. Simulated effects of ground-water withdrawals and artificial recharge on discharge to streams, springs, and riparian vegetation in the Sierra Vista Subwatershed of the Upper San Pedro Basin, southeastern: U.S. Geological Survey Scientific Investigations Report 2008-5207, 14 p. http://pubs.usgs.gov/sir/2008/5207/sir2008-5207.pdf.

Leake, S.A. 2011. Capture – rates and direction of groundwater flow don't matter! Groundwater, Vol. 49, No. 4, p. 456 – 458.

Lohman, S.W. 1972. Definitions of selected ground-water terms: Revisions and conceptual refinements, U.S. Geological Survey Water Supply Paper, 1988, 21 p., <a href="http://pubs.usgs.gov/wsp/wsp">http://pubs.usgs.gov/wsp/wsp</a> 1988/pdf/wsp 1988.pdf.

Lopez, D.A. 2002. Geologic map of the Conrad 30' x 60' quadrangle, north-central Montana: Montana Bureau of Mines and Geology Open-File Report 444, 11 p., 1 sheet, scale 1:100,000, https://mbmg.mtech.edu/pdf 100k/conrad.pdf

Madison, J.P. 2022. Potentiometric surface in Gallatin, Lower Madison, Lower Jefferson, and Upper Missouri River Valleys within parts of Madison and Gallatin Counties, Montana: Montana Bureau of Mines and Geology Montana Ground-Water Assessment Atlas 8-04, 1 sheet, scale 1:100,000.





Michalek, T. and Sutherland M. 2020. Hydrogeologic investigation of the Four Corners area, Gallatin County, Montana. Montana Bureau of Mines and Geology Open-File Report 735.

Moench, A.F., 1994. Specific yield as determined by type-curve analysis of aquifer-test data: Groundwater, v. 32, No. 6, p. 949-957.

Natural Resources Conservation Service (NRCS), 2003. Irrigation Water Requirement (IWR) computerprogram,

http://www.nrcs.usda.gov/wps/portal/nrcs/detailfull/national/water/manage/?cid=stelprdb1044890.

Neuman, S.P. 1974. Effect of partial penetration on flow in unconfined aquifers considering delayed gravity response, Water Resources Research, vol. 10, no. 2, pp. 303-312.

Soil Survey Staff, Natural Resources Conservation Service, United States Department of Agriculture. Soil Series Classification Database. Available online. Accessed June 2025.

Sutherland, M. 2023. Hydrogeologic investigation of the Belgrade-Manhattan area, Gallatin County, Montana: Superposition groundwater modeling report: Montana Bureau of Mines and Geology Open-File Report 756, 52 p.

Paul, W., Poeter, E., and R Laws. 2007. Consumptive loss from and individual sewage disposal system in a semi-arid mountain environment. Colorado Water, Newsletter of the Water Center of Colorado State University, August/September 2007, Volume 24, Issue 4.

Theis, C.V., 1935. The relation between the lowering of the piezometric surface and the rate and duration of discharge of a well using groundwater storage, Am. Geophys. Union Trans., vol. 16, pp. 519-524.

U.S. Geological Survey (USGS0, USGS National Hydrographic Dataset, accessed (2025), https://landscape11.arcgis.com/arcgis/services/USA Soils Hydric Class/ImageServer

U.S. Geological Survey (USGS), Probability of streamflow permanence model (PROSPER): A spatially continuous model of annual streamflow permanence throughout the Pacific Northwest, accessed (2025), StreamStats web application. <a href="https://streamstats.usgs.gov/ss/">https://streamstats.usgs.gov/ss/</a>

Well Pumping Depletion Model (WPDM) software, 2001. Western Water Consulting, Inc. Littleton, Colorado, <a href="http://westernwaterconsulting.com/WPDM.htm">http://westernwaterconsulting.com/WPDM.htm</a>.

Wolock, D. 2003. Flow characteristics at U.S. Geological Survey stream gages in the conterminous United States. USGS Open-File Report: 2003-146,

https://water.usgs.gov/GIS/metadata/usgswrd/XML/qsitesdd.xml#stdorder.

Vanslyke, G. and H. Simpson. 1974. Consumptive use of water by homes utilizing leach fields for sewage disposal, technical memorandum by the Colorado Division of Water Resources, 5 p.

Xunhong, C. 2006. Groundwater evapotranspiration captured by seasonally pumped wells in river valleys, Journal of Hydrology, V. 318, Issues 1-4, p. 334-347.



Appendix A: Groundwater Rights within Area of Potential Impact



WRNUMBER	ALL_OWNERS
41H 30127867	FLIR SYSTEMS INC
41H 100672 00	VANIMAN, CECILIA R TRUST; VANIMAN, DONALD D TRUST
41H 80659 00	CRESTVIEW LAKE LLC
41H 113364 00	CECILIA R VANIMAN; DONALD D VANIMAN
41H 115518 00	HIDDEN VALLEY OWNER LLC
41H 115515 00	HIDDEN VALLEY OWNER LLC
41H 40130 00	HIDDEN VALLEY OWNER LLC
41H 39225 00	HIDDEN VALLEY OWNER LLC
41H 115516 00	HIDDEN VALLEY OWNER LLC
41H 115517 00	HIDDEN VALLEY OWNER LLC
41H 42480 00	DALE LILLEJORD
41H 59866 00	LYNN C WINDHAM
41H 60759 00	MICHAEL D COK
41H 90747 00	D2BZ1 LLC
41H 108859 00	JULIE OGHIGIAN; MATTHEW OGHIGIAN
41H 117208 00	WOODY LAURIE BATES REVOCABLE TRUST DATED 4/4/95
41H 96799 00	9019 LLC
41H 30125032	KEVIN KENT
41H 30000996	SARAH HALL
41H 30063822	MICHAEL D COK
41H 30045047	CRESTVIEW LAKE LLC
41H 108896 00	JULIE OGHIGIAN; MATTHEW OGHIGIAN
41H 30162630	KAMERON KELSEY; SALLY KELSEY
41H 25895 00	ABIGAIL L MINFORD; BENJAMIN D PRENTISS
41H 100708 00	COSTCO WHOLESALE
41H 107598 00	GALLATIN CENTER LTD PRTNRSHP
41H 116445 00	BOZEMAN MONTANA HOLDINGS LLC
41H 100715 00	NINETEENTH STREET PARTNERSHIP
41H 30162633	KAMERON KELSEY; SALLY KELSEY
41H 30045048	CRESTVIEW LAKE LLC
41H 39213 00	TRACEY PETER REVOCABLE TRUST
41H 40108 00	S&S DAVIS LLC
41H 30069875	JOSHUA N GRUENBERG; MIKARON F GRUENBERG
41H 116444 00	BOZEMAN MONTANA HOLDINGS LLC
41H 30103555	PETER E GARCIA; TASHA D GARCIA
41H 36789 00	MARY ELLEN BRUHN
41H 80669 00	CAROLYN J TATARKA; RAYMOND J TATARKA
41H 107475 00	JOHN HECHT
41H 107601 00	GALLATIN CENTER LTD PRTNRSHP
41H 113372 00	JOHN D HECHT; MARY HECHT
41H 30148873	KRUSE, KELLY R LIVING TRUST; KRUSE, PATRICIA A LIVING TRUST
41H 40413 00	ROBERT A WHITTMYER; SHARON WHITTMYER
41H 79512 00	CHRISTINA RIFFLE; SCOTT RIFFLE



41H 93745 00	BOB DAVIS; ROXI M DAVIS
41H 30149453	BARTIMCO PROPERTIES LLC
41H 111644 00	JOHN D HECHT; MARY HECHT
41H 139045 00	HEMINGWAY, PATRICK & CAROL T TRUST
41H 6741 00	BOZEMAN, CITY OF
41H 30020414	FHG CONSTRUCTION INC
41H 42468 00	JOHN D HECHT
41H 32752 00	BARBARA F MCLAUGHLIN
41H 30120927	MICHAEL W DINKINS
41H 114302 00	SUSAN R TAYLOR
41H 138 00	NICOLE R BOWER; SPENCER J BOWER
41H 104756 00	ORVILLE WAY LLC
41H 30067919	KENNETH WIRTZ
41H 30106534	STEVEN SMITH
41H 30161488	BURT HAMNER; EMILY MORRILL
41H 39221 00	LARRY D KIRKPATRICK; KAREN S LANZ
41H 47327 00	BMCH RENTALS LLC
41H 96656 00	BRANDON BEAMER
41H 30170704	RICHARD A NOONAN; LEAH J REUTER; RICHARD J REUTER; CAROLYN G WIDMAN
41H 111645 00	FIRST INTERSTATE BANK OF COMMERCE
41H 14010 00	4 CLOVERS LLC; OREILLY PARTNERSHIP LLC; SEVEN OX SEVEN LLC
41H 39746 00	LANTANA CORPORATION
41H 45560 00	BOZEMAN HEALTH URGENT CARE LLC
41H 53161 00	RUSSELL HOSNER LLC
41H 106106 00	KELLER SUPPLY CO
41H 30105693	MONTANA, STATE OF DEPT OF TRANSPORTATION
41H 30047249	CRESTVIEW LAKE LLC
41H 30047250	CRESTVIEW LAKE LLC
41H 103121 00	JERRI K ALEXANDER; LOREN C ALEXANDER
41H 31114 00	BOZEMAN ELEMENTARY DISTRICT NO. 7
41H 95370 00	FETTIS, WILLIAM J TRUST
41H 19409 00	DALLAS J PEUSE
41H 103232 00	G AND S FAMILY TRUST
41H 89705 00	KENNETH WIRTZ
41H 99364 00	SANDAN LLC
41H 59783 00	VANIMAN, CECILIA R TRUST; VANIMAN, DONALD D TRUST
41H 23019 00	DAROLD E BRUHN; NORMA J BRUHN
41H 23316 00	JAMES D BRUHN
41H 104707 00	VALLEY CENTER LTD PRTNRSHP
41H 114952 00	BOZEMAN 6 RE LLC
41H 16414 00	WALDO E KUCHLING
41H 17696 00	FLOYD MATHISON
41H 17715 00	K SCOTT HALL; TERESA C HALL
41H 18751 00	KEVIN KENT



41H 21416 00	JOHN WESEN
41H 22014 00	ORR F MARY; MICHAEL J SWEENEY
41H 22940 00	FIVEFOLD HOLDINGS LLC
41H 23687 00	MARY S SEED; RAYMOND B SEED
41H 28957 00	JOSEPHINE Z HOWE; ROBERT H HOWE
41H 31360 00	LAURA F BARRY; STEPHEN R BARRY
41H 32618 00	LINDA K ANDERSON
41H 34684 00	JOSHUA C CAMPBELL
41H 36426 00	RONALD D GREEN; RUTH A GREEN
41H 37428 00	BOZEMAN ELEMENTARY DISTRICT NO. 7
41H 40139 00	DEBRA A GILL; MICHAEL L GILL
41H 44265 00	CRAYTON, ROBERT F & CYNTHIA REVOCABLE LIVING TRUST
41H 44266 00	CRAYTON, ROBERT F & CYNTHIA REVOCABLE LIVING TRUST
41H 49600 00	PATTERSON PLACE LLC
41H 55200 00	KEVIN J FRANK
41H 58361 00	TODD J PIERONI
41H 75642 00	ROBERT L ADAMS; JOHN L MARCELLA; PAMELA J MARCELLA
41H 9574 00	DYPEX INC
41H 30149451	BARTIMCO PROPERTIES LLC
41H 89647 00	RR1045 LLC
41H 104721 00	ANITA L SAUNDERS; R ED SAUNDERS
41H 110100 00	CARRIE MCCLAUGHRY; TOBIAS H MCCLAUGHRY
41H 30047450	CHAD MUESKE
41H 30048611	SOUTH HAMILTON COURT CONDO ASSN
41H 30105386	TAC INVESTMENTS LLC
41H 30043137	CATKIN CONDOMINIUM OWNERS ASSN INC
41H 30147910	ARMKNECHT STEVEN R REVOCABLE LIVING TRUST
41H 100809 00	AMERICAN SIMMENTAL ASSOC INC
41H 30065502	NATHAN S NAPRSTEK
41H 30161243	BRIAN LAPKA
41H 30161244	BRIAN LAPKA
41H 73705 00	ROGER S KIRK
41H 30115761	DERRICK SALVESON; JYLISSA SALVESON
41H 40136 00	CASNURSPROP LLC
41H 108962 00	RIVERGLEN CONDOMINIUMS
41H 30050963	BOZEMAN SCHOOL DIST 7
41H 114948 00	BOZEMAN 6 RE LLC
41H 11915 00	CASNURSPROP LLC
41H 139905 00	ROBERT D LANE; THOMAS E LANE
41H 30005476	JAMES ARMSTRONG; NINA ARMSTRONG
41H 30010468	KINGMA REVOCABLE TRUST
41H 30011859	SANDAN LLC
41H 30012764	SANDAN LLC
41H 30013046	SANDAN LLC



# Groundwater Permit Technical Analyses Report-Part A Application No. 41H 30165312 Bozeman Regional Office Gallatin County

41H 30016832 RICHTER, DELBERT L & DENA S REVOCABLE LIVING TRUST  41H 30021277 P ANDREW VAN ORDEN  41H 30021278 C&C MANAGEMENT LLC  41H 30023647 JASON A DARROW  41H 30024622 BAXTER MEADOWS MASTER COMMUNITY ASSN INC  41H 30024623 BAXTER MEADOWS MASTER COMMUNITY ASSN INC  41H 30025056 SANDAN LLC  41H 30028964 BRENT J SCHMOLL  41H 30029336 TURNQUIST REVOCABLE TRUST  41H 30030867 GALLATIN COUNTY SCHOOL DISTRICT # 7  41H 30030868 GALLATIN COUNTY SCHOOL DISTRICT # 7  41H 30031011 JACQUELINE J REYGERS; LODY E REYGERS  41H 30041929 HENRY J BOUMA
41H 30021278 C&C MANAGEMENT LLC  41H 30023647 JASON A DARROW  41H 30024622 BAXTER MEADOWS MASTER COMMUNITY ASSN INC  41H 30024623 BAXTER MEADOWS MASTER COMMUNITY ASSN INC  41H 30025056 SANDAN LLC  41H 30028964 BRENT J SCHMOLL  41H 30029336 TURNQUIST REVOCABLE TRUST  41H 30030867 GALLATIN COUNTY SCHOOL DISTRICT # 7  41H 30030868 GALLATIN COUNTY SCHOOL DISTRICT # 7  41H 30031011 JACQUELINE J REYGERS; LODY E REYGERS
41H 30023647 JASON A DARROW  41H 30024622 BAXTER MEADOWS MASTER COMMUNITY ASSN INC  41H 30024623 BAXTER MEADOWS MASTER COMMUNITY ASSN INC  41H 30025056 SANDAN LLC  41H 30028964 BRENT J SCHMOLL  41H 30029336 TURNQUIST REVOCABLE TRUST  41H 30030867 GALLATIN COUNTY SCHOOL DISTRICT # 7  41H 30030868 GALLATIN COUNTY SCHOOL DISTRICT # 7  41H 30031011 JACQUELINE J REYGERS; LODY E REYGERS
41H 30024622 BAXTER MEADOWS MASTER COMMUNITY ASSN INC 41H 30024623 BAXTER MEADOWS MASTER COMMUNITY ASSN INC 41H 30025056 SANDAN LLC 41H 30028964 BRENT J SCHMOLL 41H 30029336 TURNQUIST REVOCABLE TRUST 41H 30030867 GALLATIN COUNTY SCHOOL DISTRICT # 7 41H 30030868 GALLATIN COUNTY SCHOOL DISTRICT # 7 41H 30031011 JACQUELINE J REYGERS; LODY E REYGERS
41H 30024623 BAXTER MEADOWS MASTER COMMUNITY ASSN INC 41H 30025056 SANDAN LLC 41H 30028964 BRENT J SCHMOLL 41H 30029336 TURNQUIST REVOCABLE TRUST 41H 30030867 GALLATIN COUNTY SCHOOL DISTRICT # 7 41H 30030868 GALLATIN COUNTY SCHOOL DISTRICT # 7 41H 30031011 JACQUELINE J REYGERS; LODY E REYGERS
41H 30025056       SANDAN LLC         41H 30028964       BRENT J SCHMOLL         41H 30029336       TURNQUIST REVOCABLE TRUST         41H 30030867       GALLATIN COUNTY SCHOOL DISTRICT # 7         41H 30030868       GALLATIN COUNTY SCHOOL DISTRICT # 7         41H 30031011       JACQUELINE J REYGERS; LODY E REYGERS
41H 30028964 BRENT J SCHMOLL 41H 30029336 TURNQUIST REVOCABLE TRUST 41H 30030867 GALLATIN COUNTY SCHOOL DISTRICT # 7 41H 30030868 GALLATIN COUNTY SCHOOL DISTRICT # 7 41H 30031011 JACQUELINE J REYGERS; LODY E REYGERS
41H 30029336 TURNQUIST REVOCABLE TRUST 41H 30030867 GALLATIN COUNTY SCHOOL DISTRICT # 7 41H 30030868 GALLATIN COUNTY SCHOOL DISTRICT # 7 41H 30031011 JACQUELINE J REYGERS; LODY E REYGERS
41H 30030867 GALLATIN COUNTY SCHOOL DISTRICT # 7 41H 30030868 GALLATIN COUNTY SCHOOL DISTRICT # 7 41H 30031011 JACQUELINE J REYGERS; LODY E REYGERS
41H 30030868 GALLATIN COUNTY SCHOOL DISTRICT # 7 41H 30031011 JACQUELINE J REYGERS; LODY E REYGERS
41H 30031011 JACQUELINE J REYGERS; LODY E REYGERS
41H 30041929 HENRY J BOUMA
12.1.000 12.000
41H 30042369 GALLATIN COUNTY SCHOOL DISTRICT # 7
41H 30042370 GALLATIN COUNTY SCHOOL DISTRICT # 7
41H 30044488 URBAN VILLA HOMEOWNERS ASSN
41H 30145989 LACEY BUCZALA; ROBERT BUCZALA
41H 361 00 RUSSELL HOSNER LLC
41H 362 00 RUSSELL HOSNER LLC
41H 5099 00 TATARKA FAMILY FARMS LLC
41H 636 00 RONALD K LEWIS



# Appendix B: Groundwater Rights Within 1-foot Drawdown Contour



		Well Depth	Static Water	Drawdown (ft)	Available Water Column (ft)
WRNUMBER	ALL_OWNERS	(ft)	Level (ft)		2.5
41H 30161243	BRIAN LAPKA	52	17	8.8	26
	PETER E GARCIA; TASHA	63	23	1.7	38
41H 30103555	D GARCIA				
41H 30041929	HENRY J BOUMA	60	16	2.6	41
41H 107475 00	JOHN HECHT	60	17	1.2	42
	BARTIMCO PROPERTIES	72	5	17.2	50
41H 30149453	LLC	72	J	17.2	
	JOHN D HECHT; MARY	60	6	1.4	53
41H 111644 00	HECHT	60	О	1.4	
41H 30065502	NATHAN S NAPRSTEK	82	25	1.2	56
	VANIMAN, CECILIA R				62
	TRUST; VANIMAN,	74	10	1.6	
41H 59783 00	DONALD D TRUST				
	MONTANA, STATE OF				65
	DEPT OF	80	10	5	
41H 30105693	TRANSPORTATION				
	BARTIMCO PROPERTIES			6.0	72
41H 30149451	LLC	88	9	6.9	
	CECILIA R VANIMAN;				86
41H 113364 00	DONALD D VANIMAN	100	12	1.6	
41H 30047450	CHAD MUESKE			1	
	VANIMAN, CECILIA R				
	TRUST; VANIMAN,			1.6	
41H 100672 00	DONALD D TRUST				



# **Groundwater Permit Technical Analyses Report – Part B**

# Department of Natural Resources and Conservation (DNRC or Department) Water Resources Division

Kendrew Ellis, Water Resource Specialist, Bozeman Regional Office

Application No.	41H 30165312	Proposed Point of Diversion	SWSESE Section 22, T1S, R5E, Gallatin County
Applicant	Barnard Construction		

#### Overview

This report is Part B of a two-part publication which analyzes data submitted by the Applicant in support of the above-mentioned water right application. This report provides technical analyses as required under the Administrative Rules of Montana (ARM) 36.12.1303 in support of the water rights criteria assessment as required in § 85-2-311, Montana Code Annotated (MCA).

This Groundwater Permit Technical Analyses Report – Part B contains the following sections:

Overview	1
Variances	2
1.0 Application Details	2
2.0 Surface Water Analysis of Depleted Surface Water	1
3.0 Area of Potential Impact Analysis of Depleted Surface Water	1
Review	2
References	2





#### **Variances**

A variance from the requirements found in ARM 36.12.121(3)(a) "pumping must be maintained throughout the duration of the test and the rate may not depart from the average pumping rate by more than 5%" was granted from the Bozeman Regional Office April 14, 2025. Multiple times throughout the first 1,620 minutes of the aquifer testing, the measured discharged fluctuated slightly more than 5% from the average measured discharge rate of 269.5 gpm. From 1,620 minutes until the end of the test, the pumping was maintained at a constant discharge rate and consistent drawdown was collected in both the Production and Observation Wells.

A variance from the requirements found in ARM 36.12.121(3)(e)(iii) "the testing procedures for a minimum eight-hour drawdown and yield test performed on any production well must follow (a), (d), and (h)" was also granted from the Bozeman Regional Office on April 14, 2025. During the first 16-minutes of the eight-hour drawdown and yield test, the discharge started at 225 gpm and was raised to up to approximately 275 gpm with an average measured discharge rate of 263.8 gpm. The discharge deviation greater than 5 % at the start of well testing is common, and the remainder of the pumping was maintained at a constant discharge rate. The requirements for drawdown at yield test under 3(e)(iii), specifically 3(d) and 3(h) were met.

A variance from the requirements found in ARM 36.12.121(3)(g) "to monitor background groundwater levels in the production well and observation well(s) at frequent intervals for at least two days prior to beginning the aquifer test according to From No. 633" was also granted from the Bozeman Regional Office on April 14, 2025. The background water levels in the Production Well and Observation Well 1 were collected two days prior to the day of aquifer testing. The water level difference in the Production Well on the day prior to the aquifer testing was 0.1 ft. The drawdown and recovery data in the Production Well and Observation Well 1 did not appear to be affected by any background level trends. The background level data collected for Observation Well 2 represented the start of the aquifer testing. However, clear interference drawdown was shown in Observation Well 2 and impacts from background levels were not recognizable.

A variance from the requirements found in ARM 36.12.121(3)(h) "water levels in the production well and/or observation well(s) must be reported with 0.01-foot precision according to the schedule specified on Form No. 633" was also granted from the Bozeman Regional Office on April 14, 2025. The Applicant does not follow minimum required time increment schedule for Observation Well 1 and 2 for first 60 minutes of data collection. The remainder of the data collection period fulfilled the requirements of 3(h) and is adequate for obtaining aquifer properties.

# 1.0 Application Details

The Applicant proposes to divert groundwater from 1/1 to 12/31 for non- consumptive geothermal use from two extraction well points of diversion (PODs) in the SWSESE Section 22,



T1S, R5E, Gallatin County (EX-1 and EX-2). The two injection wells for the project are located in SESWSE Section 22, T1S, R5E, Gallatin County (IN-1 and IN-2). The wells will divert a total 298.38 AF at a total flow rate of 550 GPM (275 GPM per well) from 1/1 to 12/31 to provide geothermal cooling for the commercial building in SESWSE and SWSESE Section 22 and NWNENE Section 27, T1S, R5E, all in Gallatin County, as seen in **Table 1** and **Figure 1**.

**Table 1.** Summary of the proposed use.

Source	Flow Rate	Diverted Volume	Consumed Volume	Purpose	Period of Use	Place of Use	Point(s) of Diversion	Period of Diversion
Groundwater	550 GPM	298.38 AF/yr	0 AF	Geothermal	1/1- 12/31	SESWSE & SWSESE Section 22, T1S, R5E, Gallatin County  NWNENE Section 27, T1S, R5E, Gallatin County	SWSESE Section 22, T1S, R5E, Gallatin County SWSESE Section 22, T1S, R5E, Gallatin County	1/1-12/31






Figure 1: Map of the Applicant's proposed POD on the source and proposed place of use by Water & Environmental Technologies dated 5/5/2025.





# 2.0 Surface Water Analysis of Depleted Surface Water

As net depletions to the surface water source are 0 AF, the Department did not find the physical availability of the surface water source for later comparison to downstream legal demands.

# 3.0 Area of Potential Impact Analysis of Depleted Surface Water

The Area of Potential Impact for this application is: The proposed use is non-consumptive, and a net depletion of 0 AF was identified for the hydraulically connected surface water. No area of potential impact for surface water was identified because no net depletion will occur.



Groundwater Permit Technical Analyses Report- Part B
Application No. 41H 30165312
Bozeman Regional Office
Gallatin County


### Review


This document has been reviewed by the Department on July 7, 2025.

# References


Department Standard Practice for Determining Physical Availability of Surface Water Department Standard Practice for Area of Potential Impact Analysis











# BURLINGTON NORTHERN RAILROAD RIGHT-OF-WAY



UULC LITIES UNDERGROUND LOCATION CENTER MONTANA ONE CALL CALL BEFORE YOU DIG!

1-800-424-5555 www.Callbeforeyoudig.org

Project Number Drawn By:

Reviewed By:

Approved By:

21-723

OVERALL SITE AND UTILITY PLAN

AndersonMasonDale Architects SANDERSON STEWART **Enduring Community Design** 

Architect ThinkOne Architects 101 E Main St. Studio 1 Bozeman, MT, 59715 T: 406-586-7020

Denver, CO 80211

T: 303-294-9448

T: 406-587-0721 MEP Engineer **Associate Architect** AndersonMasonDale Architects, P.C. Morrison-Maierle, Inc. 3198 Speer Boulevard 2880 Technology Blvd

Structural Engineer

Morrison-Maierle, Inc.

2880 Technology Blvd.

Bozeman, MT 59715

Bozeman, MT 59715


T: 406-587-0721

**Landscape Architect** Sanderson Stewart 106 East Babcock St. Suite L1 Bozeman, MT 59715 T: 406-522-9876

T: 406-522-9876

Civil Engineer Sanderson Stewart 106 East Babcock St. Suite L1 Bozeman, MT 59715





SITE PLAN MODIFICATION SEAT WALL ELEVATION GRADING REVISION

02/07/2025 03/21/2025 05/05/2025

Date


BOZEMAN, MT **Project Number** 

**ROYAL WOLF WAY** 

21-723

**BARNARD OFFICE HQ** 







**Enduring Community Design** 

Architect ThinkOne Architects 101 E Main St. Studio 1 Bozeman, MT, 59715 T: 406-586-7020

T: 303-294-9448


**Associate Architect** AndersonMasonDale Architects, P.C. 3198 Speer Boulevard Denver, CO 80211

Morrison-Maierle, Inc. 2880 Technology Blvd. Bozeman, MT 59715 T: 406-587-0721

MEP Engineer Morrison-Maierle, Inc. 2880 Technology Blvd Bozeman, MT 59715 T: 406-587-0721

Sanderson Stewart 106 East Babcock St. Suite L1 Bozeman, MT 59715 T: 406-522-9876

Civil Engineer Sanderson Stewart 106 East Babcock St. Suite L1 Bozeman, MT 59715 T: 406-522-9876 BARNARD CONSTRUCTION





SITE PLAN MODIFICATION 02/07/2025 SEAT WALL ELEVATION 03/21/2025 GRADING REVISION 05/05/2025

**ROYAL WOLF WAY** BOZEMAN, MT Project Number

21-723

Drawn By: Reviewed By: Approved By: SITE AND UTILITY PLAN - WEST






Bozeman, MT 59715

T: 406-522-9876

T: 303-294-9448

**Enduring Community Design** 

T: 406-587-0721



CHANGED TO 50 PSI IN



engineers - surveyors - planners - scientists

Architect ThinkOne Architects

101 E Main St. Studio 1 Bozeman, MT, 59715 T: 406-586-7020

**Associate Architect** AndersonMasonDale Architects, P.C. Morrison-Maierle, Inc. 3198 Speer Boulevard Denver, CO 80211 T: 303-294-9448

Structural Engineer Landscape Architect Sanderson Stewart Morrison-Maierle, Inc. 2880 Technology Blvd. 106 East Babcock Bozeman, MT 59715 Suite L1 Bozeman, MT 59715 T: 406-522.9876

T: 406-587-0721


MEP Engineer

2880 Technology Blvd.

Bozeman, MT 59715

T: 406-587-0721

**Civil Engineer** Sanderson Stewart 106 East Babcock Suite L1 Bozeman, MT 59715 T: 406-522.9876




3520 ROYAL WOLF WAY BOZEMAN, MT

**Project Number** 21-723

Reviewed By: JRH Approved By:

**MECHANICAL DETAILS** 

**M-020** 








Company name: Created by: Phone:


Date: 27/08/2025

Description	Value
General information:	
Product name:	300S200-6B
Product No:	14B735C6
EAN number:	5700393985872
Technical:	
Pump speed on which pump data are based:	3450 rpm
Actual calculated flow:	284 US GPM
Rated flow:	317 US GPM
Resulting head of the pump:	230 ft
Rated head:	196.9 ft
Stages:	6
Number of reduced-diameter impellers:	В
Shaft seal for motor:	SIC/SICNBR
Approvals:	CULDWUS,CCSAUS
Approvals for drinking water:	PROP65
Curve tolerance:	ISO9906:2012 3B
Model:	В
Motor version:	T40
Return valve:	YES
Materials:	
Pump:	Stainless steel
	EN 1.4301
	AISI 304
Impeller:	Stainless steel
	EN 1.4301
	AISI 304
Motor:	Stainless steel
	DIN WNr. 1.4301
	AISI 304
Installation:	
Maximum ambient pressure:	870.23 psi
Maximum operating pressure:	870.23 psi
Maximum outlet pressure:	169.69 psi
Type of connection:	NPT(F)
Size of connection:	3 inch
Motor diameter:	6 inch
Minimum borehole diameter:	6.1 in
Liquid:	
Pumped liquid:	Water
Liquid temperature range:	5 104 °F
Max liquid t at 0.15 m/sec:	104 °F
Electrical data:	
Motor type:	MS6000
Motor flange design:	Grundfos
Rated power - P2:	20 HP
Power (P2) required by pump:	20 HP
KVA code:	J
Mains frequency:	60 Hz
Rated voltage:	3 x 440-460-480 V
Service factor:	1.15
Rated current:	33.5-32.5-32.0 A
Requested voltage:	480 V
Poted current at this voltage:	22.5.4









U1, W2	Brown
V1, U2	Black
W1, V2	Grey

Rated current at this voltage:

Starting current:
Cos phi - power factor:

Rated speed:

32.5 A

520-570-610 %

0.85-0.84-0.81

3450-3470-3480 rpm

1



Company name: Created by: Phone:

**Date:** 27/08/2025

Description	Value
Start. method:	direct-on-line
Enclosure class (IEC 34-5):	IP68
Insulation class (IEC 85):	F
Built-in motor protection:	NONE
Thermal protec:	external
Built-in temp. transmitter:	yes
Motor No:	96166166
Cable number:	N/A
Windings:	Enamelled
Others:	
Minimum efficiency index, MEI ≥:	
DOE Pump Energy Index CL:	0.92
Net weight:	169 lb
Gross weight:	235 lb
Shipping volume:	8.19 ft³
Country of origin:	US
Custom tariff no.:	8413.70.2004

# DYNAMIC HEAD CALCULATIONS - Question 33

#### Table X. Well and Piping Distrubution Dynamic Head

Barnard Geothermal System Bozeman, Montana

#### Hazens-Williams Friction Loss Calculations

System Component	Туре	Location	Length (ft)	Loss/100'	Diameter (in)	Head Loss (ft of H <sub>2</sub> O)
•					` '	
Piping	PVC Sch 120	Pump to Surface x 2	300	3.81	4	11.43
	PVC C900 DR 14	Well EX-1 to EX-2	160	3.5	4.07	5.6
	PVC C900 DR 14	Well EX-2 to Bldg	40	2.15	5.86	0.86
	PVC C900 DR 14	Bldg to IN-1 Valve Box	500	2.15	5.86	10.75
	PVC C900 DR 14	Valve Box to IN-1	20	2.15	5.86	0.43
	PVC C900 DR 14	Valve Box to IN-2	150	2.15	5.86	3.225
	PVC Sch 120	Injection Wells x 2	10	3.5	4	0.35
						32.645
			Number	Head Loss	Dia.	
Valve(s)	Gate Valve	Line from EX-1 at EX-2	2	0.14	4	0.28
		Line to IN-1 and IN-2	2	0.12	6	0.24
Elbow	45	Distr. Piping	6	0.24	6	1.44
	90	Well Heads and splits	6	0.45	6	2.7
Ts	4x6	4" to 6" at EX-2	2	0.3	6	0.6
						5.26
Formation Pressure (est.)						0
Pumping Head <sup>1</sup>						150
Building Heat Exchange ( Se	e Page 80)					43.7
					Total Loss	231.605

#### Notes:

Loss / 100 ft: Loss per 100 ft of 4 inch PVC calculated for 275 gpm (Max / Peak demand flow)

Loss per 100 ft of 6-inch PVC calculated for 550 gpm (Max / Peak demand flow)

Average flow will be approx. 60% of max / peak demand flow

<sup>&</sup>lt;sup>1</sup> - Pumping head estimated from drawdown during 72-Hr test at max pump rate. Average rate will be 60% of max.

Project Name: Barnard Building

Project Number: 2200.051
Engineer: JRH
Input date: 14-Dec-22
Print: 30-Jul-25

# **Pump Head Calculation - Closed Systems**

Pump Tag: WWP-1/2 Design GPM: 550.0 ←

Equipment or Area Served: Well Water Loop

oss Item		(internal	to building p	roodro	rices emy)	Head Loss, ft of H2O
Piping:		Length	Loss/100			
. •	Pipe:	35	1.9			0.7
	itting:	Percent of pipe loss				1.0
entrifugal	Separato	r:				
5	Separator					13.8
(	Check Val	ve		CV	408	1.8
Е	Balance V	alve				5.4
Į:	solation V	alve		CV	1542	0.1
ŀ	solation V	alve		CV	1542	0.1
at Excha	anger:					
ŀ	Heat Exch	anger				10.8
5	Strainer					0.6
E	Balance V	alve				1.8
l:	solation V	alve		CV	1542	0.1
Į:	solation V	alve		CV	1542	0.1
			SubTotal	:		36.4
Glycol Correction:		(Water =	1.00)	1.0	0	36.4
			Safety factor	20	1%	7.3
			Total Des	ign He	ad Loss:	43.7

# Pipe / Materials Specifications - Question 34



# MALE-X-MALE NPT DROP PIPE COUPLING IS AVAILABLE IN A WIDE RANGE OF SIZES AND PIPE SCHEDULES

The Male-X-Male PVC drop pipe with stainless steel coupling eliminates corrosion issues and provides longer well life than corrosion-sensitive steel drop pipe.

Offered in Schedule 80 and 120, the Male-X-Male drop pipe provides the most economical solution for water well applications.

#### ASSEMBLY TIPS

- Apply a high quality, non-petroleum, pipe paste sealant, approved for PVC, to each thread joint
- Do not pre-assemble pipe lengths assemble or disassemble one length at a time in a vertical position
- Tighten joints one to a maximum of two turns beyond finger tight DO NOT OVERTIGHTEN
- Avoid using tools which may gouge or damage PVC this can lead to premature failure
- Contact Bilfinger Water Technologies for PVC handling and storage instructions, and a free PVC Drop Pipe Design Program

#### BEST PRACTICES

- Keep flow rate in pipe lower than 8 fps
- Torque arrestors are recommended in all submersible pump installations
- Water hammer suppressors, 100 psi pressure relief valves placed within 30 it, of well head, torque arrestors and/or soft start controls are always recommended for PVC pipe (required for 40 HP or higher pumps)
- Good system design will take into consideration appropriate outlet flow rates and pressures when selecting pump size

The above information only applies when Johnson Screens products are stored, hundled and installed correctly. Contact your local Johnson Screens product representative for higher or lower pressures or different system design conditions.

#### **BILFINGER WATER TECHNOLOGIES**

## JOHNSON SCREENS\* PVC DROP PIPE MALE-X-MALE, NPT

# Advantages of the Male-X-Male, NPT drop pipe include:

- Stainless steel couplings for a variety of sizes;
   exclusive design for 3 to 8 m. (76 to 203 mm)
- Simple alignment and engagement
- Quick makeup
- Watertight seal
- Sizes range from 1 to 8 in. (25 to 203 mm)
- Available in Schedule 80 and 120
- Coupling can be ordered pre-installed on the pipe to eliminate insufficient couplings at the job site





# Blue Brute C900

PRESSURE-RATED PVC PIPE







AWWA C900-16, CSA B137.3 ASTM D1784 Cell Class 12454 ANSI/NSF 61/14, UL 1285

Gasket: ASTM F477 Joint: ASTM D3139

**MARKETS** 



**Potable** 



Irrigation



Reclaim



Sewer

**DESCRIPTION** 

**Available Pipe Sizes (CIOD)** 

4", 6", 8", 10", 12", 14", 16",

18",

20", 24",

48"

Nominal Laying length = 20 feet (Laying length tolerances are in accordance with AWWA and CSA standards)

Color:

Blue

Green

Purple

White



AWWA C900-16										
305 psi	(DR 14)									
235 psi	(DR 18)									
200 psi	(DR 21)									
165 psi	(DR 25)									
125 psi	(DR 32.5)									
100 psi	(DR 41)									
80 psi	(DR 51)									

Note: FM Approvals Pressure Class 185 psi for DR18 and 250 psi for DR14.

CSA B137.3									
309 psi	(DR 14)								
235 psi	(DR 18)								
167 psi	(DR 25)								



**BENEFITS** 



Field-cut with a power saw or handsaw; bevel without complicated machinery.

Does not need lining, wrapping, coating, or cathodic protection to prevent galvanic corrosion.





Corrosive resistant, safe, long-lasting, and stable solution for a modern infrastructure.

Consistency in carrying capacity (flow coefficient, C=150), for savings in pumping costs, and size of the pipe.

# Blue Brute C900

PRESSURE-RATED PVC PIPE



#### SUBMITTAL AND DATA SHEET

PIPE SIZE (IN)	AVERAGE O.D. (IN)	NOM. I.D. (IN)	MIN. T. (IN)	APPROX. E, (IN)	APPROX. E <sub>2</sub> (IN)	APPROX. D <sup>9</sup> (IN)	APPROX. WGT (LBS/FT)		
				ASS 305 psi (					
				FFNESS: 815 ps					
4	4.80	4.07	0.343	4.5	5.5	6.365	3.2		
6	6.90	5.86	0.493	5.25	6.25	8.887	6.7		
8	9.05	7.68	0.646	6.25	7.25	11.499	11.6		
10	11.10	9.42	0.793	7.25	8.25	14.072	17.6		
12	13.20	11.20	0.943	8.25	9.25	16.57	25.1		
16	17.40	14.85	1.242	7.25	8.75	21.637	43.77		
24	25.80	21.89	1.843	9.75	11.25	31.958	98.33		
		PK		ASS 235 psi ( FFNESS: 364 ps					
4	4.80	4.23	0.267	4.5	5.5	6.204	2.6		
6	6.90	6.09	0.383	5.25	6.25	8.654	5.3		
8	9.05	7.98	0.503	6.25	7.25	11.195	9.2		
10	11.10	9.79	0.617	7.25	8.25	13.699	13.9		
12	13.20	11.65	0.733	8.25	9.25	16.125	19.7		
14	15.30	13.50	0.850	6.5	8	18.603	26.75		
16	17.40	15.35	0.967	7.25	8.75	21.135	34.86		
18	19.50	17.20	1.083	7.75	9.25	23.832	48.95		
20	21.60	19.06	1.200	8.75	10.25	26.107	54.22		
24	25.80	22.76	1.433	9.75	11.25	31.089	77.97		
30	32.00	28.23	1.778	11.5	13.5	38.264	117.82		
		PRI		ASS 200 psi (					
14	15.30	13.75	0.729	6.5	8	18.347	23.07		
16	17.40	15.64	0.729	7.25	8.75	20.097	30.04		
18	19.50	17.53	0.929	7.75	9.25	23.505	37.27		
20	21.60	19.42	1.029	8.75	10.25	25.744	46.71		
24	25.80	23.19	1.229	9.75	11.25	30.656	67.53		
30	32.00	28.77	1.524	11.5	13.5	37.725	103.71		
36	38.30	34.43	1.824	13.25	15.25	44.753	152.16		
		PI	RESSURE CI	.ASS 165 psi (C	OR 25)				
			PIPE STII	FFNESS: 129 ps	i				
4	4.80	4.39	0.192	4.5	5.5	6.045	1.9		
6	6.90	6.31	0.276	5.25	6.25	8.427	3.9		
8	9.05	8.28	0.362	6.25	7.25	10.896	6.7		
10	11.10	10.16	0.444	7.25	8.25	13.332	10.1		
12	13.20	12.08	0.528	8.25	9.25	15.69	14.4		
14	15.30	14.00	0.612	6.5	8	18.098	19.48		
16	17.40	15.92	0.696	7.25	8.75	20.561	25.38		
18	19.50	17.85	0.780	7.75	9.25	23.19	31.99		
20	21.60	19.77	0.864	8.75	10.25	25.395	39.46		
24	25.80	23.61	1.032	9.75	11.25	30.239	56.98		
30	32.00	29.29	1.280	11.5	13.5	37.208	88.49		
36	38.30	35.05	1.532	13.25	15.25	44.134	128.41		
42	44.50	40.73	1.780	15.5	17.5	51.56	176.02		
48*	50.80	46.49	2.032	16.5	18.5	58.393	231.22		
		PR		ASS 125 psi (DF FFNESS: 57 psi					
14	15.30	14.30	0.471	6.5	8	17.799	15.14		
16	17.40	16.27	0.535	7.25	8.75	20.219	19.63		
18	19.50	18.23	0.600	7.75	9.25	22.808	24.75		
20	21.60	20.19	0.665	8.75	10.25	24.973	30.54		
24	25.80	24.12	0.794	9.75	11.25	29.734	44.11		
30	32.00	29.91	0.985	11.5	13.5	36.582	68.45		
36	38.30	35.80	1.178	13.25	15.25	43.383	99.22		
48	50.80	47.49	1.563	16.5	18.5	57.399	178.49		

PIPE SIZE	AVERAGE O.D.	NOM, I.D.	MIN. T.	ADDDOX 5	ADDDOX 5	APPROX. D <sup>o</sup>	APPROX. WGT				
(IN)			(IN)	APPROX. E, (IN)	APPROX. E <sub>2</sub> (IN)	(IN)	(LBS/FT)				
PRESSURE CLASS 100 psi (DR 41)											
PIPE STIFFNESS: 28 psi											
14	15.30	14.52	0.373	6.5	8	17.599	12.01				
16	17.40	16.51	0.424	7.25	8.75	19.992	15.63				
18	19.50	18.50	0.476	7.75	9.25	22.555	19.72				
20	21.60	20.49	0.527	8.75	10.25	24.691	24.31				
24	25.80	24.48	0.629	9.75	11.25	29.397	35.10				
30	32.00	30.35	0.780	11.5	13.5	36.163	54.65				
36	38.30	36.30	0.934	13.25	15.25	42.885	78.97				
42	44.50	42.18	1.085	15.5	17.5	50.108	108.19				
48	50.80	48.14	1.239	16.5	18.5	56.736	142.10				
		PR	ESSURE C	LASS 80 psi (I	DR 51)*						
			PIPE ST	IFFNESS: 14 ps	i						
30	32.00	30.67	0.627	11.5	13.5	35.836	44.08				
36	38.30	36.71	0.751	13.25	15.25	42.478	64.32				
42	44.50	42.65	0.872	15.5	17.5	49.652	88.10				
48	50.80 49.69		0.996 16.5		18.5	56.217	115.79				

Product Standard: ANSI/AWWA C900-16 CSA B137.3\* (DR 18, 25, 4"-18"; DR 14, 4"-12") Pipe Compound: ASTM D1784 Cell Class 12454

Gasket: ASTM F477

Integral Bell Joint: ASTM D3139
Certifications: ANSI/NSF 61, ANSI/NSF 14\*

UL 1285 (DR 14, 18, 25, up to 24"), FM 1612\* (DR 14 / DR 18; 4-12"), CSA B137.3\*


Note: FM Approvals Pressure Class 185 psi for DR 18 and 250 psi for DR 14.

Nominal Laying Length: 20 feet

(Laying length tolerences with AWWA and/or CSA standards)

Installation: JM Eagle™ Blue Brute Installation Guide

Manning Coefficient (n) = 0.009 • Hazen-Williams Coefficient (c) = 150 \*Please call regarding availability.



I.D.: Inside Dameter

O.D.: Outside Diameter

T: Wall Thickness

D9: Bell Outside Diameter

E<sub>1</sub>: Distance between 1st Insertion/ Assembly Mark to the end of spigot.

**E**<sub>2</sub>: Distance between 2nd Insertion/ Assembly Mark to the end of spigot.















This information may have been updated. Please visit www.jmeagle.com for all updated information and warranty details.

CUSTOMER SERVICE:1.800.621.4404

# SCHEDULE 120 MALE-X-MALE DROP PIPE

Nomi Pipi Size (in.)	e	OD (in.)	Mir Wa (in.	II Weigh (lbs./	it Wat	ter F sure	low Rati		iction .oss osi/		Rec N Surfa F	Max Do ce Dis Pressi	sch	i (ft.) arge	Tens Streng	
				(psi) GPM ft./ 100 ft.		31 ps			50 081	60 ps	(lbs.					
1	1	.32	0.20	0.46		11	5	5	20	680	0 66		40	620		
			0,1.0	0.46	360	17	8	12	.40	590		-	50	540		
						21	10	1 18	.90	530		-	-	480	700	
1.25	1,3	86	0,22	0.65	205	19	5	3.	50	580	-	-		510		
			- 141.72	U.U.J	300	30	8	8.8	30	520	500		_	460		
			-			37	10	13.	40	480	460	10	_	420	980	
1.5	1.9	0	0.23	0.79	070	26	5	2.9	0	520	500	-	-	450	_	
				0.70	270	41	8	7.2	0	470	450		-	410		
						52	10	11.5	i0 :	430	420	400		380	1,180	
2	2,38	3	0.25	1.20	240	43	5	2.20	) (	160	440	420	-	390		
				1,20	240	69	- 8	5.60	) 4	130	400	390	_	370	1,670	
						86	10	8.80	4	00	380	360	-	340	1,6/0	
3	3.50	0	.35	2.40	220	97	5	1.50	4	20	400	380	_	350		
				71.17	221)	155	8	3.80	40	00	380	360	-	40	Call*	
						192	10	5.90	38	30	360	340	_	20		
4	4.50	0.	44	3.80	215	162	5	1.20	42	0	400	380	-	50		
					210	260	8	3.00	41	0	390	360	-	10	Call*	
			-000			322 260	10	4.50	390	0	370	350	33	-	Juli	
5	5.56	0.3	50	5.40	200	410	5	1.00	380	) ;	360	340	32			
			William -			510	8	2.50	370		350	330	30	0	Call*	
						370	10	3,80	360	_	340	320	290	0	2.0	
6	6.63	0.5	6	7.10	185	590	<u>5</u>	0.80	360	_	40	320	300	)	-	
					-	740	10	2.00	350	_		310	290		Call *	
p -						630	5	3.10	340	-		300	280	_		
8 8	3.63	0.72	2	11.80	180	1920	8	0.60	340	*******		90	270			
			400.00		-	1260	10	1.60	330	31		90 ;	260	(	Call*	
se conta						-	10	2.40	320	30	0 2	80 2	260	-		

NOTE: In practice, field installations encompass flow velocities from 5 - 10 ft./sec. To avoid potentially dangerous surge pressures and to minimize friction losses, keep pipe flow velocities below 8 ft./sec. Tensile values assume nominal thread engagement and are based on 6,000 PSI yield and minimum wall with 6:1 safety factor.


<sup>\*</sup>Please contact Customer Service Department Representative for recommendations regarding your installation.







# <u>6" I.D. STANDARD INDUSTRIAL PARTS BREAKDOWN</u>






Figure 3-Flowing Well Spool





Figure 4

All Industrial cap bolts are made of stainless steel





SPECIFICATIONS	PF-61-030			
Flow Range	160-315 GPM			
System Inlet Connection	3" Flg			
System Outlet Connection	3" Flg			
Purge Connection	1" fpt			
Manual Air Bleed Valve	1/4" fpt			
Volume	7 GAL			
Est. Weight, Dry	98 lbs			
Est. Weight, Operating	156 lbs			

#### **ENGINEERING • MANUFACTURING • SERVICE**

# PF-61-030 SPECIFICATION SHEET FLANGED SEPARATOR

#### Features:

- True tangential entry
- 150 psi working pressure
- Five year limited warranty
- Electrically actuated ball valve

#### **Options:**

- Manual purge
- Isolation valve kit
- Wall mounting bracketS
- Inspection port

#### **SYSTEM COMPONENTS**

#### Separator:

- Carbon steel construction
- Fusion-bond polyester coated vessel
- Manual air bleed valve
- Inlet/Outlet pressure gauges

#### **Electrical Controls:**

- NEMA 4X Enclosure
- Short circuit protection
- Purge switch selector
- Adjustable purge timer

PRESSURE DROP vs. FLOW RATE										
Pressure Drop 3 psi 4 psi 6 psi 8 psi 10 psi 12 psi CV Facto							CV Factor			
Flow (GPM)	158	183	224	259	289	317	91.5			

<sup>\*(</sup>Flow rate / CV values may vary slightly

To determine the approximate pressure drop at flow rates not shown in this chart, use the following formula  $\Delta P$ = (FLOW RATE / CV) $^2$ 

CV Factor: CV is defined as the flow in gallons per minute (GPM) that will produce a one pound pressure drop across the separator

Pressure Drop at 325 GPM = 12.6 psi

## **Technical specification**

#### Gasketed Plate Heat Exchanger

Project ref: Barnard Office HQ

Line ref:

Approx. packed weight:

Model: T5-BFG Page: 1(2)

No of units: 1 Date: 07/24/2023

		Hot side	Cold Side			
Fluid: Density: Specific heat capacity: Thermal conductivity: Viscosity inlet: Viscosity outlet:	lb/ft³ Btu/(lb·°F) Btu/(ft·h·°F) cP cP	35.0% Prop.glycol 63.13 0.9293 0.2630 1.29 1.82	50.0% Prop.glycol 64.18 0.8719 0.2208 4.70 3.03			
Volume flow rate: Inlet temperature: Outlet temperature:	GPM °F °F	68.2 120.0 100.0	71.0 80.0 100.0			
Pressure drop: Heat exchanged: LMTD: Heat transfer area: Relative directions of fluids:	psi kBtu/h °F ft²					
Connection positions and flow directions:		S1->S2	S3->S4			
Connections: S1,S2,S3,S4	ASME B1.20.1 - 2-11.5 NPT, ALLOY 316L, 101 mm					
External loads according to API:		No loads				
Design pressure (MAWP): Test pressure: Design temperature max.: Design temperature min. (MDMT):	psi psi °F °F	150 196 200.0 -18.0	150 196 200.0 -18.0			
Pressure vessel approval:		ASME U	M-stamp			
Number of plates: Nominal A-dimension: Plate material/thickness: Gasket material and attachment:	mm	57 131 ALLOY 316/0.5 mm NBRB Clip-on NBRB Cl				
Approx. outer dimensions (L x W x H) Approx. weight, empty / operating:	in Ib	14.6 x 10 218 <i>i</i>	).2 x 27.6 / 237			
Type of package: Skid base + box (domest						

lb

292.957

The performance of the equipment is conditioned by the process media and process parameters being consistent with the provided customer data. Data, specifications, and other kind of information of technological nature set out in this document and submitted by Alfa Laval to you (Proprietary Information) are intellectual proprietary rights of Alfa Laval. The Proprietary Information shall remain the exclusive property of Alfa Laval and shall only be used for the purpose of evaluating Alfa Laval's quotation. The Proprietary Information may not, without the written consent of Alfa Laval, be used or copied, reproduced, transmitted or communicated or disclosed in any other way to a third party.

#### **Engineering Specification**

Job Name ————	Contractor —
Job Location ————	Approval ————————————————————————————————————
Engineer —————	Contractor's P.O. No.
Approval ————————————————————————————————————	Representative —

# LEAD FREE

# Series 77F-DI-125, 77F-DI-FDA-125

Flanged, Wye Pattern, Cast Iron Strainers

2" - 12"

Series 77F-DI-125, 77F-DI-FDA-125 Flanged, Wye Pattern, Cast Iron Strainers feature 304 stainless steel perforated screens, a cast iron flanged retainer cap and a drain/blowoff connection furnished with a closure plug. Series 77F-DI-FDA-125 also features a double coated, heat fused epoxy coating on the interior and exterior for NSF/ANSI/CAN 61 approved sanitary applications.

#### **Features**

- Flanges conform to American National Standards Institute, Class 125 (ANSI B16.1) and WW-S-2739 Type 2
- Lead Free\* cast iron body
- 304 Stainless steel perforated screens
- Cast iron flanged retainer cap with gasket tapped for closure plug
- Drain/Blowoff connection furnished with closure plug
- Series 77F-DI-FDA-125 comes with heat fused NSF/ANSI/CAN 61 approved epoxy coating (interior and exterior)

#### Models

77F-DI-125 — 2" – 12" with flanged connections for water and steam service

77F-DI-FDA-125 — 2" – 12" with flanged connections and double coated, heat fused NSF/ANSI/CAN 61 approved epoxy coating (interior and exterior) for water service only

#### Specification (77F-DI-125)

A flanged, wye pattern, cast iron strainer to be installed as indicated on the plans. The strainer must have flanges that conform to American National Standards Institute, Class 125, 304 stainless steel perforated screens and a drain/blowoff connection furnished with a closure plug. Pressure rating no less than 200psi (13.8 bar) WOG non-shock and 125psi (8.6 bar) WSP. Strainer shall be a Watts Series 77F-DI-125.



77F-DI-FDA-125

#### Pressure - Temperature

Maximum Operating Pressure: 200psi (13.8 bar) WOG, non-shock, @ 210°F (99°C) 125psi (8.6 bar) WSP @ 353°F (178°C)

#### Standard Screens

2" – 5": 1/16" perforation 6" – 8": 1/8" perforation 10" – 12": 3/16" perforation

#### Screen Options

Wire Mesh Liners: 304 stainless steel (#20, #40, #60, #80, #100) Perforated Screens: 304 stainless steel (3/64", 1/16", 1/8", 3/16")

#### Specification (77F-DI-FDA-125)

A flanged, wye pattern, cast iron strainer with a double coated, heat fused, NSF/ANSI/CAN 61 approved epoxy coating on the interior and exterior surfaces for NSF/ANSI/CAN 61 sanitary applications. Flanges to conform to ANSI B16.1 Class 125, 304 stainless steel perforated screens, and a drain/blowoff connection furnished with a closure plug. Pressure rating 200psi (13.8 bar) WOG. Strainer shall be a Watts Series 77F-DI-FDA-125.

#### NOTICE

The information contained herein is not intended to replace the full product installation and safety information available or the experience of a trained product installer. You are required to thoroughly read all installation instructions and product safety information before beginning the installation of this product. Inquire with governing authorities for local installation requirements.



<sup>\*</sup>The wetted surface of this product contacted by consumable water contains less than 0.25% of lead by weight.

#### Materials

# 1

A. Screen AISI 304SS Cover Gasket В. Graphite \*ASTM A47 C. Plug D. Washer ASTM A6 E. Cotter Pin ASTM A112 F. Plate \*ASTM A6 G. **Bolt Nut** ASTM A6 Н. Bolt ASTM A6 Ι. Set Screw ASTM B16 J. Cover Bolt Nut ASTM A6 K. Cover Bolt ASTM A6

L. Cover \*ASTM A-126 Class B Body \*ASTM A-126 Class B Μ. Note:\* 77F-DI-FDA-125 component parts epoxy coated internally and externally.

#### Standards

Tested and Certified by NSF International






#### Dimensions - Weights

Call customer service if you need assistance with technical details.


SIZE		DIMENSIONS											
	,	Ą	В		C(NPT)		D*		Screen Area				
in.	in.	mm	in.	mm	in.	mm	in.	mm	sq.in.	lbs.	kgs.		
2	77//8	200	51/4	133	1/2	13	7	178	36	18	8		
21/2	10	254	61/2	165	1	25	93/4	248	56	28	13		
3	101//8	257	7	178	1	25	10	254	75	34	15		
4	121/8	308	81/4	210	11/2	38	12	305	121	60	27		
5	15%	397	111/4	286	2	51	17	432	210	95	43		
6	181/2	470	13½	343	2	51	20	508	278	133	60		
8	21%	551	15½	394	2	51	223/4	578	387	247	112		
10	26	660	18½	470	2	51	28	711	577	370	168		
12	297/8	759	21¾	552	2	51	30	762	795	579	262		

<sup>\*</sup> D dimension is minimum clearance for screen removal.

# Flow/Pressure Drop Chart



Pressure Drop - psi





USA: T: (978) 689-6066 • Watts.com Canada: T: (888) 208-8927 • Watts.ca

Latin America: T: (52) 55-4122-0138 • Watts.com

ES-77F-DI-125 2512 © 2025 Watts

#### **Engineering Specification**

Job Name	Contractor
Job Location	Approval
Engineer	Contractor's P.O. No.
Approval	Representative

# LEAD FREE\*

# **Butterfly Valves**

Series BF-03-M2 Full Lug and BF-04-M2 Wafer

Sizes: 2" - 12"\*\* 200psi (13.8 bar) 14" - 24"\*\* 150psi (10.3 bar)

Watts Series BF resilient seated butterfly valve is available in sizes 2" – 24"\*\* in wafer or lug body design. Incorporating a 200psi (13.8 bar) pressure rating for 2" – 12"\*\* and a 150psi (10.3 bar) pressure rating 14" – 24"\*\*, the BF series butterfly is standardly constructed of a ductile iron body with a choice of either ductile iron, aluminum bronze, or 316 stainless steel discs and 416 stainless steel or 316 stainless steel shaft. A phenolic-backed seat (2"-12")\*\* or aluminum-backed seat (14" – 24")\*\* prevents the seat from collapsing or dislodging. Standard seat materials available include EPDM, Buna-N and Viton. The BF Series mounting pad is designed to ISO 5211 standard to accommodate lever handles, gear operators, or actuation.

The Watts Series BF butterfly valves are designed and manufactured for use with ANSI 125 or 150 Class flanges and comply with API 609 and MSS-SP 67 standards to meet the stringent requirements of HVAC, Irrigation, OEM, Commercial, Institutional, and Industrial applications.

#### **Approvals**

The valves are MSS-SP-67 Type I – Valves for tight shut-off (tested per section 10.2.1). As specified in MSS-SP-67, we conduct 100% shell testing at 1.5 times rated pressure and seat leakage testing at 1.1 times rated pressure.

#### **Features**

- Body Available in Full Lug (BF-03-M2) and Wafer (BF-04-M2) styles designed for use between ANSI 125 and 150 flanges. Face-to-face dimensions comply with API 609 and MSS-SP-67. All valves are designed to accommodate 2" of insulation. The mounting pad is designed to ISO 5211 standard. The body material is ASTM A-536 ductile iron.
- Disc Disc edge is machined and polished 360 degrees to assure leak-tight shutoff while minimizing operating torque.
   Positive, disc-to-shaft connection is provided by stainless steel precision taper pins. Discs are available in ductile iron, aluminum bronze, or 316 stainless steel.
- Seat Phenolic or aluminum backed, non-collapsible, resilient seat is mechanically secured to allow for dead-end service usage to the full pressure rating in lug style valves. Full 360 degrees sealing isolates the body components from the media and provides the primary shaft seal. Seats are available in EPDM, Buna-N, and Viton.



 Shaft – One-piece shaft delivers positive disc-to-seat location with maximum strength. 416SS is standard shaft with ductile iron and aluminum bronze disc. 316SS shaft is standard with 316SS disc models.

Three shaft bushings provide shaft support for proper alignment and minimal shaft deflection. Bi-directional shaft seals prevent external contamination of the stem area and provide backup for the primary shaft seal formed by the disc/seat interface.

• Handle – ISO 5211 top work design allows for standard 10 position handle 2" – 6"\*\* and manual, worm gear operators for 8" – 24"\*\* sizes. An infinite positioning locking handle is an available option on 2" – 12"\*\* valves. The posi-lok handle provides an infinite position stop, a memory stop, and a padlocking device in the fully closed position.

#### NOTICE

The information contained herein is not intended to replace the full product installation and safety information available or the experience of a trained product installer. You are required to thoroughly read all installation instructions and product safety information before beginning the installation of this product.

#### NOTICE


Inquire with governing authorities for local installation requirements


\*The wetted surface of this product contacted by consumable water contains less than 0.25% of lead by weight.

\*\*This product is produced with ASME/ANSI flanged end connections.



#### **Dimensions**






9	SIZE		TOP F Dril						ED LUG Ata	KEY WAY		WEIGHT LBS. †		ı	C <sub>v</sub> R (Full							
Ī			N	0		0		0		0		BOLT CIRCLE		NO.	BOLT	Q				ı	Size	
	in.	in.	mm	in.	mm	in.	mm	Holes	P	in.	mm	88	87	_	in.	ſ						
Ξ	2	2	50	1/4	7	41/4	121	4	%"-11UNC x 1%"	-	-	8	6	Ξ	2	ſ						
	21/2	2	50	1/4	7	5½	140	4	%"-11UNC x 1¾"	-	_	10	7		21/2	ĺ						
Ξ	3	2	50	1/4	7	6	150	4	%"-11UNC x 1¾"	-	-	10	7		3	ĺ						
	4	23/4	70	3/8	10	71/2	191	8	%"-11UNC x 2"	_	_	17	12	_	4	l						
Ξ	5	23/4	70	3%	10	81/2	216	8	3/4"-10UNC x 23/16"	-	_	25	16	_	5	l						
Ξ	6	23/4	70	3%	10	91/2	241	8	3/4"-10UNC x 23/16"	-	_	27	20	_	6	l						
Ξ	8	4	102	1/2	13	113/4	298	8	34"-10UNC x 23/4"	-	_	40	29	_	8	l						
	10	4	102	1/2	13	141/4	362	12	%"-9UNC x 2%"	_	_	63	48		10	l						
	12	5	125	1/2	13	17	432	12	7/8"-9UNC x 3"	1/4 x 11/4	6 x 32	107	78	_	12	ĺ						
Ξ	14	5	125	1/2	13	18¾	476	12	1"-8UNC x 3"	1/4 x 11/4	6 x 32	156	99	_	14	ĺ						
Ξ	16	51/2	140	11/16	18	211/4	540	16	1"-8UNC x 3%"	5⁄16 <b>x 1</b> <sup>13</sup> ∕16	8x46	203	140		16	ĺ						
Ξ	18	51/2	140	11/16	18	223/4	578	16	11/4"-7UNC x 41/4"	3% x 1%6	10x40	269	188		18	ĺ						
Ξ	20	5½	165	7/8	22	25	635	20	11/4"-7UNC x 51/4"	3% x 1%6	10x40	392	248		20	ſ						
_	24	51/2	165	7/8	22	291/2	750	20	11/4"-7UNC x 6"	½ x 2%	13x60	593	450		24	ſ						

levers; 14" - 24" have bare shafts. Refer to Watts F-CDBF for gear operator weights

# (4) "0" Diameter of holes on the "N" bolt circle 45° off center.

	SEATING TORQUE BUNA-N, EPDM								
SIZE	NORMAL	CONDITIONS							
in.	Wet	Dry							
	inlbs.	inlbs.							
2	134	214							
21/2	190	289							
3	250	387							
4	390	644							
5	600	959							
6	907	1,542							
8	1,697	2,919							
10	2,500	4,857							
12	3,300	7,071							
14	3,500	7,305							
16	5,500	10,027							
18	8,200	13,437							
20	10,000	17,925							
24	18,680	28,020							

			CL			CL	TURNS	
VALVE			TO	HW.		TO	OPEN/	UNIT
SIZE	DEPTH	WIDTH	HW	DIA.	HEIGHT	MT PAD	CLOSE	WEIGH
in.	Α	В	С	D	E	F		lbs.
2, 21/2, 3	5.0	4.2	6.5	6.0	2.7	1.5	7.0	10.0
4	5.0	4.2	6.5	6.0	2.7	1.5	7.0	10.0
5, 6	5.0	4.2	6.5	6.0	2.7	1.5	7.0	10.0
8	7.0	6.2	9.5	12.0	3.0	1.8	7.5	27.5
10	7.0	6.2	9.5	12.0	3.0	1.8	7.5	27.5
12, 14	7.8	6.4	9.5	12.0	3.0	2.0	12.5	33.0
16	11.5	9.6	15.0	16.0	4.2	2.5	20.0	70.5
18	11.5	9.6	15.0	16.0	4.2	2.5	20.0	70.5
20	11.5	9.6	15.0	16.0	4.2	2.5	20.0	70.5
24	12.6	9.1	15.0	24.0	4.5	2.0	20.0	80.0



#### Materials

600 1,022

5,340 8,250

16,388 21,705

43,116

Body: ASTM A-536 Ductile Iron epoxy electrostatic

sprayed (RAL5015F-NSF).

Bushing: Duralon(3): Teflon® - Dacron inner liner

bonded to fiberglass - epoxy resin outer shell 2"-12"\*\*, Bronze 14"-24"\*\*

Stem O-rings: Buna-N

Disc: ASTM A-395 Ductile Iron / Electroless

Nickel Plated

ASTM B-148 Aluminum Bronze ASTM A-351 316 Stainless Steel

Shaft: 416 Stainless Steel

316 Stainless Steel on 316SS Disc Models

EPDM: +5°F to 248°F (-15°C to +120°C)

Buna-N: +14°F to 176°F (-10°C to +80°C)


Viton: -4°F to 302°F (-20°C to +150°C)

#### NOTICE

Seat:

Do not use EPDM when hydrocarbons are present.

#### How to Order Watts Series BF-M2



5: Standard handle (10-position only) - 2" thru 12" P: Positioning / Locking Kit with handle - 2" thru 12"



USA: T: (978) 689-6066 • Watts.com
Canada: T: (888) 208-8927 • Watts.ca
Latin America: T: (52) 55-4122-0138 • Watts.com

ES-BF-03-M2/BF-04-M2 2306 © 2022 Watts

# Steel Models

#### VW, VG, VF, AW, AG, AF, EF, ER

**Differential Pressure: Inches W.C. 16 to 260 GPM** 

	iudi Pre	ssure: In	ches W.	<b>-</b>									
Flow							Models						
GPM	200L	200H	250L	250H	300L	300H	400L	400H	500L	500H	600L	600H	800L
16	10												
18	13												
20	16												
22	19												
24	23												
26	27	10	11				ļ						
28	31	11	12										
30	36	13	14										
32	41	15	16										
34	46	17	18										
36	52	19	20										
38	58	21	23										
40	64	23	25										
42	71	26	28										
44	77	28	30										
46	85	31	33										
48	92	33	36										
50	100	36	39										
55	121	44	47		11								
60	144	52	56	11	14								
65	169	61	66	13	16								
70	196	71	77	15	18								
75	225	82	88	17	21								
80	256	93	100	20	24								
85	289	105	113	22	27								
90	324	118	127	25	30								
95	361	131	141	28	34		10						
100	400	145	156	31	38		11						
120		209	225	44	54	13	16						
130		245	264	52	64	15	19	10	11				
140		285	306	60	74	17	22	12	12				
150		327	352	69	85	20	25	13	14				
160		372	400	79	96	23	28	15	16				
170		420	452	89	109	26	32	17	18				
180		470		100	122	29	36	19	20				
190				111	136	32	40	21	23				
200				123	151	36	44	24	25				
220				149	182	43	54	29	30				
240				178	217	51	64	34	36		10		
260				209	254	60	75	40	42	10	12		



### Steel Models

#### VW, VG, VF, AW, AG, AF, EF, ER

#### Differential Pressure: Inches W.C. 280 to 775 GPM

Differential Pressure: Inches W.C.													
Flow		Models											
GPM	200L	200H	250L	250H	300L	300H	400L	400H	500L	500H	600L	600H	800L
280				242	295	70	87	47	49	12	14		
300				278	339	80	100	54	56	13	16		
325				326	396	94	117	63	66	16	19		
350				278	461	109	136	73	77	18	22		
375				434		125	156	84	88	21	25		
400				494		143	178	95	100	24	28		
425						161	201	107	113	27	32		11
450						180	225	120	127	30	36		12
475						201	251	134	141	33	40	10	13
500						223	278	149	156	37	44	11	15
525						246	305	164	172	40	48	13	16
550						270	336	180	189	44	53	14	18
575						295	367	197	207	49	58	15	19
600						321	400	214	225	53	63	16	21
625						348	434	232	244	57	69	18	23
650						376	469	251	264	62	74	19	25
675						406		271	285	67	80	21	27
700						437		291	306	72	86	22	29
725						468		313	329	77	92	24	31
750								335	352	83	99	26	33
775								357	375	88	106	27	35

#### Notes:

- 1. (Permanent pressure loss equals 10 percent of differential pressure (DP).
- 2. The recommended ranges are shown in bold. All differentials have been rounded to the nearest inch.
- 3. Generally, the recommended low DP signal is 24" so it can be read on most HVAC instruments. DPs below 12" are not accurate on some sizes.
- 4. The upper DP limit is an effort to minimize the permanent pressure loss which is 10 percent of the DP signal. Any venturi can be operated above the recommended range if the permanent pressure drop is acceptable.
- 5. The DPs in the table were calculated using the following formula:



#### Outlook

#### [EXTERNAL] RE: Deficiency Letter for Beneficial Water Use Permit Application No. 41H 30165312

From Pat Thomson <pthomson@waterenvtech.com>

Date Mon 11/10/2025 10:25 AM

Ellis, Kendrew < Kendrew. Ellis@mt.gov>

Cc Strasheim, Kerri <kstrasheim@mt.gov>

#### Good Morning Kindrew,

Just checking in on the Barnard permit. Are you able to give me an update on the status of the permit?

Thanks,

Pat

From: Pat Thomson

Sent: Monday, October 20, 2025 10:16 AM To: 'Ellis, Kendrew' < Kendrew. Ellis@mt.gov> Cc: Strasheim, Kerri <kstrasheim@mt.gov>

Subject: RE: Deficiency Letter for Beneficial Water Use Permit Application No. 41H 30165312

Hi Kindrew,

The following link to Form 600 for Permit App No. 41H 30165312 has been amended in response to DNRCs deficiency letter dated October 14, 2025. Please let me know if you have any questions.

600 Barnard signed 102025 revised.pdf [wetenvtech-my.sharepoint.com]

Thanks, Pat



#### Patrick J. Thomson, PG

Senior Hydrogeologist

P: (406) 723-1532 C: (406) 490-0329

waterenvtech.com [waterenvtech.com]

From: Ellis, Kendrew < <a href="mailto:Kendrew.Ellis@mt.gov">Kent: Tuesday, October 14, 2025 2:15 PM</a>

To: Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

Cc: Strasheim, Kerri < <a href="mailto:kstrasheim@mt.gov">kstrasheim@mt.gov</a>>

Subject: Deficiency Letter for Beneficial Water Use Permit Application No. 41H 30165312

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

Pat-

The Department of Natural Resources and Conservation (DNRC or Department) has begun reviewing Application for Beneficial Water Use Permit No. 41H 30165312 by Barnard Construction, Inc. The attached letter is to notify you of the deficiencies in the application as required in ARM 36.12.1501(1) and §85-2-302(5)(b), MCA. Please submit the information specified above to the Bozeman Regional Office by February 11, 2026. This is the only deficiency letter that will be sent. An application not corrected or completed within 120 days from the date of this letter is terminated per ARM 36.12.1501(2) and §85-2-302(6)(a), MCA.

The attached letter was sent in the mail today, 10/14/2025. The deficiency response is due in 120 days, by 2/11/2026.

Please let me know if you have any questions.

#### -Kendrew



Kendrew Ellis (she/her) | Water Resource Specialist

Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation

2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

DESK: 406-556-4538 EMAIL: kendrew.ellis@mt.gov

Website | Facebook [facebook.com] [facebook.com] [twitter.com]X

[twitter.com](T [twitter.com]witter [twitter.com]) | Instagram

[instagram.com]

How did we do? Let us know here: [forms.office.com]Feedback Survey

[forms.office.com]

Technical Analyses Report/ Scientific Credibility Review

- Departmental Technical Analyses Report/ Scientific Credibility Review
- Any correspondence relating to the Technical Analyses Report

Technical Analyses
Report /
Scientific Credibility
Review

#### THE MONTANA DEPARTMENT OF NATURAL RESOURCES AND CONSERVATION

**GOVERNOR GREG GIANFORTE** 



DNRC DIRECTOR AMANDA KASTER

DNRC 2273 Boot Hill Ct, STE 110 Bozeman, MT 59715

July 7, 2025 Barnard Construction 701 Gold Avenue Bozeman, MT 59715

Subject: Completed Technical Analyses Report for Beneficial Water Use Permit Preapplication No. 41H 30165312

#### Dear Applicant:

As designated on the submitted Preapplication Meeting Form per §85-2-302(3)(b), MCA, the Department of Natural Resources and Conservation (DNRC or Department) has completed the technical analyses for Beneficial Water Use Permit Preapplication No. 41H 30165312 based on the information provided in your Preapplication Meeting Form accepted by the Department on 5/23/2025. The technical analyses can be found in the attached report. Please note this Groundwater Permit Technical Analyses Report is a two-part publication, comprised of a Part A completed by Evan Norman and a Part B completed by Kendrew Ellis.

This Technical Analyses Report <u>IS</u>: A collection of facts that the DNRC has gathered, including content provided in the Preapplication Meeting Form materials. The Department will use these data to analyze the criteria in §85-2-311, MCA if you submit an application for the project described in the completed Preapplication Meeting Form.

This Technical Analyses Report <u>IS NOT</u>: An analysis or discussion of whether the Preapplication Meeting Form as filed meets the criteria (§85-2-311, MCA).

You have 180 days to submit the Beneficial Water Use Permit Application Form 600 considering the information provided in the technical analyses and Preapplication Meeting Form. If the Application Form is not submitted to the Bozeman Regional Office by 1/3/2026, a new preapplication meeting will be required to process the Application with expedited timelines (ARM 36.12.1302(6)(b)). If any details described in the submitted Application are changed from that of the submitted Preapplication Meeting Form, the discounted filing fee and expedited timelines will not apply (ARM 36.12.1302(6)(a)). Please note that the technical analyses will expire one year from the date of this letter (ARM 36.12.1302(8)).

Please let me know if you have any questions.

Sincerely,

Kendrew Ellis

Water Resources Specialist

**Bozeman Water Resources Office** 

Water Resources Division

CC, via email: Pat Thomson, pthomson@waterenvtech.com





#### **Groundwater Permit Technical Analyses Report - Part A**

# **Department of Natural Resources and Conservation (DNRC) Water Resources Division**

Evan Norman, Groundwater Hydrologist, Water Sciences Bureau (WSB)

Application No.	41H 30165312	Point of Diversion Legal Land Description	Section 27 and 22, Township 01 South, Range 5 West
Applicant	Barnard Construction		

#### **Overview**

Appendix B: 1-foot-Contour Water Rights

This report is Part A of a two-part publication which analyzes data submitted by the Applicant in support of the above-mentioned water right application. This report provides technical analyses as required under the Administrative Rules of Montana (ARM) 36.12.1303 in support of the water rights criteria assessment as required in §85-2-311, Montana Code Annotated (MCA). For applications in closed basins, this report fulfills the requirements of MCA 85-2-361.

This Groundwater Permit Technical Analyses Report – Part A contains the following sections:

Overview	1
1.0 Executive Summary	2
2.0 Hydrogeologic Setting	3
3.0 Aquifer Test Summary	4
4.0 Aquifer Test Analysis	7
5.0 Drawdown and Yield Test	12
6.0 Modeling Inputs	13
7.0 Adequacy of Diversion Analysis	13
8.0 Physical Availability Analysis	17
9.0 Adverse Effect Analyses	19
9.1 Groundwater - Drawdown in Existing Wells	19
9.2 Surface Water - Net Depletion	19
Review	1
References	1
Appendix A: Groundwater Rights Within Area of Potential Impact	



#### 1.0 Executive Summary

#### **Application Details**

The Applicant requests to divert 550.0 gallons per minute (gpm) and up to 298.40 acre-feet (AF) of groundwater from two points of diversion (wells) for geothermal cooling purposes. The two Extraction Wells, Montana Bureau of Mines and Geology (MBMG) Groundwater Information Center (GWIC) IDs 335313 and 335315, would each divert water at a rate of 275.0 gpm. Two injection Wells, GWIC IDs 335309 and 335811, would each inject water at a rate of 275.0 gpm back into the aquifer via an open-loop geothermal cooling system.

#### Recommended and Approved Variances from ARM 36.12.121

The required variances, rationale, and recommended action to grant the variance requests were sent in an Aquifer Testing Addendum Review checklist to the Bozeman Regional Office on April 7, 2025. Variances from aquifer test requirements found in ARM 36.12.121: 3(a), 3(g), 3(h), and 3(e)(iii) were approved by the Bozeman Regional Office on April 14, 2025.

#### **WSB Technical Analyses Findings**

Based on information submitted, the WSB estimated aquifer properties, evaluated the extraction well(s) available water column, quantified the water available in the source aquifer, and evaluated potential impacts to existing groundwater and surface water rights. These technical analyses are in support of the following criteria assessment: adequacy of diversion, physical availability, and adverse effect. A summary of WSB findings described in subsequent sections are listed below.

#### **TECHNICAL ANALYSES FINDINGS**

AQUIFER TEST ANALYSIS	Using the Cooley-Case (1973) solution, saturated thickness (b) of 218 feet (ft), and submitted 72.2-hour aquifer testing data for GWIC ID 335315, estimates of aquifer properties include a Transmissivity (T) of 873 ft $^2$ /day and Storativity (S) of 1.1 x 10 $^{-4}$ .
MODELING INPUTS	The following aquifer properties were used to complete adequacy of diversion, physical availability and adverse effect technical analyses: T of 873 ft²/day, S of 1.1 x $10^{-4}$ . The estimated leakage parameter (r/B; $\beta$ ), storage ratio in aquitard (S'/Sy), and dimensionless height of capillary fringe (L/b') are identified in figures below. Pumping schedules and boundaries used to model each criterion are identified within the document.
ADEQUACY OF DIVERSION	The aquifer adjacent to GWIC ID 335313 and 335315 would experience 54.20 and 58.90 ft of drawdown after the first year, leaving approximately 134 ft and 159 ft of available water column above the bottom of the perforated intervals, respectively.
PHYSICAL AVAILABILITY	The model predicted the 0.01-foot drawdown contour, or zone of influence (ZOI), has a width of approximately 14,000 ft in the predominate direction of groundwater flow. The northeastern and eastern extent of the ZOI was





truncated to the East Gallatin River. The total flux through the ZOI is equal to 1,024 AF/year. There are 152 existing groundwater rights with a status of active and severed within the ZOI. (**Appendix A**).

#### ADVERSE EFFECT (DRAWDOWN IN EXISTING WELLS)

The 1-foot drawdown contour extends out approximately 4,100 ft from GWIC ID 335313 and 335315 at the end of July of the fifth year of pumping. 13 water rights are predicted to experience drawdown equal to or greater than 1-foot (**Appendix B**).

#### ADVERSE EFFECT (NET DEPLETION TO SURFACE WATER)

The East Gallatin River is identified as being hydraulically connected to the source aquifer. There would be no consumed volume associated with the proposed geothermal purpose, and therefore no net depletion to hydraulically connected surface waters.


#### 2.0 Hydrogeologic Setting

As identified in **Figure 1**, the Production Wells GWIC ID 335313 and 335315 (Extraction Wells 1 & 2) were completed to 202 and 232 ft below ground surface (bgs) in Section 27 and 22, Township 01 South, Range 05 East, Gallatin County, respectively. Both wells are completed in the Tertiary aged valley-fill sediments (120SDMS) with perforated interval lengths of 35 ft. The wells, GWIC IDS 335309 and 335811 (Reinjection Wells 1 & 2) are completed to 300 and 215 ft bgs, respectively, in Section 22, Township 01 South, Range 05 East, Gallatin County. The injection wells are also completed in the source aquifer 120SDMS with perforated interval lengths of 144 and 100 ft. Well logs near the project location primarily describe alternating lenses of sand and gravel, clay-bound gravels, and clay which may act as localized leaky-confining units.

The surficial geology is mapped as Quaternary braided plain alluvium deposits of cobbles, boulders, sand, silt and clay up to 30 ft thick (Vuke et al., 2014). The Quaternary sediments are underlain by Tertiary Madison Valley member silt, siltstone, sandstone and conglomerates, in some parts of the valley up to 300 ft thick (Vuke et al., 2014).

The Gallatin Valley Quaternary and Tertiary aquifer system contains shallow unconfined, semi-confined (leaky confined), confined, and possibly even perched groundwater (English, 2018). Generally, groundwater and surface water flows from southeast to northwest across the valley and is recharged by irrigation, stream losses, and ditch leakage ultimately discharging to the Gallatin River (Hackett et al., 1960). The wells are on the edge of the Bozeman hydrogeologic subarea (Fan) adjacent to the Upper East Gallatin and Belgrade hydrogeologic subareas mapped by Hackett et al. (1960). Recent studies suggest that recharge from the surrounding bedrock aquifer and leakage from canals and ditches are the two largest components of groundwater recharge to the Gallatin Valley Aquifer (Michalek and Sutherland, 2020).





**Figure 1:** Map of the Applicant's aquifer test location and nearby T values derived from aquifer tests (**Table 4**).

#### 3.0 Aquifer Test Summary

DNRC requires two different types of tests: "Aquifer Tests" and "Drawdown and Yield Tests." which aid DNRC in analyzing different application criteria.

- An "aquifer test" is a pumping test that is meant to provide data to model aquifer properties. The minimum duration of these tests is either 24-hours or 72-hours, depending on the proposed flow rate and volume (AMR 36.12.121(3)(e)), and DNRC only requires one of these tests per application. Aquifer Tests must include observation well data and pre-test monitoring data as well as post-test recovery data.
- A "drawdown and yield test" is a pumping test that is meant to evaluate well construction
  and the ability of the aquifer to yield water to the well. This is also known as
  demonstrating "adequacy of diversion." The minimum duration of these tests is 8 hours,
  and every well that is a part of the application, that did not have an aquifer test, must be



Groundwater Permit Technical Analyses Report-Part A
Application No. 41H 30165312
Bozeman Regional Office
Gallatin County

tested for at least 8 hours. Observation wells, pre-test background data, and post-test recovery data are not required for Drawdown and Yield Tests.

#### Field Methods and Equipment

A 72.2-hour aquifer test was conducted on the Production Well, GWIC ID 335315. Water pressure was collected using an In-situ LevelTROLL 400 water level logger and corrected using a BaroTROLL 400 data logger in the Production Well and Observation Wells (GWIC ID 335313 and 304409). Manual water level measurements were collected using a Geotech water level meter. Observation Wells GWIC ID 335313 and 304409 are 163 and 430 ft from the Production Well and completed in the same source aquifer. The discharge was measured with a Blue-White Brand F-300 flow meter attached to a 4-inch discharge pipe.

#### **Background Data**

A variance for ARM 36.12.121 was granted for 3(g) and therefore, limited background data was collected as part of the 72.2-hour aquifer test. Background level trends did not appear to affect the drawdown and recovery data.

#### **Drawdown Data**

The 72.2-hour aquifer test started on July 23, 2024, at 12:00 P.M. on the Production Well and is considered (t = 0) for the computation of drawdown. The average pumping rate was 269.5 gpm. The pumping rate varied during the test beyond a margin of 5% of the average discharge (+/- 5% average discharge). The additional drawdown and yield test was submitted to meet the total requested flow rate of 550.0 gpm.







Figure 2: Measured discharge for Production Well GWIC ID 335315 during the 72.2-hour test.

The maximum drawdown in the Production Well was 87.86 ft below the static water level (swl) of 16.05 ft below top of casing (btc) leaving approximately 130 ft of available water column above the bottom of the perforated interval. Observation Well, GWIC ID 335313, experienced a maximum drawdown of 24.22 ft below the swl of 14.94 ft btc leaving approximately 165 ft of available water column above the bottom of the perforated interval. Observation Well, GWIC ID 304409, did not have observable drawdown as a result of the aquifer testing. A plot of drawdown and recovery for the Production and Observation Wells with measured drawdown is shown in **Figure 3**.

#### **Recovery Data**

Recovery groundwater level data was monitored for 72-hours in the Production Well GWIC ID 335315 and Observation Well GWIC ID 335313. At the end of the recovery period the Production and Observation Wells were both -0.05 ft from pre-test swls, respectively.





**Figure 3:** Drawdown and recovery data for Production and Observation Wells during the 72.2-hour aquifer test.

#### 4.0 Aquifer Test Analysis

#### Methods

The DNRC utilized AQTESOLV® (HydroSOLVE, Inc., 2007) to analyze drawdown data from the aquifer test and obtain estimates of aquifer properties. Aquifer properties were used in forward modeling to evaluate the available water column in the well, quantity of water available in the source aquifer, and potential impacts to groundwater and surface water rights. AQTESOLV® is an analytical modeling software that uses image-well theory and the principle of superposition to simulate aquifer stress tests. Drawdown data and measured flow rates from the aquifer test, and the spatial location of each well are input into the model. Using this compilation of data, aquifer properties including T and S are identified based on a best-fit visual and statistical match between the observed and theoretical drawdown data.

#### **Analyses**

Analytical groundwater solutions were matched to Production and Observation Well drawdown data to generate estimates of aquifer properties for the source aquifer. As identified in **Figure 4** through **Figure 6**, theoretical AQTESOLV® predicted derivatives (red line) were compared to the




Groundwater Permit Technical Analyses Report-Part A
Application No. 41H 30165312
Bozeman Regional Office
Gallatin County

calculated derivatives from the observed drawdown (black triangles) and predicted drawdown (blue line) compared to the observed drawdown (black squares).

For estimation of aquifer properties, the Production and Observation Wells were assumed to be fully penetrating, and a saturated thickness (b) of 218 ft was used, which is length between the bottom of the perforated interval and the swl for the Production Well. Drawdown data and measured flow rates from the aquifer test, and the relative location of the Production Well and Observation Wells were input into AQTESOLV®. As shown in **Figure 4** and **Figure 5**, the Cooper-Jacob (1946) solution was used to perform a preliminary analysis of T and S using the Production and Observation Wells. The drawdown data for the Production Well and Observation Well show slight declines in the derivative throughout the aquifer testing, indicative of leaky-confined aquifer conditions.


The Cooley-Case (1973) solution for leaky-confined aquifers with a water-table aquitard was used to analyze T, S, and the leakage parameters for Observation Well GWIC ID 335313 based on the best-fit visual and statistical match between the observed and theoretical drawdown (**Figure 6**). The Cooley-Case (1973) model assumes a homogenous, isotropic leaky confined aquifer with instantaneous drainage at the water table from storage. **Table 3** lists the aquifer test analyses for the Production and Observation wells. The recommended aquifer T and S to be used in forward modeling is  $873 \, \text{ft}^2/\text{day}$  and  $1.1 \, \text{x} \, 10^{-4}$  from the Cooley-Case (1973) solution for Observation Well GWIC ID 335313. The estimated parameters are supported by existing hydrogeologic data below and the conceptual model of the project location described in the hydrogeologic setting above.






**Figure 4:** Cooper-Jacob (1946) time-drawdown and derivative analysis for the Production Well GWIC ID 335315.





**Figure 5:** Cooper-Jacob (1946) time-drawdown and derivative analysis for the Observation Well GWIC ID 335313.





**Figure 6:** Cooley-Case (1973) time-drawdown and derivative analysis for the Observation Well GWIC ID 335313.

Table 3: Aquifer test analyses for 72.2-hour test completed on the Production Well.

Production Well (GWIC ID, Phase)	Well Analyzed (GWIC ID)	Analysis Solution	T (ft²/day)	S
335315, Drawdown	335315	Cooper-Jacob (1946)	998	NA
335315, Drawdown	335313	Cooper-Jacob (1946)	1,134	1.1 x 10 <sup>-4</sup>
335315, Drawdown & Recovery	335313	Cooley-Case (1973)	873	1.1 x 10 <sup>-4</sup>



**Table 4:** Nearby Aquifer Tests and estimates of T and S when available.

Water Right No.	GWIC ID	Well Completion Depth (ft)	Distance from Proposed Project (miles)	Aquifer Test Length (hours)	Pumping Rate (gpm)	T (ft²/day)	S
41H 30127867	304056	155	1.2	72	240	1,704	1.0E-3
41H 30109060	292561	178	1.7	76	397	28,000	0.1
41H 30109060	292562	158	1.7	72	388	34,000	0.1
41H 30115127	296973	280	2.6	72	206	5,545	4.0E-4
41H 30000136	205719	146	2.6	24	250	1,265	0.1
41H 30010803	215306	140	3.4	72	200	4,680	
41H 30009188	183089	282	4.5	72	583	179	
41H 30048037	95855	171	4.6	72	583	940	0.2

The Quaternary and Tertiary sediments of the Bozeman fan have T ranges of 602 to 8,689 ft²/day and 40 to 361 ft²/day, respectively (Hackett et al. 1960). Further, Custer et al. (1991) provided a T range for the Quaternary and Tertiary sediments of 214 ft²/day to 10,694 ft²day. The reported S range of  $4.0 \times 10^{-4}$  to 0.2 in **Table 4**, supports the confined to unconfined conditions of the Quaternary and Tertiary aquifer system introduced by English (2018). The range of values shown from the aquifer test data in **Table 4**; published literature values; and findings that the Tertiary sediments in the Bozeman Fan subarea are generally less conductive than surrounding basin-fill and sedimentary rock aquifer subareas (Sutherland, 2023), support the recommended property values shown **Figure 6** and **Table 3**.

#### 5.0 Drawdown and Yield Test

An 8.0-hour drawdown and yield test was conducted on the Production Well, GWIC ID 335313. Water levels during the test were collected using an In-situ Leveltroll 400 transducer. The discharge rate was measured with a 4-inch diameter discharge pipe and averaged 275 gpm. Per ARM 36.12.121 and Form 633, background level and recovery data are not required for drawdown and yield tests on additional Production Wells. However, the data was collected and is found in submitted Form No. 633 for GWIC ID 335313 as part of Application No. 41H 30165312.



#### **Drawdown Data**

The 8.0-hour drawdown and yield test started on August 12, 2024, at 09:46 A.M. on the Production Well and is considered (t = 0) for the computation of drawdown. The maximum drawdown in the Production Well was 73.69 ft below the static water level (swl) of 16.06 ft below top of casing (btc), leaving approximately 114 ft of available water column above the bottom of the perforated interval adjusting for the well casing stick-up height of 2-ft.

#### **6.0 Modeling Inputs**

Technical analyses in support of the following criteria assessment: adequacy of diversion, physical availability, and adverse effect (drawdown in existing wells) were modeled in AQTESOLV® (HydroSOLVE INC., 2007) using the following inputs:

- Cooley-Case (1973) solution for fully penetrating wells in an isotropic aquifer
- Well radius of 0.33 ft
- $T = 873 \text{ ft}^2/\text{day}$
- $S = 1.1 \times 10^{-4}$
- r/B;  $1/B = 1.7 \times 10^{-4}$ ;  $5.0 \times 10^{-4}$
- $\beta$ ;  $\beta/r = 7.8 \times 10^{-5}$ ;  $2.4 \times 10^{-4}$
- S'/Sy = 0.001
- L/b' = 0.001

The leakage parameters used to forward model multiple wells were adjusted from r/B and  $\beta$  shown in **Figure 6** to account for the distance of the Observation Well GWIC ID 335313 used to derive aquifer properties from the Production Well 335315 (r = 163 ft). Leakage parameters used to forward model one well were adjusted from r/B and  $\beta$  shown in **Figure 6** to account for the radius of the modeled well (0.3 ft). The storage ratio in the aquitard (S'/S<sub>y</sub>) of 0.001 was taken from **Figure 6** and verified as a representative input using the above estimated parameters, and representative vertical hydraulic conductivity and thickness of the aquitard. The dimensionless height of the capillary fringe (L/b') was taken from **Figure 6**. Monthly pumping schedules and boundaries used to complete technical analyses are identified in subsequent criteria sections.

#### 7.0 Adequacy of Diversion Analysis

An evaluation of the potentially available water column remaining in the proposed wells was modeled in FWD:SOLV (HydroSOLVE INC., 2007) using the following pumping schedule:

 The monthly pumping and injection schedule identified in column 4 and column 7 of Table 5 for one year of pumping.

Predicted theoretical drawdown for the proposed wells was modeled for the period of diversion using the monthly pumping schedule for each well identified in **Table 5**. The Applicant requests



298.40 AF, which was apportioned evenly to each Extraction and Injection Well based on the monthly pumping schedule provided by the Applicant.

Table 5: Proposed monthly extraction and injection schedule for the Applicant's wells.

	I	Extraction Scl	hedule	Injection Schedule			
	GWI	C ID 335313 a	nd 335315	GWIC ID 335309 and 335		and 335811	
Month	Volume	Flow Rate	Flow Rate	Volume	Flow Rate	Flow Rate	
	(AF)	(gpm)	(gpm/well)	(AF)	(gpm)	(gpm/well)	
January	19.2	140.0	70.0	-19.2	-140.0	-70.0	
February	17.3	140.0	70.0	-17.3	-140.0	-70.0	
March	19.2	140.0	70.0	-19.2	-140.0	-70.0	
April	18.6	140.0	70.0	-18.6	-140.0	-70.0	
May	21.2	154.5	77.2	-21.2	-154.5	-77.2	
June	28.0	210.9	105.4	-28.0	-210.9	-105.4	
July	46.9	342.2	171.1	-46.9	-342.2	-171.1	
August	45.3	330.3	165.2	-45.3	-330.3	-165.2	
September	25.7	193.7	96.9	-25.7	-193.7	-96.9	
October	19.4	141.9	71.0	-19.4	-141.9	-71.0	
November	18.6	140.0	70.0	-18.6	-140.0	-70.0	
December	19.2	140.0	70.0	-19.2	-140.0	-70.0	
Total	298.40			-298.40			



As identified in **Table 6**, total drawdown is the sum of interference drawdown and predicted drawdown with well loss. Two extraction and two injection wells are proposed; interference drawdown was calculated using the pumping and injection schedule for each well. Predicted drawdown with well loss is calculated by dividing the predicted theoretical maximum drawdown by a well efficiency value. Well efficiency is calculated by dividing the maximum modeled drawdown for the aquifer test by the maximum observed drawdown of the aquifer test.


The aquifer adjacent to extraction wells GWIC ID 335313 and GWIC ID 335315 would experience a predicted total drawdown of 54.20 ft and 58.90 ft at the end of the first year, respectively. The remaining available water columns for GWIC ID 335313 and 335315 are approximately 134 and 159 ft, respectively. The remaining available water column is equal to the available drawdown above the bottom of the perforations minus total drawdown including interference drawdown.

**Table 6:** The remaining available water column for extraction wells.

Drawdown Estimate	<b>GWIC ID 335313</b>	<b>GWIC ID 335315</b>
Total Depth at Bottom of Perforated Interval (ft btc) <sup>1</sup>	204	234
Pre-Test Static Water Level (ft btc)	16.06	16.05
Available Drawdown Above Bottom of Perforations (ft)	188	218
Aquifer Test Observed Drawdown (ft)	73.69	87.86
Modeled Drawdown Using Average Aquifer Test Rate (ft)	81.00	77.00
Well Efficiency (%)	100	88
Predicted Theoretical Maximum Drawdown from assumed monthly pumping schedule (ft)	52.00	52.00
Predicted Drawdown with Well Loss (ft)	52.00	59.33
Interference Drawdown (ft)	2.20	-0.40
Total Drawdown (ft)	54.20	58.90
Remaining Available Water Column (ft)	134	159


<sup>&</sup>lt;sup>1</sup>The total well depth measuring point (bgs) was adjusted to the top of well casing based on a 2-foot stickup reported on the well logs.





**Figure 7**: Cooley-Case (1973) time-drawdown plot of the predicted theoretical drawdown in the extraction wells at the end of the first year of the assumed monthly pumping schedule.





**Figure 8**: Cooley-Case (1973) time-drawdown plot of the predicted theoretical drawdown in GWIC ID 335313 (dotted line) and GWIC ID 335315 (solid line) including interference drawdown at the end of the first year of the assumed monthly pumping schedule.

#### 8.0 Physical Availability Analysis

An evaluation of groundwater availability in the source aquifer for the purpose of evaluating physical and legal availability was done by calculating groundwater flux through a zone of influence (ZOI) corresponding to the 0.01-foot drawdown contour. The 0.01-foot drawdown contour was modeled in AQTESOLV<sup>®</sup> (HydroSOLVE INC., 2007) using the following pump schedule and boundaries:

 Constant pumping rate of 240.7 gpm and -240.7 gpm for the Extraction and Injection Wells, respectively, for one year of pumping.

The normalized pumping rate required to produce the adjusted annual volume for the Extraction and Injection Wells is 240.7 gpm and -240.7 gpm, respectively. As shown in **Figure 9**, the 0.01-foot drawdown has an average width of approximately 14,000 ft perpendicular to direction of



groundwater flow to the northwest and is truncated to the East Gallatin River. **Appendix A** provides a list of groundwater rights that are within the 0.01-foot drawdown contour.

The calculation for groundwater flux (Q) through the delineated area is given by Eq. 1 and is 122,220 ft<sup>3</sup>/day or 1,024 AF/year:


Q = TWi

where:

 $T = Transmissivity = 873 ft^2/day$ 

W = Width of Zone of Influence = 14,000 ft

i = Groundwater gradient (English (2018); Sutherland (2023)) = 0.01 ft/foot



**Figure 9:** 0.01-foot and 1-foot drawdown contour and water rights (active, severed) within each contour extent for Permit Application No. 41H 30165312.





#### 9.0 Adverse Effect Analyses

Using the Applicant's proposed pump schedule and associated annual volume, potential impacts to existing water rights are evaluated by modeling drawdown in nearby wells and net depletions to surface water(s).

#### 9.1 Groundwater - Drawdown in Existing Wells

The drawdown in existing wells was modeled in AQTESOLV® (HydroSOLVE, Inc., 2007) using the following pump schedule and boundaries:

• The monthly pumping and injection schedule identified in column 4 and column 7 of **Table 5** assigned to the Extraction and Injection Wells for five years of pumping.

The drawdown is the largest at the end of July of the fifth year using the proposed pumping schedule. As identified in **Figure 9**, the 1-foot drawdown contour extends to a maximum of approximately 4,100 ft from the Extraction Wells at the end of July of the fifth year of pumping. The 1-foot drawdown contour includes 13 water rights that are predicted to experience drawdown equal to or greater than one foot (**Appendix B**).

#### 9.2 Surface Water - Net Depletion

Pursuant to *Montana Trout Unlimited v. DNRC*, 2006 MT 72, 331 Mont. 483, 133 P.3d 224, the DNRC recognizes the connection between surface water and groundwater, and the effect of <u>prestream capture</u> and <u>induced infiltration</u> on surface waters.

Net depletions to surface water depend on propagation of drawdown to areas of the aquifer from which water can be captured. Captured water consists of two possible sources – a reduction in the natural discharge (outflow) rate of groundwater from the aquifer (pre-stream capture) or an increase in the natural/artificial recharge (inflow) rate to the aquifer (e.g. induced infiltration). Two important assumptions are made when evaluating net depletions: first the stream and underlying aquifer remain hydraulically connected by a continuous saturated zone, and second, the stream does not become dry. In addition, net depletion is not a function of groundwater flow rate or direction (Theis, 1938; Leake, 2011) and drawdown from pumping can propagate through the entire thickness of the confining layer to overlying aquifers or surface waters (Konikow and Neuzil, 2007).

As such, net depletions are identified for hydraulically connected surface water sources, not including ditches or ephemeral streams. Net depletion is equal to consumption for proposed groundwater use and is described as the calculated volume, rate, timing, and location of reductions to surface water that are offset by return flows (non-consumed water). Net depletion is evaluated by 1) quantifying the consumed volume associated with the proposed use; 2) identifying hydraulically connected surface waters; and 3) calculating the monthly rate and timing of net depletions to affected surface water(s).



#### 1. Consumed Volume

Consumed groundwater does not return to the source aquifer. Consumed volume depends on the proposed use and its associated percentage of known consumption. Depletion is assumed to be equivalent to consumption on an annual basis unless return flows do not accrete to the potentially affected surface water.

Monthly consumption for irrigation, not including turf grass, can be calculated using ARM 36.12.115 irrigation standards and associated efficiency values or the net irrigation requirement (dry year 80% chance) calculated using the USDA Natural Resources Conservation Service (NRCS) IWR program with inputs consistent with DNRC consumptive use rules in ARM 36.12.1902. Monthly consumption for irrigation of turf grass (lawns) is calculated using either a minimum efficiency value of 70% and ARM 36.12.115 lawn and garden standards or the net irrigation requirement from IWR with inputs consistent with DNRC (2010) Consumptive Use Methodology for turf grass.

Consumption for other purposes are listed in **Table 7** and are based on the results of studies by Kimsey and Flood (1987), Vanslyke and Simpson (1974), Paul, Poeter, and Laws (2007), DNRC (2018), wastewater treatment method, operation of systems, or DNRC policy. Net evaporation is calculated using gridded monthly net evaporation values and methodologies associated with DNRC (2023).

**Table 7:** Percent consumption by purpose.

Purpose	Method of treatment/Use	Consumed
Domestic/Municipal*/Commercial/Institutional	Individual drainfields	10%
Domestic/Municipal*/Commercial/Institutional	Central treatment facility with minimal consumption	5%
Domestic/Municipal*/Commercial/Institutional	Evaporation basin or land application	100%
Municipal Use for Municipality	Variable	100%
Water Marketing/Agriculture Spraying/Stock Water/some Industrial Uses	Variable	100%
Geothermal	Open-loop geothermal cooling system with pumping and reinjection wells.	0%
Commercial/Industrial	Aggregate Washing – construction standard for moisture allowed in the finished aggregate product.	5%
Commercial	Snow Making – depends on time of day, machine, weather at time of operation, etc.	10-30%
Fisheries, Recreation, Storage for Irrigation	Net evaporation off reservoir surface, gridded monthly net evaporation values and	AF/acre

<sup>\*</sup>Municipal use for a non-municipality, such as a Water District.



#### **WSB Findings**

For the subject application, the proposed project includes an open-loop geothermal cooling system, and therefore, will have no consumed volume.

#### 2. Hydraulically Connected Surface Water(s) and Location of Net Depletion

Potentially affected surface waters in a net depletion evaluation are identified by their hydraulic connection, both direct and indirect, to the source aquifer of a proposed groundwater diversion. Hydraulic connection depends on the depth to groundwater beneath the beds of surface waters, connection between deep and overlying shallow aquifers, vertical gradients, and can vary along a reach and with time of year.

Procedures for evaluating hydraulic connection and identifying one or more potentially affected surface water(s) for a proposed well in an unconfined/confined aquifer or regional bedrock aquifer can be found in DNRC (2018) and DNRC (2019), respectively. Net depletion is apportioned between multiple potentially affected surface waters generally following procedures described in Section 3.2 of a guidance document developed by the Province of British Columbia (2016) for determining the effect of groundwater diversion on specific streams.

Following protocols in DNRC (2018) **Table 8** identifies published information used to assess hydraulically connected surface water(s). Not all data may be available for each project and is noted as "NA" when that occurs.

**Table 8:** Published information used to identify hydraulically connected surface water(s).

Published Information	Surface Water Source
r abilished illiormation	East Gallatin River
USGS National Hydrographic Dataset (NHD) <sup>1</sup>	Perennial
USGS PROSPER Dataset <sup>2</sup>	Perennial (0.9+)
MBMG GWIC wells, less than 50 ft deep, within 1,000 ft of surface water, static water levels above or within 10 ft of elevation of stream bed (DNRC, 2018) <sup>3</sup>	Mapped GWIC ID's 91805, 91796, 91789, 151869, 151868, 151867, 151871, 165050, 91779 (Figure 13)
Published Water Table Maps, Publications, Previous Water Rights, etc. <sup>4</sup>	Sutherland (2023), Madison (2022), Provisional Permit No. 41H 30115965
Gridded National Soil Survey Geographic Database <sup>5</sup>	Hydric conditions mapped along river (Figure 13)
Aerial imagery	Wet channel (NAIP 2013-2024)
Affidavits, photographs, etc.	NA

<sup>&</sup>lt;sup>1</sup> Review NHD to identify perennial, intermittent, and ephemeral classifications for surface water sources most proximal to the proposed diversion(s).

<sup>&</sup>lt;sup>2</sup> USGS PROSPER probability of streamflow permanence (greater than 50 percent of the time it flows).

<sup>&</sup>lt;sup>3</sup> Per DNRC (2018) hydraulic connection of individual stream reaches to groundwater is evaluated by comparing streambed elevations to static ground water elevations measured in MBMG GWIC wells less than 50 ft deep and within 1,000 ft of surface water or from published water table maps. Surface water within that area is considered




hydraulically connected to the unconfined aquifer if static ground water elevations are above or within 10 ft of the elevation of the stream bed.

<sup>4</sup>No water table maps available.

#### **WSB Scientific Findings**

Based on the review of the published information in **Table 8**, the source aquifer is hydraulically connected to the East Gallatin River, a perennial surface water source. As identified in **Figure 13** the starting point of the depleted reach starts along the northern side of the NWSESW of Section 23, Township 01 South, Range 05 East, Gallatin County.



**Figure 13:** Information used to assess hydrologic connection and location of starting point of the depleted reach on the East Gallatin River for Permit Application No. 41H 30165312.

<sup>&</sup>lt;sup>5</sup> Review Gridded National Soil Survey Geographic Database to identify hydric soils or shallow water tables near surface water sources.



#### 3. Rate and Timing of Depletions

Evaluations of the rate and timing of depletions caused by pumping are based on the basic concept that groundwater pumping eventually is offset by an equivalent increase in recharge or decrease in discharge (Theis, 1940; Leake et al., 2008), a process defined as capture by Lohman (1972). Capture occurs as drawdown propagates to surface water and areas of phreatophyte vegetation (areas of groundwater discharge) that takes water directly from groundwater. In the absence of credible evidence to the contrary, capture of ET by phreatophytes is neglected and net depletion is assumed to equal total capture. This assumption is justified because published estimates for conditions common in Montana alluvial valleys indicate capture of ET generally is less than 10 percent of total capture (Xunhong, 2006). Capture of ET in ephemeral drainages may be significant and will be evaluated on an application-by-application basis.

The rate and timing of net depletion caused by pumping may be modeled using a variety of analytical and numerical models selected to fit site-specific conditions and needs. Simple models including the Alluvial Water Accounting System (AWAS), the Well Pumping Depletion Model (WPDM) or FWD:SOLV (HydroSOLVE, Inc. 2024) typically are used by DNRC to model depletions to one source with simple aquifer boundaries. Adjustments may be made for more complex conditions or multiple sources using methods like those described by Contor (2011), analytical models by Hunt (2003) and Butler et al. (2001) or a superposition numerical groundwater flow model.

Modeling may not be necessary in some situations such as where a proposed use is constant year-round, the source aquifer is confined, or the distance to potentially affected stream reaches is greater than one mile. Modeling net depletions can be simplified if the proposed place of use is located the same relative distance from the potentially affected surface water as the proposed wells and all non-consumed water infiltrates the source aquifer and returns to the potentially affected surface water as return flows. Under those simplifying assumptions, net depletion can be modeled based on withdrawal of the monthly consumed amounts. Otherwise, net depletion by the full withdrawals and return flows need to be modeled separately with net depletion calculated as depletion minus return flows.

The proposed use is geothermal, water will be extracted and injected simultaneously. There would be no consumed volume, and therefore, no timing of net depletions was completed as part of Application No. 41H 30165312.

#### Review

This document has been reviewed on June 30, 2025 in accordance with Category 7 of <u>DNRC's Water Sciences Bureau Minimum Standards of Review</u>, Version 2, February 2024.

#### References

Alluvial Water Accounting System (AWAS), 2003. Integrated Support System at Colorado State University, http://www.ids.colostate.edu/projects.php?project=awas.

Butler, J.J., Zlotnik, V.A., and Tsou, M.S. 2001. Drawdown and stream depletion produced by pumping in the vicinity of a partially penetrating stream. Ground Water 39 (5), 651–659.

Cooley, R.L. and C.M. Case, 1973. Effect of a water table aquitard on drawdown in an underlying pumped aquifer, Water Resources Research, vol. 9, no. 2, pp. 434-447.

Contor, B.A. 2011. Adaptation of the Glover/Balmer/Jenkins Analytical Stream-Depletion Methods for No-Flow and Recharge Boundaries, Idaho Water Resources Research Institute, Technical Completion Report, 15 p.

Cooper, H.H. and C.E. Jacob, 1946. A generalized graphical method for evaluating formation constants and summarizing well field history, Am. Geophysical Union Trans., vol. 27, pp. 526-534.

Custer, S.G., Donohue, D., Tanz, G., Nichols, T., Sill, W., and Wideman, C. 1991. Final report of research results: Ground water potential in the Bozeman-Fan Subarea, Gallatin County, Montana: Bozeman, Mont., Montana State University, 142 p.

DNRC, 2010. Consumptive Use Methodology – Turf Grass (New Projects). March 23, 2010.

DNRC, 2018. Technical Memorandum: Standard Practices for Net Surface Water Depletion from Ground Water Pumping. July 6, 2018.

DNRC, 2019. Technical Memorandum: Physical and Legal Availability of Ground Water, dated April 22, 2019.

DNRC, 2023. Technical Memorandum: Pond and Wetland Evaporation/Evapotranspiration, dated June 7, 2023.

English, A.R. 2018, Evaluation of potential high-yield groundwater development in the Gallatin Valley, Gallatin County, Montana: Montana Bureau of Mines and Geology Open-File Report 698, 22 p., 2 sheets.

Groundwater Information Center (GWIC), Montana Bureau of Mines and Geology, Accessed (2025). http://mbmggwic.mtech.edu/.

Hackett, O.M., Visher, F.N., McMurtrey, R.G., and Steinhilber, W.L., 1960, Geology and groundwater resources of the Gallatin Valley, Gallatin County, Montana: U.S. Geological Survey Water Supply Paper 1482, 282 p., plates 1–11, 11 p.





Harbaugh, A.W. 2000. MODFLOW-2000, the U.S. Geological Survey Modular Groundwater Model—User Guide to Modularization Concepts and the Groundwater Flow Process. U.S. Geological Survey Open File Report 00-92.

Hubbel, J.M., C.W. Bishop, G.S. Johnson, and J.G. Lucas, 1997. Numerical ground-water flow modeling of the Snake River Plain Aquifer using superposition technique, Ground Water, V. 35, N. 1, p. 59-66.

Hunt, B., 2003. Unsteady stream depletion when pumping from semi-confined aquifer. Journal of Hydrologic Engineering 8, no. 1: 12-19.

HydroSOLVE, Inc. 2007. AQTESOLV<sup>®</sup> for Windows, v.4.5. written by G.M. Duffield, http://www.aqtesolv.com/.

HydroSOLVE, Inc. 2024. FWD: SOLV Predictive Modeling Software v.2. written by G.M. Duffield. http://www.aqtesolv.com/fwdsolv.htm

Johnson, G.S. and D.M. Cosgrove, 1999. Application of steady state response ratios to the Snake River plain aquifer. Idaho Water Resources Research Institute, University of Idaho, Moscow, ID, 26 pp.

Kimsey, D.W. and P.K. Flood. 1987. Domestic consumptive use, technical memorandum to the Chief Engineer of the State of Colorado, 16 p.

Konikow, L. F. *and* C. E. Neuzil. 2007. A method to estimate groundwater depletion from confining layers, Water Resources Research., 43, *W07417*, *doi:*10.1029/2006WR005597.

Kruseman, G.P., and de Ridder, N.A. 1990. Analysis and Evaluation of Pumping Test Data. Publication 47. International Institute for Land Reclamation and Improvement, Wageningen, The Netherlands.

Leake, S. A., Pool, D. R., and Leenhouts, J. M. 2008. Simulated effects of ground-water withdrawals and artificial recharge on discharge to streams, springs, and riparian vegetation in the Sierra Vista Subwatershed of the Upper San Pedro Basin, southeastern: U.S. Geological Survey Scientific Investigations Report 2008-5207, 14 p. http://pubs.usgs.gov/sir/2008/5207/sir2008-5207.pdf.

Leake, S.A. 2011. Capture – rates and direction of groundwater flow don't matter! Groundwater, Vol. 49, No. 4, p. 456 – 458.

Lohman, S.W. 1972. Definitions of selected ground-water terms: Revisions and conceptual refinements, U.S. Geological Survey Water Supply Paper, 1988, 21 p., <a href="http://pubs.usgs.gov/wsp/wsp">http://pubs.usgs.gov/wsp/wsp</a> 1988/pdf/wsp 1988.pdf.

Lopez, D.A. 2002. Geologic map of the Conrad 30' x 60' quadrangle, north-central Montana: Montana Bureau of Mines and Geology Open-File Report 444, 11 p., 1 sheet, scale 1:100,000, https://mbmg.mtech.edu/pdf 100k/conrad.pdf

Madison, J.P. 2022. Potentiometric surface in Gallatin, Lower Madison, Lower Jefferson, and Upper Missouri River Valleys within parts of Madison and Gallatin Counties, Montana: Montana Bureau of Mines and Geology Montana Ground-Water Assessment Atlas 8-04, 1 sheet, scale 1:100,000.





Michalek, T. and Sutherland M. 2020. Hydrogeologic investigation of the Four Corners area, Gallatin County, Montana. Montana Bureau of Mines and Geology Open-File Report 735.

Moench, A.F., 1994. Specific yield as determined by type-curve analysis of aquifer-test data: Groundwater, v. 32, No. 6, p. 949-957.

Natural Resources Conservation Service (NRCS), 2003. Irrigation Water Requirement (IWR) computerprogram,

http://www.nrcs.usda.gov/wps/portal/nrcs/detailfull/national/water/manage/?cid=stelprdb1044890.

Neuman, S.P. 1974. Effect of partial penetration on flow in unconfined aquifers considering delayed gravity response, Water Resources Research, vol. 10, no. 2, pp. 303-312.

Soil Survey Staff, Natural Resources Conservation Service, United States Department of Agriculture. Soil Series Classification Database. Available online. Accessed June 2025.

Sutherland, M. 2023. Hydrogeologic investigation of the Belgrade-Manhattan area, Gallatin County, Montana: Superposition groundwater modeling report: Montana Bureau of Mines and Geology Open-File Report 756, 52 p.

Paul, W., Poeter, E., and R Laws. 2007. Consumptive loss from and individual sewage disposal system in a semi-arid mountain environment. Colorado Water, Newsletter of the Water Center of Colorado State University, August/September 2007, Volume 24, Issue 4.

Theis, C.V., 1935. The relation between the lowering of the piezometric surface and the rate and duration of discharge of a well using groundwater storage, Am. Geophys. Union Trans., vol. 16, pp. 519-524.

U.S. Geological Survey (USGSO, USGS National Hydrographic Dataset, accessed (2025), https://landscape11.arcgis.com/arcgis/services/USA Soils Hydric Class/ImageServer

U.S. Geological Survey (USGS), Probability of streamflow permanence model (PROSPER): A spatially continuous model of annual streamflow permanence throughout the Pacific Northwest, accessed (2025), StreamStats web application. <a href="https://streamstats.usgs.gov/ss/">https://streamstats.usgs.gov/ss/</a>

Well Pumping Depletion Model (WPDM) software, 2001. Western Water Consulting, Inc. Littleton, Colorado, http://westernwaterconsulting.com/WPDM.htm.

Wolock, D. 2003. Flow characteristics at U.S. Geological Survey stream gages in the conterminous United States. USGS Open-File Report: 2003-146,

https://water.usgs.gov/GIS/metadata/usgswrd/XML/qsitesdd.xml#stdorder.

Vanslyke, G. and H. Simpson. 1974. Consumptive use of water by homes utilizing leach fields for sewage disposal, technical memorandum by the Colorado Division of Water Resources, 5 p.

Xunhong, C. 2006. Groundwater evapotranspiration captured by seasonally pumped wells in river valleys, Journal of Hydrology, V. 318, Issues 1-4, p. 334-347.



Appendix A: Groundwater Rights within Area of Potential Impact



WRNUMBER	ALL_OWNERS
41H 30127867	FLIR SYSTEMS INC
41H 100672 00	VANIMAN, CECILIA R TRUST; VANIMAN, DONALD D TRUST
41H 80659 00	CRESTVIEW LAKE LLC
41H 113364 00	CECILIA R VANIMAN; DONALD D VANIMAN
41H 115518 00	HIDDEN VALLEY OWNER LLC
41H 115515 00	HIDDEN VALLEY OWNER LLC
41H 40130 00	HIDDEN VALLEY OWNER LLC
41H 39225 00	HIDDEN VALLEY OWNER LLC
41H 115516 00	HIDDEN VALLEY OWNER LLC
41H 115517 00	HIDDEN VALLEY OWNER LLC
41H 42480 00	DALE LILLEJORD
41H 59866 00	LYNN C WINDHAM
41H 60759 00	MICHAEL D COK
41H 90747 00	D2BZ1 LLC
41H 108859 00	JULIE OGHIGIAN; MATTHEW OGHIGIAN
41H 117208 00	WOODY LAURIE BATES REVOCABLE TRUST DATED 4/4/95
41H 96799 00	9019 LLC
41H 30125032	KEVIN KENT
41H 30000996	SARAH HALL
41H 30063822	MICHAEL D COK
41H 30045047	CRESTVIEW LAKE LLC
41H 108896 00	JULIE OGHIGIAN; MATTHEW OGHIGIAN
41H 30162630	KAMERON KELSEY; SALLY KELSEY
41H 25895 00	ABIGAIL L MINFORD; BENJAMIN D PRENTISS
41H 100708 00	COSTCO WHOLESALE
41H 107598 00	GALLATIN CENTER LTD PRTNRSHP
41H 116445 00	BOZEMAN MONTANA HOLDINGS LLC
41H 100715 00	NINETEENTH STREET PARTNERSHIP
41H 30162633	KAMERON KELSEY; SALLY KELSEY
41H 30045048	CRESTVIEW LAKE LLC
41H 39213 00	TRACEY PETER REVOCABLE TRUST
41H 40108 00	S&S DAVIS LLC
41H 30069875	JOSHUA N GRUENBERG; MIKARON F GRUENBERG
41H 116444 00	BOZEMAN MONTANA HOLDINGS LLC
41H 30103555	PETER E GARCIA; TASHA D GARCIA
41H 36789 00	MARY ELLEN BRUHN
41H 80669 00	CAROLYN J TATARKA; RAYMOND J TATARKA
41H 107475 00	JOHN HECHT
41H 107601 00	GALLATIN CENTER LTD PRTNRSHP
41H 113372 00	JOHN D HECHT; MARY HECHT
41H 30148873	KRUSE, KELLY R LIVING TRUST; KRUSE, PATRICIA A LIVING TRUST
41H 40413 00	ROBERT A WHITTMYER; SHARON WHITTMYER
41H 79512 00	CHRISTINA RIFFLE; SCOTT RIFFLE



41H 93745 00	BOB DAVIS; ROXI M DAVIS
41H 30149453	BARTIMCO PROPERTIES LLC
41H 111644 00	JOHN D HECHT; MARY HECHT
41H 139045 00	HEMINGWAY, PATRICK & CAROL T TRUST
41H 6741 00	BOZEMAN, CITY OF
41H 30020414	FHG CONSTRUCTION INC
41H 42468 00	JOHN D HECHT
41H 32752 00	BARBARA F MCLAUGHLIN
41H 30120927	MICHAEL W DINKINS
41H 114302 00	SUSAN R TAYLOR
41H 138 00	NICOLE R BOWER; SPENCER J BOWER
41H 104756 00	ORVILLE WAY LLC
41H 30067919	KENNETH WIRTZ
41H 30106534	STEVEN SMITH
41H 30161488	BURT HAMNER; EMILY MORRILL
41H 39221 00	LARRY D KIRKPATRICK; KAREN S LANZ
41H 47327 00	BMCH RENTALS LLC
41H 96656 00	BRANDON BEAMER
41H 30170704	RICHARD A NOONAN; LEAH J REUTER; RICHARD J REUTER; CAROLYN G WIDMAN
41H 111645 00	FIRST INTERSTATE BANK OF COMMERCE
41H 14010 00	4 CLOVERS LLC; OREILLY PARTNERSHIP LLC; SEVEN OX SEVEN LLC
41H 39746 00	LANTANA CORPORATION
41H 45560 00	BOZEMAN HEALTH URGENT CARE LLC
41H 53161 00	RUSSELL HOSNER LLC
41H 106106 00	KELLER SUPPLY CO
41H 30105693	MONTANA, STATE OF DEPT OF TRANSPORTATION
41H 30047249	CRESTVIEW LAKE LLC
41H 30047250	CRESTVIEW LAKE LLC
41H 103121 00	JERRI K ALEXANDER; LOREN C ALEXANDER
41H 31114 00	BOZEMAN ELEMENTARY DISTRICT NO. 7
41H 95370 00	FETTIS, WILLIAM J TRUST
41H 19409 00	DALLAS J PEUSE
41H 103232 00	G AND S FAMILY TRUST
41H 89705 00	KENNETH WIRTZ
41H 99364 00	SANDAN LLC
41H 59783 00	VANIMAN, CECILIA R TRUST; VANIMAN, DONALD D TRUST
41H 23019 00	DAROLD E BRUHN; NORMA J BRUHN
41H 23316 00	JAMES D BRUHN
41H 104707 00	VALLEY CENTER LTD PRTNRSHP
41H 114952 00	BOZEMAN 6 RE LLC
41H 16414 00	WALDO E KUCHLING
41H 17696 00	FLOYD MATHISON
41H 17715 00	K SCOTT HALL; TERESA C HALL
41H 18751 00	KEVIN KENT



41H 21416 00	JOHN WESEN
41H 22014 00	ORR F MARY; MICHAEL J SWEENEY
41H 22940 00	FIVEFOLD HOLDINGS LLC
41H 23687 00	MARY S SEED; RAYMOND B SEED
41H 28957 00	JOSEPHINE Z HOWE; ROBERT H HOWE
41H 31360 00	LAURA F BARRY; STEPHEN R BARRY
41H 32618 00	LINDA K ANDERSON
41H 34684 00	JOSHUA C CAMPBELL
41H 36426 00	RONALD D GREEN; RUTH A GREEN
41H 37428 00	BOZEMAN ELEMENTARY DISTRICT NO. 7
41H 40139 00	DEBRA A GILL; MICHAEL L GILL
41H 44265 00	CRAYTON, ROBERT F & CYNTHIA REVOCABLE LIVING TRUST
41H 44266 00	CRAYTON, ROBERT F & CYNTHIA REVOCABLE LIVING TRUST
41H 49600 00	PATTERSON PLACE LLC
41H 55200 00	KEVIN J FRANK
41H 58361 00	TODD J PIERONI
41H 75642 00	ROBERT L ADAMS; JOHN L MARCELLA; PAMELA J MARCELLA
41H 9574 00	DYPEX INC
41H 30149451	BARTIMCO PROPERTIES LLC
41H 89647 00	RR1045 LLC
41H 104721 00	ANITA L SAUNDERS; R ED SAUNDERS
41H 110100 00	CARRIE MCCLAUGHRY; TOBIAS H MCCLAUGHRY
41H 30047450	CHAD MUESKE
41H 30048611	SOUTH HAMILTON COURT CONDO ASSN
41H 30105386	TAC INVESTMENTS LLC
41H 30043137	CATKIN CONDOMINIUM OWNERS ASSN INC
41H 30147910	ARMKNECHT STEVEN R REVOCABLE LIVING TRUST
41H 100809 00	AMERICAN SIMMENTAL ASSOC INC
41H 30065502	NATHAN S NAPRSTEK
41H 30161243	BRIAN LAPKA
41H 30161244	BRIAN LAPKA
41H 73705 00	ROGER S KIRK
41H 30115761	DERRICK SALVESON; JYLISSA SALVESON
41H 40136 00	CASNURSPROP LLC
41H 108962 00	RIVERGLEN CONDOMINIUMS
41H 30050963	BOZEMAN SCHOOL DIST 7
41H 114948 00	BOZEMAN 6 RE LLC
41H 11915 00	CASNURSPROP LLC
41H 139905 00	ROBERT D LANE; THOMAS E LANE
41H 30005476	JAMES ARMSTRONG; NINA ARMSTRONG
41H 30010468	KINGMA REVOCABLE TRUST
41H 30011859	SANDAN LLC
41H 30012764	SANDAN LLC
41H 30013046	SANDAN LLC



# Groundwater Permit Technical Analyses Report-Part A Application No. 41H 30165312 Bozeman Regional Office Gallatin County

41H 30016832	RICHTER, DELBERT L & DENA S REVOCABLE LIVING TRUST
41H 30021277	P ANDREW VAN ORDEN
41H 30021278	C&C MANAGEMENT LLC
41H 30023647 J	JASON A DARROW
41H 30024622	BAXTER MEADOWS MASTER COMMUNITY ASSN INC
41H 30024623	BAXTER MEADOWS MASTER COMMUNITY ASSN INC
41H 30025056	SANDAN LLC
41H 30028964	BRENT J SCHMOLL
41H 30029336	TURNQUIST REVOCABLE TRUST
41H 30030867	GALLATIN COUNTY SCHOOL DISTRICT # 7
41H 30030868	GALLATIN COUNTY SCHOOL DISTRICT # 7
41H 30031011 J	JACQUELINE J REYGERS; LODY E REYGERS
41H 30041929	HENRY J BOUMA
41H 30042369	GALLATIN COUNTY SCHOOL DISTRICT # 7
41H 30042370	GALLATIN COUNTY SCHOOL DISTRICT # 7
41H 30044488	URBAN VILLA HOMEOWNERS ASSN
41H 30145989	LACEY BUCZALA; ROBERT BUCZALA
41H 361 00	RUSSELL HOSNER LLC
41H 362 00	RUSSELL HOSNER LLC
41H 5099 00	TATARKA FAMILY FARMS LLC
41H 636 00	RONALD K LEWIS



## Appendix B: Groundwater Rights Within 1-foot Drawdown Contour



WRNUMBER	ALL_OWNERS	Well Depth (ft)	Static Water Level (ft)	Drawdown (ft)	Available Water Column (ft)
41H 30161243	BRIAN LAPKA	52	17	8.8	26
41H 30103555	PETER E GARCIA; TASHA D GARCIA	63	23	1.7	38
41H 30041929	HENRY J BOUMA	60	16	2.6	41
41H 107475 00	JOHN HECHT	60	17	1.2	42
41H 30149453	BARTIMCO PROPERTIES LLC	72	5	17.2	50
41H 111644 00	JOHN D HECHT; MARY HECHT	60	6	1.4	53
41H 30065502	NATHAN S NAPRSTEK	82	25	1.2	56
41H 59783 00	VANIMAN, CECILIA R TRUST; VANIMAN, DONALD D TRUST	74	10	1.6	62
41H 30105693	MONTANA, STATE OF DEPT OF TRANSPORTATION	80	10	5	65
41H 30149451	BARTIMCO PROPERTIES LLC	88	9	6.9	72
41H 113364 00	CECILIA R VANIMAN; DONALD D VANIMAN	100	12	1.6	86
41H 30047450	CHAD MUESKE			1	
41H 100672 00	VANIMAN, CECILIA R TRUST; VANIMAN, DONALD D TRUST			1.6	



#### **Groundwater Permit Technical Analyses Report – Part B**

## Department of Natural Resources and Conservation (DNRC or Department) Water Resources Division

Kendrew Ellis, Water Resource Specialist, Bozeman Regional Office

Application No.	41H 30165312	Proposed Point of Diversion	SWSESE Section 22, T1S, R5E, Gallatin County
Applicant	Barnard Construction		

#### Overview

This report is Part B of a two-part publication which analyzes data submitted by the Applicant in support of the above-mentioned water right application. This report provides technical analyses as required under the Administrative Rules of Montana (ARM) 36.12.1303 in support of the water rights criteria assessment as required in § 85-2-311, Montana Code Annotated (MCA).

This Groundwater Permit Technical Analyses Report – Part B contains the following sections:

Overview	1
Variances	2
1.0 Application Details	2
2.0 Surface Water Analysis of Depleted Surface Water	1
3.0 Area of Potential Impact Analysis of Depleted Surface Water	1
Review	
References	





#### **Variances**

A variance from the requirements found in ARM 36.12.121(3)(a) "pumping must be maintained throughout the duration of the test and the rate may not depart from the average pumping rate by more than 5%" was granted from the Bozeman Regional Office April 14, 2025. Multiple times throughout the first 1,620 minutes of the aquifer testing, the measured discharged fluctuated slightly more than 5% from the average measured discharge rate of 269.5 gpm. From 1,620 minutes until the end of the test, the pumping was maintained at a constant discharge rate and consistent drawdown was collected in both the Production and Observation Wells.

A variance from the requirements found in ARM 36.12.121(3)(e)(iii) "the testing procedures for a minimum eight-hour drawdown and yield test performed on any production well must follow (a), (d), and (h)" was also granted from the Bozeman Regional Office on April 14, 2025. During the first 16-minutes of the eight-hour drawdown and yield test, the discharge started at 225 gpm and was raised to up to approximately 275 gpm with an average measured discharge rate of 263.8 gpm. The discharge deviation greater than 5 % at the start of well testing is common, and the remainder of the pumping was maintained at a constant discharge rate. The requirements for drawdown at yield test under 3(e)(iii), specifically 3(d) and 3(h) were met.

A variance from the requirements found in ARM 36.12.121(3)(g) "to monitor background groundwater levels in the production well and observation well(s) at frequent intervals for at least two days prior to beginning the aquifer test according to From No. 633" was also granted from the Bozeman Regional Office on April 14, 2025. The background water levels in the Production Well and Observation Well 1 were collected two days prior to the day of aquifer testing. The water level difference in the Production Well on the day prior to the aquifer testing was 0.1 ft. The drawdown and recovery data in the Production Well and Observation Well 1 did not appear to be affected by any background level trends. The background level data collected for Observation Well 2 represented the start of the aquifer testing. However, clear interference drawdown was shown in Observation Well 2 and impacts from background levels were not recognizable.

A variance from the requirements found in ARM 36.12.121(3)(h) "water levels in the production well and/or observation well(s) must be reported with 0.01-foot precision according to the schedule specified on Form No. 633" was also granted from the Bozeman Regional Office on April 14, 2025. The Applicant does not follow minimum required time increment schedule for Observation Well 1 and 2 for first 60 minutes of data collection. The remainder of the data collection period fulfilled the requirements of 3(h) and is adequate for obtaining aquifer properties.

#### 1.0 Application Details

The Applicant proposes to divert groundwater from 1/1 to 12/31 for non- consumptive geothermal use from two extraction well points of diversion (PODs) in the SWSESE Section 22,



T1S, R5E, Gallatin County (EX-1 and EX-2). The two injection wells for the project are located in SESWSE Section 22, T1S, R5E, Gallatin County (IN-1 and IN-2). The wells will divert a total 298.38 AF at a total flow rate of 550 GPM (275 GPM per well) from 1/1 to 12/31 to provide geothermal cooling for the commercial building in SESWSE and SWSESE Section 22 and NWNENE Section 27, T1S, R5E, all in Gallatin County, as seen in **Table 1** and **Figure 1**.

**Table 1.** Summary of the proposed use.

Source	Flow Rate	Diverted Volume	Consumed Volume	Purpose	Period of Use	Place of Use	Point(s) of Diversion	Period of Diversion
Groundwater	550 GPM	298.38 АF/уг	O AF	Geothermal	1/1- 12/31	SESWSE & SWSESE Section 22, T1S, R5E, Gallatin County  NWNENE Section 27, T1S, R5E, Gallatin County	SWSESE Section 22, T1S, R5E, Gallatin County SWSESE Section 22, T1S, R5E, Gallatin County	1/1-12/31






Figure 1: Map of the Applicant's proposed POD on the source and proposed place of use by Water & Environmental Technologies dated 5/5/2025.





#### 2.0 Surface Water Analysis of Depleted Surface Water

As net depletions to the surface water source are 0 AF, the Department did not find the physical availability of the surface water source for later comparison to downstream legal demands.

#### 3.0 Area of Potential Impact Analysis of Depleted Surface Water

The Area of Potential Impact for this application is: The proposed use is non-consumptive, and a net depletion of 0 AF was identified for the hydraulically connected surface water. No area of potential impact for surface water was identified because no net depletion will occur.



Groundwater Permit Technical Analyses Report- Part B
Application No. 41H 30165312
Bozeman Regional Office
Gallatin County

#### Review

This document has been reviewed by the Department on July 7, 2025.

#### References

Department Standard Practice for Determining Physical Availability of Surface Water Department Standard Practice for Area of Potential Impact Analysis

## **Preapplication Materials**

- Preapplication Meeting Request
- Preapplication Meeting Form
- All attachments
- All correspondence prior to application receipt

# Preapplication Materials



### PREAPPLICATION MEETING FORM

§ 85-2-302

Form No. 600P (Revised 4/2024)

#### PREAPPLICATION MEETING FEE

\$ 500

#### FILING FEE REDUCTION & EXPEDITED TIMELINE

An application will be eligible for a filing fee reduction and expedited timelines if the applicant completes a preapplication meeting with the Department (ARM 36.12.1302(1)), which includes submitting any follow-up information identified by the Department (ARM 36.12.1302(3)(c)) and receiving either Department-completed technical analyses or Department review of applicant-submitted technical analyses (ARM 36.12.1302(4) and (5)). An application for the proposed project also must be submitted within 180 days of delivery of Department technical analyses or scientific credibility review and no element on the submitted application can be changed from the completed preapplication meeting form (ARM 36.12.1302(6)).

For Department Use Only	For D	epartment	Use	Only
-------------------------	-------	-----------	-----	------

Application # 30165312 Basin 41H
Meeting Date 2/11/2025 Time 1:00

Completed Form Deadline 8/10/2025

#### **RECEIVED**

#### **MAY 01 2025**

#### DNRC

#### **BOZEMAN WATER RESOURCES**

Completed Form Received					
Fee Rec'd \$500	Check #				
Deposit Receipt # CC					
Payor WET					
Refund \$	Date				

The Department will fill out Form No. 600P and will identify follow-up during the preapplication meeting. The Department and Applicant will sign the Preapplication Meeting Affidavit and Certification within five business days. Within 180 days of the preapplication meeting, the Applicant will complete identified follow-up on a separate document with the question numbers clearly labeled.

#### Applicant Information: Add more as necessary.

Applicant Name Bamard Construction			
Mailing Address 701 Gold Avenue	City Bozeman	State MT	Zip 59715
Phone Numbers: Home	Work 406-586-1995	Cell 406-59	5-2201
Email Address <u>matthew.engel@barnard-inc.cor</u>	m		
Applicant Name			
Mailing Address	City	State	Zip
Phone Numbers: Home	Work	Cell	
Email Address			
Contact/Representative Information: A	Add more as necessary		
Contact/Representative is:	Consultant Attorney	Other (descri	be)
Contact/Representative Name Pat Thomson (Wi			
Mailing Address <u>480 Fast Park St</u>	City Butte	State <u>MT</u>	Zip <u>59701</u>
Phone Numbers: Home	Work <u>406-782-5220</u>	Cell_406-490	0-0329
Email Address pthomson@waterenvtech.com			
NOTE: If a contact person is identified as an atto	orney, all communication will be se	ent only to the attorney	unless the attorney

**NOTE:** It a contact person is identified as an attorney, all communication will be sent only to the attorney unless the attorney provides written instruction to the contrary. If a contact person is identified as a consultant, employee, or lessee, the individual filing the water right form or objection form will receive all correspondence and a copy may be sent to the contact person.

Meeting Attendees: Add more as necessary.

Name	Organization	Position
Pat Thomson	WET	Senior Hydrogeologist
Matt Engel	Barnard Construction	Project Manager
Evan Norman	DNRC	Groundwater Hydrologist
Kerri Strasheim	DNRC	Regional Manager
Kendrew Ellis	DNRC	Water Resources Specialist
Derek Rasmussen	DNRC	Water Resources Specialist
Lyra Reynolds	DNRC	Hydrologist

### Table of Contents

Application Details	
Surface Water	<del>(</del>
Surface Water: Physical Availability	
Surface Water: Physical Availability: Ephemeral Surface Water: Physical Availability: Lakes	
Surface Water: Physical Availability: Other	1
Surface Water: Identification of Legal Demands in Area of Potential Impact Surface Water: Basin Closure Area	
Groundwater	13
Groundwater: Physical Availability	13
Groundwater: Physical Availability: Well/Pit	
Groundwater: Physical Availability: Developed Spring	
Groundwater: Physical Availability: Ponds	
Groundwater: Identification of Groundwater Legal Demands	
Groundwater: Adverse Effect to Existing Groundwater Rights	
Groundwater: Physical Availability of Depleted Surface Water Source(s)	
Groundwater: Legal Availability of Depleted Surface Water Source(s)	
Groundwater: Adequacy of Diversion	
Groundwater: Basin Closure Area	20
Project-Specific Questions	21
Project-Specific Questions: Controlled Groundwater Areas and Basin Closures	21
Project-Specific Questions: Place of Storage	23
Project-Specific Questions: Ditch-Specific Questions	
Project-Specific Questions: Water Marketing	
Non-Mandatory Questions for Criteria Analysis	20
Adverse Effect	26
Adequate Diversion Means and Operation	
Beneficial Use	
Possessory Interest	29
PREAPPLICATION MEETING AFFIDAVIT & CERTIFICATION	30
FOLLOW-UP PAGE	31
AMENDED RESPONSES PAGE	
FOLLOW-UP PAGE AFFIDAVIT & CERTIFICATION	

#### **Application Details**

The following questions are mandatory and must be filled out before the Preapplication Meeting Form is determined to be complete. Narrative responses that are larger than the space provided can be answered in an attachment. If an attachment is used, mark the see attachment ("A") checkbox on this form and label the attachment with the question number. Constrain narrative responses to the specific question as is asked on the form; do not respond to multiple questions in one narrative. Label units in narrative responses. Responses in the form of a table may be entered into the table provided on this form or in an attachment. Responses in the form of a table that are larger than the table provided on this form should be placed in an attachment. If an attachment is used, the table must have the exact headings found on this form, and the see attachment ("A") checkbox must be marked. For tables in this form, circle correct unit at header of column when faced with a choice of units. For tables in attachments, label all units. Questions that require Applicant to submit items to the Department have a submitted ("S") checkbox, which is marked when the required item is attached to the Preapplication Meeting Form. Label all submitted items with the question number for which they were submitted. For all questions where follow-up is necessary, mark the "F" checkbox in the "Follow-Up" column and write the question number on the "Follow-Up Page".

	Questions, Narrative	Responses, and Tables				Check- boxes	Follow -Up
1. Do you elect to have DNRC of	conduct Technical Analyses?					Υ□N	□F
2. Provide a map created on an a range, a north arrow, all proposed conveyance structure		S	■ F				
1 5	orm 600 may be the incorrect	Basin Closure Area? If yes, immediatorm, or this project may not meet the		•		Υ□N	□F
4. Is the proposed use temporary	7?					Y ■ N	□F
a. If yes, when will the	appropriation cease?					A	□F
5. Describe the proposed purpos MM/DD), flow rate (GPM or		od of diversion (MM/DD-MM/DD),	period of use (MI	M/DD-		A	□F
Purpose	Period of Diversion	Period of Use	Flow Rate			Volume	e
	(MM/DD-MM/DD)	(MM/DD-MM/DD)	Flow Rate	GPM	CFS	(AF)	
Geothermal Cooling	1/1-12/31	1/1-12/31	550	✓			0
		Total	550				0



POD #	1/4	1/4	1/4	Sec	Twp	Rge	County	Lot	Block	Tract	Subdivision	Gov Lot	SW or GW	Source	Name	Mean	IS	
1	SE			22	15	5E	GALLATIN	26	7		NELSON MEADOWS		GW	GROUN	IDWATER		WEL	_
_2	SE	SW	SE	22	18	5E	GALLATIN	26	7		NELSON MEADOWS		GW	GROUN	IDWATER		WEL	L
	_	_																_
	-				-													_
					-													_
7. Wł	nat are	the s	geoco	des of	the plac	ce of us	se?				***					Tα		
										T		_						
06-09	104-2	<u> </u>	<u>U T-Z</u>	<u> 2-000</u>	<u>IU</u>			_		<u> </u>								-
1														_				
										1								_
						on for tl	he proposed pl	ace of	use and,	if an irr	rigation or law	n and g	arden pu	rpose, list	the	□ A		
nur	nber (	of irri	gated	acres.	•				use and,							□ A		
	nber (	of irri		acres.			1/4	ace of		if an irr	S	ec	arden pu	p	Rge		Cou	
nur	nber (	of irri	gated	acres.	•		1/ <sub>4</sub> SE		SW	1/4	SE S	ec 22		7p 1S	Rge	5 <u>E</u>	GA	LL
nur	nber (	of irri	gated	acres.	•		1/ <sub>4</sub> SE		SW	1/4	SE SE	22 2 2		1 <u>S</u>	Rge	5E	GA (19	II.
nur	nber (	of irri	gated	acres.	•		1/ <sub>4</sub> SE		SW	1/4	SE S	ec 22		7p 1S	Rge	5 <u>E</u>	GA	II.
nur	nber (	of irri	gated	acres.	•		1/ <sub>4</sub> SE		SW	1/4	SE SE	22 2 2		1 <u>S</u>	Rge	5E	GA (19	II.
nur	nber (	of irri	gated	acres.	•		1/ <sub>4</sub> SE		SW	1/4	SE SE	22 2 2		1 <u>S</u>	Rge	5E	GA (19	II
nur	nber (	of irri	gated	acres.	•		1/ <sub>4</sub> SE		SW	1/4	SE SE	22 2 2		1 <u>S</u>	Rge	5E	GA (19	IL
nur	nber (	of irri	gated Gov't	acres.	•		1/ <sub>4</sub> SE		SW	1/4	SE SE	22 2 2		1 <u>S</u>	Rge	5E	GA (19	IL
nur	nber (	of irri	gated	acres.	•		1/ <sub>4</sub> SE		SW	1/4	SE SE	22 2 2		1 <u>S</u>	Rge	5E	GA (19	L
nur	nber (	of irri	gated Gov't	acres.	•		1/ <sub>4</sub> SE		SW	1/4	SE SE	22 2 2		1 <u>S</u>	Rge	5E	GA (19	IL
Acres	mber o	of irri	gated Gov't  Fotal	Lot	Block	k	1/ <sub>4</sub> SE	1/4	SW SE NE	1/4	SE SE NE	22 22 23		1 <u>S</u>	Rge	5E 5 E	GA (AA	II
Acres	ll othe	of irri	gated Gov't	Lot  ght(s) s	Block	nent or	SE SW	1/4	SW SE NE	1/4 ntribute	SE SE NE to the purpos	ec 22 22 23 23 e(s)?	Tw	1 <u>S</u>	Rge	5E	GA (AA	L



Reserve the project map (question 2).    POD	wat	er (SV	W), so	ource	name,	and me	eans of					es, if source is l). Label each					□А		□F
2 SE SW SE 22 18 5E GALLATIN 26 7 NELSON MEADOWS GW GROUNDWATER WELL  7. What are the geocodes of the place of use?  8. Describe the legal land description for the proposed place of use and, if an irrigation or lawn and garden purpose, list the number of irrigated acres.    Acres   Gov't Lot   Block   1/4	POD					_		County	Lot	Block	Tract	Subdivision	l l		Source N	lame	Means	8	
7. What are the geocodes of the place of use?    O6-0904-22-4-01-25-0000		SE	SW	SE	22	1S	5E	GALLATIN	26	7		NELSON MEADOWS	+		GROUND	WATER		WEL	L
8. Describe the legal land description for the proposed place of use and, if an irrigation or lawn and garden purpose, list the number of irrigated acres.    Acres   Gov't Lot   Block   1/4	2				22	1S	5E	GALLATIN	26	7		NELSON MEADOWS		GW	GROUND	WATER		WEL	L
8. Describe the legal land description for the proposed place of use and, if an irrigation or lawn and garden purpose, list the number of irrigated acres.    Acres   Gov't Lot   Block   1/4																			
8. Describe the legal land description for the proposed place of use and, if an irrigation or lawn and garden purpose, list the number of irrigated acres.    Acres   Gov't Lot   Block   1/4																			
8. Describe the legal land description for the proposed place of use and, if an irrigation or lawn and garden purpose, list the number of irrigated acres.    Acres   Gov't Lot   Block   1/4																			
8. Describe the legal land description for the proposed place of use and, if an irrigation or lawn and garden purpose, list the number of irrigated acres.    Acres   Gov't Lot   Block   1/4																			
8. Describe the legal land description for the proposed place of use and, if an irrigation or lawn and garden purpose, list the number of irrigated acres.    Acres   Gov't Lot   Block   1/4   1/4   1/4   Sec   Twp   Rge   County	7. Wh	at are	the g	geoco	des of	the plac	ce of us	se?									□A		$\Box$ F
number of irrigated acres.    Acres   Gov't Lot   Block   1/4   1/4   1/4   Sec   Twp   Rge   County	06-09	04-2	2-4-(	01-2	5-000	0													
number of irrigated acres.    Acres   Gov't Lot   Block   1/4   1/4   1/4   Sec   Twp   Rge   County																			
number of irrigated acres.    Acres   Gov't Lot   Block   1/4   1/4   1/4   Sec   Twp   Rge   County																			
number of irrigated acres.    Acres   Gov't Lot   Block   1/4   1/4   1/4   Sec   Twp   Rge   County																			
9. Will other water right(s) supplement or overlap the place of use to contribute to the purpose(s)?						scriptio	n for th	ne proposed p	lace of	use and,	if an irr	igation or law	n and g	arden pur	pose, list t	the	ПА		ПБ
9. Will other water right(s) supplement or overlap the place of use to contribute to the purpose(s)? □ Y ■ N □ F	nun	iber c	of irri	gated	acres.							<i></i>		1	r,				
9. Will other water right(s) supplement or overlap the place of use to contribute to the purpose(s)? □ Y ■ N □ F		iber c				Block	ζ.	1/4	1/4			Se						Cour	
9. Will other water right(s) supplement or overlap the place of use to contribute to the purpose(s)? □ Y ■ N □ F		iber o				Block	ζ.		1/4	SW		Se	ec		p	Rge			nty
9. Will other water right(s) supplement or overlap the place of use to contribute to the purpose(s)? □ Y ■ N □ F		iber o				Block	ζ.		1/4	SW		Se	ec		p	Rge			nty
9. Will other water right(s) supplement or overlap the place of use to contribute to the purpose(s)? □ Y ■ N □ F		iber o				Block	ζ		1/4	SW		Se	ec		p	Rge			nty
9. Will other water right(s) supplement or overlap the place of use to contribute to the purpose(s)? □ Y ■ N □ F		iber o				Block	K		1/4	SW		Se	ec		p	Rge			nty
9. Will other water right(s) supplement or overlap the place of use to contribute to the purpose(s)? □ Y ■ N □ F		iber o				Block	ζ		1/4	SW		Se	ec		p	Rge			nty
9. Will other water right(s) supplement or overlap the place of use to contribute to the purpose(s)? □ Y ■ N □ F		nber c				Block	ζ		1/4	SW		Se	ec		p	Rge			nty
9. Will other water right(s) supplement or overlap the place of use to contribute to the purpose(s)? □ Y ■ N □ F		nber c				Block	ζ		1/4	SW		Se	ec		p	Rge			nty
		nber o				Block	ζ		1/4	SW		Se	ec		p	Rge			nty
a. If yes, summarize how the water rights will be operated as a whole to serve the purpose(s).		nber o	G	Sov't]		Block	ζ		1/4	SW		Se	ec		p	Rge			nty
a. If yes, summarize now the water rights will be operated as a whole to serve the purpose(s).	Acres		T	lov't	Lot			SE			1/4	SE Se	22 22		p	Rge	E	GA	nty LLATIN
	9. Wil	l othe	To the result of	ov't	Lot ht(s) s	upplem	ent or	SE overlap the pl	ace of t	use to co	1/4  ontribute	SE Se state of the purpose	ec 22 22 e(s)?	Tw	p	Rge	E	GA	LLATIN F
	9. Wil	l othe	To the result of	ov't	Lot ht(s) s	upplem	ent or	SE overlap the pl	ace of t	use to co	1/4  ontribute	SE Se state of the purpose	ec 22 22 e(s)?	Tw	p	Rge	E	GA	LLATIN F
	9. Wil	l othe	To the result of	ov't	Lot ht(s) s	upplem	ent or	SE overlap the pl	ace of t	use to co	1/4  ontribute	SE Se state of the purpose	ec 22 22 e(s)?	Tw	p	Rge	E	GA	LLATIN F
	9. Wil	l othe	To the result of	ov't	Lot ht(s) s	upplem	ent or	SE overlap the pl	ace of t	use to co	1/4  ontribute	SE Se state of the purpose	ec 22 22 e(s)?	Tw	p	Rge	E	GA	LLATIN F

Form No. 600P

1.1	or overlapping water right, pleased/DD), flow rate (GPM or CFS), a		, purpose, typical period of diversi	ion	□ A	□F
Water Right No.	Avg. Period of Diversion (MM/DD-MM/DD)	Avg. Period of Use (MM/DD-MM/DD)	Flow Rate (GPM or CFS)	Volun	ne Contribut	ed (AF)
11 Will this application su	upplement contract water from a F	Sederal Project, ditch compa	nv. or other source?		□Y■N	□F
a. If yes, explain.	**		ily, or outer source.			
	ve one or more place(s) of storage rns. If yes, answer questions 53 to		nan 0.1 acre-feet? This does not in	clude	□Y■N	□F
13. Does the project involv	ve one or more conveyance ditche	es? If yes, answer questions of	62 to 64 for ditch-specific question	ns.	□Y■N	□F
Addendum Application		t for Appropriations Greater	? If yes, you must submit a Criteri- than 5.5 CFS and 4,000 AC-FT (F		□Y■N	□F
	ng water for use outside of Montar with the application. The out-of-st		omit an Out-of-State Use Addendu in §85-2-402(6), MCA.	ım	□Y■N	□F
1 0	de the water marketing purpose? I Idendum (Form 600/606-WMA) v	2	o 71 for water marketing. A Water tion submittal.	*	□Y■N	□F
1 3	6 6		sultation with and review of your poe required at application submitta		□Y■N	□F

Surface Wa	ater							
	Applicable, move or							
The following to be completed by the complete to the complete	ng questions are mand	atory for surface wa	iter permit application	ns and must be fil	led out before the	Preapplication Me	eting Form is a	letermine
ю ве сотри	eie.							
Surj	face Water: Physical	Availability						
Questions	Questions, Narrative Responses, and Tables							
18. What i	s the flow rate (GPM	or CFS), volume (A	F), period of diversion	n start date and er	nd date (MM/DD-	MM/DD), and	□ A	<u>-Up</u> □ F
	type (e.g., perennial, each point of diversion.		point of diversion? Us	e the same POD 7	# as the project ma	ap (question 2) to		
POD#	Flow Rate (GPM or CFS)	Volume (AF)	Period Start (MM/DD)	Period End (MM/DD)	Source Type			
19. What i	s the source type of the	e surface water dive	rsion?				□ A	□F
Perennia	l or Answer	Ephemeral	Answer questions	Lakes	Answer	Other	Answer	
intermitt	ent question 20		22 to 24		question 25		question 26	)
		Physical Availability able □ Not Applica	v: Perennial or Internable	mittent				
20. Is strea	ım gage data available	?					$\square$ Y $\square$ N	□F
a.	If yes, answer the fol	llowing questions re	lated to the number of	f stream gages that	at are available.			
	i. One stream	gage is available						
	1. Wha	at is the gage name?						□F

Form No. 600P

Surface Water

6

2.	Who operates and maintains the gage?		□F
3.	Is the stream gage upstream or downstream of point(s) of diversion?		□F
4.	Is there a limiting or controlling factor that would make the Drainage Area Method not practical? This includes dams that control the flow and streams with large gaining and/or losing reaches. If you have questions about this, please contact the Regional Hydro-Specialist or the Water Sciences Bureau.	□Y□N	□F
5.	Is the period of record greater than or equal to 10 years?	$\square$ Y $\square$ N	□F
6.	How frequently is stage data recorded?		□F
7.	If data gaps were to occur, are they identified and left unfilled or estimated using interpolation, ice correction, or indirect discharge measurements methods?	$\square$ Y $\square$ N	□F
8.	Was the rating curve established and maintained throughout the duration of the period of record using measurements taken near the reference gage and stage recorder according to USGS protocols?	$\square$ Y $\square$ N	□F
9.	Were there requirements for maintaining a permanent gage datum and meeting specified accuracy limits?	$\square$ Y $\square$ N	□F
10.	Does the gage data meet the Department's standard to be sufficient to calculate the median of the mean monthly flow rate and volume during the proposed months of diversion?	$\square$ Y $\square$ N	□F
	a. If yes, this section is complete. Skip to question 27.		
	b. If no, answer question 20.b.		
ii. More t	han one stream gage is available		
1.	List the gage names.		□F
2.	Who operates and maintains the gages?		□F
3.	Is one stream gage upstream and one downstream of point(s) of diversion?	$\square$ Y $\square$ N	□F
4.	Do the stream gages have similar periods of record?	$\square$ Y $\square$ N	□F
5.	Are the periods of record each greater than or equal to 10 years?	$\square$ Y $\square$ N	□F



Surface Water 7

6.	How frequently is stage data recorded at each gage?		□F
7.	For each gage, if data gaps were to occur, are they identified and left unfilled or estimated using interpolation, ice correction, or indirect discharge measurements methods?	$\square$ Y $\square$ N	□F
8.	Were the rating curves established and maintained throughout the duration of the period of record using measurements taken near the reference gages and stage recorders according to USGS protocols?	□Y□N	□F
9.	For each gage, were there requirements for maintaining a permanent gage datum and meeting specified accuracy limits?	$\square$ Y $\square$ N	□F
10.	. Does the gage data meet the Department's standard to be sufficient to calculate the median of the mean monthly flow rate and volume during the proposed months of diversion?	$\square$ Y $\square$ N	□F
	a. If yes, this section is complete. Skip to question 27.		
	b. If no, answer question 20.b.		
	is available or if available gage data does not meet the Department's standard to be sufficient to edian of the mean monthly flow rate and volume during the proposed months of diversion, is the se measured?	$\square$ Y $\square$ N	□F
i. If yes,			
1.	Submit available measurements to the Department.	□S	□F
2.	Who collected the measurements?	□ A	□F
3.	With what method was the data collected?	□ A	□F
4.	What is the period of record?		□F
5.	What is the frequency of measurement?		□F
6.	Are there gaps in the data?	$\square$ Y $\square$ N	□F



Surface Water 8

a. If yes	s, what is the nature of the gaps and how are gaps handled to ensure data quality?	□ A	□F
7. Is there a pro	ocess for maintaining the data and meeting specified accuracy limits?	□Y□N	□F
a. If yes	s, explain.	□ A	□F
	e mean monthly flow rate and volume during the proposed months of diversion?	$\square$ Y $\square$ N	□F
a. If yes	s, this section is complete. Skip to question 27.		
b. If no	, answer question 21.		
	, gage and/or otherwise measured, meet the Department's standard of including a flows to be sufficient to use for calibration of a department-accepted estimation	□Y□N	□F
a. If yes, describe the estimation	n technique.	□ A	□F
b. If no,			
Department's standar	be collected prior to submission of a completed Form No. 600P that meet the rd of including a minimum of high, moderate, and low flows to be sufficient to use for rtment-accepted estimation technique?	□Y□N	□F
1. If yes,			
a. With	what method will the data be collected?	□ A	□F

Form No. 600P

Surface Water

9

	b.	What will be the interval of measurement?		□F		
	c.	Describe the proposed estimation technique.	□ A	□F		
	2. If no,					
	a.	Describe your plan to comply with the requirements of ARM 36.12.1702(1).	□ A	□F		
	b.	Do you plan on requesting a variance from measurement requirements pursuant to ARM 36.12.1702(1)(b)?	$\square$ Y $\square$ N	□F		
		vsical Availability: Ephemeral ble □ Not Applicable				
22.	If you will conduct Technical A Technical Analyses, write N/A	Analyses, what is your plan to calculate mean annual runoff? If DNRC will conduct	□ A	□F		
23.	23. Where do you plan to obtain climate and drainage area data?					
24.	Where is the downstream point	of diversion, which will be used to delineate the drainage basin?	□ A	□F		

Form No. 600P

Surface Water 10

# Surface Water: Physical Availability: Lakes $\square$ Applicable $\square$ Not Applicable

25. Do you have a design plan?			$\Box$ F
a. If yes,	$\Box$ S	□F	
b. If no, h	b. If no, has the lake volume been quantified by a qualified entity based on bathymetric data?		
i.	i. If yes, provide this information to DNRC.		
ii.	ii. If no, answer the following questions,		
	1. When do you plan to collect this information?		□F
	2. With what method will it be collected?	□ A	□F
	ace Water: Physical Availability: Other   Applicable   Not Applicable		
26. Have you meas	26. Have you measured the source?		□F
a. If yes,	inswer the following questions,		
i.	With what method was the data collected?	□ A	□F
ii.	What is the measurement interval?		□F
	1. Does the interval meet the requirements of 36.12.1702(4)?	$\square$ Y $\square$ N	□F
b. If no o	b. If no or if the measurement interval does not meet the requirements of 36.12.1702(4)		
i.	When do you plan to measure?		□F
ii.	With what method will the measurements be collected?	□ A	□F

Form No. 600P

Surface Water 11

#### Surface Water: Identification of Legal Demands in Area of Potential Impact

27. If you are conducting Technical Analysis, how will the Area of Potential Impact be defined? If Department is conducting Technical Analyses, write N/A.	□ A	□F
28. Is the project located in a Basin Closure Area? If yes, explain how the project meets a closure exception. More information about basin closures online at: <a href="https://dnrc.mt.gov/Water-Resources/Water-Rights/Basin-Closures-Stream-Depletion-Controlled-Ground-Water-Areas">https://dnrc.mt.gov/Water-Resources/Water-Rights/Basin-Closures-Stream-Depletion-Controlled-Ground-Water-Areas</a> . Answer the follow-up questions for specific Basin Closure Areas in the "Project-Specific Questions: Controlled Groundwater Areas and Basin Closures" section (questions 51 to 52).		□ F

#### Groundwater

<b>■</b> Applicable	, move on to c	uestion 29.	□ Not Ap	plicable,	skip to c	uestion 47
---------------------	----------------	-------------	----------	-----------	-----------	------------

The following questions are mandatory for groundwater permit applications and must be filled out before the Preapplication Meeting Form is determined to be complete.

Questions, Narrative	Responses, and Tables				Check- boxes	Follow -Up
Groundwater: I	Physical Availability					
29. What is the type of groundwater diversion? Well					 □ A	□F
Well/Pit	Answer questions 30 to 32	Developed Spring	Answer question 33	Pond	Answer questions 34 to 38	

Groundwater: Physical Availability: Well/Pit

■ Applicable □ Not Applicable

□ S	■ F
□Y■N	□F
$\square$ S	■ F
$\square$ Y $\square$ N	□F
$\square$ Y $\square$ N	□F
$\square$ Y $\square$ N	□F
$\Box$ S	□F
$\square$ Y $\square$ N	□F
$\square$ Y $\square$ N	□F
$\square$ Y $\square$ N	■ F
$\square$ Y $\square$ N	□F
	□ Y ■ N □ S □ Y □ N □ Y □ N □ Y □ N □ Y □ N □ Y □ N □ Y □ N □ Y □ N □ Y □ N

Form No. 600P

Groundwater 13

i.	If yes, provide a map with the wells/pits labeled and, if available, with the GWIC ID. Create map on an aerial photograph or topographic map that also includes the following: section corners, township and range, and a north arrow.	□S	□F
ii.	If no, answer the following questions,		
	1. When will the wells/pits be constructed?		□F
	2. Do you have an initial map with the proposed location of wells/pits?	$\square$ Y $\square$ N	□F
	a. If yes, provide an initial map to the Department. Create map on an aerial photograph or topographic map that also includes the following: section corners, township and range, and a north arrow.	□S	□F
	3. Is the requested volume for each new well/pit known?	$\square$ Y $\square$ N	□F
	a. If no, what is the total requested volume (AF) and the number of new PODs?		□F
	undwater: Physical Availability: Developed Spring  ☐ Applicable ■ Not Applicable	1	
33. Have you meas	sured the source?	$\square$ Y $\square$ N	□F
a. If yes,	answer the following questions,		
i.	Do you have flow rate (GPM or CFS) and volume measurements?	$\square$ Y $\square$ N	$\Box$ F
ii.	With what method were measurements collected?	□ A	□F
iii.	What is the interval of measurements?		□F
iv.	Is the interval of measurements sufficient to comply with ARM 36.12.1703(1)?	$\square$ Y $\square$ N	□F
b. If no, o	or if measurements do not comply with ARM 36.12.1703(1),		
i.	When do you plan to measure?		□F

ii. With what method and at what interval will measurements be collected?	□ A	□F
Groundwater: Physical Availability: Ponds  ☐ Applicable ☐ Not Applicable		
34. Have you submitted Form 653 to apply for a variance from ARM 36.12.121 for the Aquifer Test?	$\square$ Y $\square$ N	□F
a. If yes, did the Department approve the variance request?	$\square$ Y $\square$ N	□F
35. Have you submitted measurements to the Department? If yes, describe.	□Y□N	□F
36. Submit pond bathymetry data, survey, or engineering plans to the Department.	$\square$ S	□F
37. Please submit a map identifying the location of the proposed pond to the Department. Create map on an aerial photograph or topographic map that also includes the following: section corners, township and range, and a north arrow.		□F
38. If you are conducting Technical Analyses, what is your plan to determine depth, surface area, and net evaporation of the pond? If DNRC is conducting Technical Analyses, write N/A.	□ A	□F
Groundwater: Identification of Groundwater Legal Demands All information to calculated Zone of Influence was collected in previous questions.  Groundwater: Adverse Effect to Existing Groundwater Rights All information to calculate One-Foot Drawdown Contour was collected in previous questions.  Groundwater: Physical Availability of Depleted Surface Water Source(s)		
39. What are the hydraulically connected surface water source(s)?  East Gallatin River		□F
40. For each hydraulically connected surface water source, is gage data available?	$\square$ Y $\square$ N	□F
a. If yes, answer the following questions for the number of stream gages that are available.		



i. One stream gage is available		
1. What is the gage name?		□F
East Gallatin River abv Water Reclamation Fa nr Bozeman MT USGS 06048560	_	
2. Who operates and maintains the gage?		□ F
USGS		
3. Is the stream gage upstream or downstream of point(s) of diversion?		□F
<u>Upstream</u>		
- Jest 94111	_	
4. Is there a limiting or controlling factor that would make the Drainage Area Method not practical?	□Y■N	$\Box$ F
This includes dams that control the flow and streams with large gaining and/or losing reaches. If		
you have questions about this, please contact the Regional Hydro-Specialist or the Water Sciences		
Bureau.		
5. Is the period of record greater than or equal to 10 years?	■ Y □ N	$\Box$ F
6. How frequently is stage data recorded? <u>15 minutes</u>	_	$\Box$ F
7. If data gaps were to occur, are they identified and left unfilled or estimated using interpolation, ice	$\blacksquare$ Y $\square$ N	$\Box$ F
correction, or indirect discharge measurements methods?		
8. Was the rating curve established and maintained throughout the duration of the period of record	$\blacksquare$ Y $\square$ N	$\Box$ F
using measurements taken near the reference gage and stage recorder according to USGS		
protocols?		
9. Were there requirements for maintaining a permanent gage datum and meeting specified accuracy	$\blacksquare$ Y $\square$ N	$\Box$ F
limits?		
10. Does the gage data meet the Department's standard to be sufficient to calculate the median of the	$\blacksquare$ Y $\square$ N	□F
mean monthly flow rate and volume during the proposed months of diversion?		
a. If yes, this section is complete. Skip to question 42.		
b. If no, answer question 40.b.		
ii. More than one stream gage is available		
1. List the gage names.		$\Box$ F
2. Who operates and maintains the gages?		□F
3. Is one stream gage upstream and one downstream of point(s) of diversion?	$\square$ Y $\square$ N	$\Box$ F



4.	Do the stream gages have similar periods of record?	$\square$ Y $\square$ N	$\Box$ F
5.	Are the periods of record each greater than or equal to 10 years?	$\square$ Y $\square$ N	□F
6.	How frequently is stage data recorded at each gage?		□F
7.	For each gage, if data gaps were to occur, are they identified and left unfilled or estimated using	$\square$ Y $\square$ N	□F
	interpolation, ice correction, or indirect discharge measurements methods?		
8.	Were the rating curves established and maintained throughout the duration of the period of record	$\square$ Y $\square$ N	$\Box$ F
	using measurements taken near the reference gages and stage recorders according to USGS		
	protocols?		
9.	For each gage, were there requirements for maintaining a permanent gage datum and meeting specified accuracy limits?	$\square$ Y $\square$ N	□F
10	. Does the gage data meet the Department's standard to be sufficient to calculate the median of the	$\square$ Y $\square$ N	□F
	mean monthly flow rate and volume during the proposed months of diversion?		
	a. If yes, this section is complete. Skip to question 42.		
	b. If no, answer question 40.b.		
0 0	is available or if available gage data does not meet the Department's standard to be sufficient to	$\square$ Y $\square$ N	$\Box$ F
	edian of the mean monthly flow rate and volume during the proposed months of diversion, is the		
source otherwi	se measured?		
i. If yes,			
1.		$\square$ S	$\Box$ F
2.	Who collected the measurements?	$\Box$ A	$\Box$ F
2	With what method was the data collected?		□F
3.	with what method was the data confected?	□ A	1 L
4.	What is the period of record?		□F
5.	What is the frequency of measurement?		□F
6	Are there gaps in the data?	ПУПИ	□F
υ.	The more gaps in the data:		$\Gamma$

a. If yes, what is the nature of the gaps and how are gaps handled to ensure data quality	□ A	□F
7. Is there a process for maintaining the data and meeting specified accuracy limits?	$\square$ Y $\square$ N	□F
a. If yes, explain.	□ A	□F
8. Does available measurement data meet the Department's standard to be sufficient to calculate the median of the mean monthly flow rate and volume during the proposed months of diversion?	$\square$ Y $\square$ N	□F
a. If yes, this section is complete. Skip to question 42.		
b. If no, answer question 41.		
41. For each hydraulically connected surface water source, does the available measurement data, gage and/or otherwise measured, meet the Department's standard of including a minimum of high, moderate, and low flows to be sufficient to use for calibration of a department-accepted estimation technique?	■ Y □ N	□F
a. If yes, describe the estimation technique.  USGS maintained gage with record greater than 10 years  ———————————————————————————————————	□ A	□F
b. If no,		
i. Will measurements be collected prior to submission of a completed Form No. 600P that meet the Department's standard of including a minimum of high, moderate, and low flows to be sufficient to use for calibration of a department-accepted estimation technique?	□Y□N	□F
1. If yes,		
a. With what method will the data be collected?  ———————————————————————————————————	□ A	□ F

b. What will be the interval of measurement?		□F
c. Describe the proposed estimation technique.	□А	□F
If no, describe your plan to comply with the measurement requirements for hydraulically connected surface water sources.  ———————————————————————————————————	□ A	□F

Groundwater: Legal Availability of Depleted Surface Water Source(s)
All information to determine legal demands for depleted surface water source(s) was collected in previous questions.

Groundwater: Adequacy of Diversion

			Questions, Narr	ative Responses, and Tables			Check-	<b>Follow</b>
							boxes	<u>-Up</u>
42. W	hat is th	e flow rate (GPM or	CFS), volume (AF), ar	nd period of diversion required (MM/D	D-MM/DD) at each		$\square$ A	$\Box$ F
gr	oundwa	ter point of diversion	n? If the POD is a well,	provide the well depth (FT), if availab	le, or estimated well dept	h (FT).		
Pl	lease use	the same POD # as	the project map (questi	on 2) to match this information with th	e location information.	, ,		
POD	) #	Flow Rate	Volume (AF)	Period of Diversion (MM/DD-	Well Depth (FT)	Measu	red or Estim	ated
		(GPM or CFS)	, ,	MM/DD)				
	1	275 GPM	0	1/1-12/31	300		measured	

POD#	(GPM or CFS)	voiume (AF)	MM/DD)	wen Depth (F1)	Measured or Estimated
1	275 GPM	0	1/1-12/31	300	measured
2	275 GPM	0	1/1-12/31	215	measured

43. Will the monthly pumping schedule differ from an allocation of diverted volume by the number of days in the month for	□Y■N	□F
year-round uses or the IWR 80% net irrigation requirements for irrigation/lawn & garden uses (IWR, NRCS 2003)?		

Form No. 600P

•	es, provide the alestion 2).	ternative pumping schedule in	the table below. Use the same	ne POD # as the p	project map	□ A	□F
Month	POD#	Volume (AF)	Month	POD#	Volume (AF)		
January			July				
February			August				
March			September				
April			October				
May			November				
June			December				

Groundwater: Basin Closure Area

44. Are the point(s) of diversion located in a basin closure area? If yes, fill out questions 45 to 46.	$\blacksquare$ Y $\square$ N	$\Box$ F
45. Did you elect in question 1 for the Department to conduct Technical Analysis?	$\blacksquare$ Y $\square$ N	□F
a. If yes, the Basin Closure Area Addendum (Form 600-BCA), Hydrogeologic Report Addendum (Form 600-HRA),		
and Hydrogeologic Report are not required at this time. The Department's Technical Analyses will meet		
requirements of §85-2-360 for Form 600-HRA. Form 600-BCA will be required with application submittal.		
b. If no, submit the Basin Closure Area Addendum (Form 600-BCA), Hydrogeologic Report Addendum (600-HRA),	$\square$ S	$\Box$ F
and Hydrogeologic Report with your Technical Analysis.		
46. If the Hydrogeologic Report indicates that the proposed groundwater use will impact a surface water source, which of the		
following three options best describe your plan to mitigate depletions of hydraulically connected surface water? A separate		
Preapplication Meeting will be required for each application to change a water right to a mitigation or aquifer recharge		
purpose to maintain expedited timelines and reduced filing fees for the project.		
a. Application to Change a Water Right to mitigate the adverse effects created.	□Y■N	□F
b. Alternative mitigation plan.	□Y■N	□F
c. Documentation to show a mitigation plan is not required.	□Y■N	□F

## **Project-Specific Questions**

The following questions are mandatory when applicable and must be filled out before the Preapplication Meeting Form is determined to be complete.

Questions, Narrative Responses, and Tables	Check- boxes	Follow -Up
Project-Specific Questions: Controlled Groundwater Areas and Basin Closures		
47. Is the project located in the East Valley Controlled Groundwater Area?	□Y■N	□F
a. If yes,		
i. Do you have written approval from (1) Lewis and Clark County Board of Health, (2) Lewis and Clark County Water Quality Protection Bureau, (3) the U.S. Environmental Protection Agency, (4) the Montana State Dept. of Environmental Quality and (5) the Montana State Dept. of Natural Resources and Conservation? If the agencies have established a Technical Advisory Group, prior approval by the Technical Advisory Group satisfies this requirement.	□Y□N	□F
ii. Is the project in Zone 2?	$\square$ Y $\square$ N	□F
<ul> <li>i. If yes, provide in the written approval the following recommendations which will also be included as conditions on the appropriation.</li> <li>a. Well design and construction requirements necessary to measure the water level and water quality for any well;</li> <li>b. Water level measurement and water quality sample reporting requirements for any new well;</li> <li>c. Any other requirements necessary to ensure new wells can be operated in a manner consistent with purpose of the EVCGWA.</li> </ul>	□S	□F
iii. Is the project in Zone 1? If yes, a Form 600 cannot be accepted by the Department.	$\square$ Y $\square$ N	□F
48. Is the project located in the South Pine Controlled Groundwater Area?	$\square$ Y $\blacksquare$ N	$\Box$ F
a. If yes, have you completed an Application for Beneficial Water Use Permit South Pine Controlled Groundwater Area Addendum? The addendum needs to be completed by application submittal.	$\square$ Y $\square$ N	□F
49. Is the project located in the Yellowstone Controlled Groundwater Area?	$\square$ Y $\blacksquare$ N	$\Box$ F
a. If yes, is the use over 35 GPM or 10 AF per year?	$\square$ Y $\square$ N	□F
i. If no, this is the incorrect form. Use instead the Yellowstone Controlled Groundwater Area Permit Application (600-YCGA).		
<ol> <li>If yes, answer the remaining parts of question 49. A Yellowstone Controlled Groundwater Area Addendum (600 Y over35) will be required with application submittal.</li> </ol>		
1. Does the proposed use require a point of diversion with water temperature of 60 degrees Fahrenheit or more?	□Y□N	□F
2. What is the ground elevation at the point of diversion?		□F

3. What is the specific conductance at the point of diversion?		□F
4. If an application is in a basin tributary to a category 3 or 4 stream (generally in or upstream of YNP), provide a report prepared by a professional qualified in the science of groundwater hydrology, verifying that the appropriation is not hydrologically connected to surface flow that is tributary to the reserved portion of category 3 or 4 streams.	□S	□F
50. Is the project located in one of the Controlled Groundwater Areas listed on the Department's website ( <a href="https://dnrc.mt.gov/Water-Resources/Water-Rights/Basin-Closures-Stream-Depletion-Controlled-Ground-Water-Areas">https://dnrc.mt.gov/Water-Resources/Water-Rights/Basin-Closures-Stream-Depletion-Controlled-Ground-Water-Areas</a> )?	□Y■N	□F
a. If yes, list which one and describe how the proposed project meets the requirements of the Controlled Groundwater Area. An application must meet the specific requirements of the Controlled Groundwater Area to be accepted by the Department.	□ A	□F
51. Is the project located in one of the administrative, Department ordered, or legislative closures listed on the Department's website ( <a href="https://dnrc.mt.gov/Water-Resources/Water-Rights/Basin-Closures-Stream-Depletion-Controlled-Ground-Water-Areas">https://dnrc.mt.gov/Water-Resources/Water-Rights/Basin-Closures-Stream-Depletion-Controlled-Ground-Water-Areas</a> )?	■ Y □ N	□F
a. If yes, list which one and describe how the proposed project meet the requirements of the closure. An application must meet the specific requirements of the closure to be accepted by the Department.  Upper Missouri Basin Closure - nonconsumptive use	□ A	□F
52. Is the project located in one of the compact closures listed on the Department's website ( <a href="https://dnrc.mt.gov/Water-Resources/Water-Rights/Basin-Closures-Stream-Depletion-Controlled-Ground-Water-Areas">https://dnrc.mt.gov/Water-Resources/Water-Rights/Basin-Closures-Stream-Depletion-Controlled-Ground-Water-Areas</a> )?	□Y■N	□F
a. If yes, list which one and describe how the proposed project meet the requirements of the compact closure. An application must meet the specific requirements of the compact closure to be accepted by the Department.	□ A	□F

# Project-Specific Questions: Place of Storage

storage (use Additional Place of Storage Sheet for additional places of storage). If no, this section is complete, and you can	⊔ Y ■ N	□
skip to question 62.		
54. Provide a map showing the location of the place of storage. Create map on an aerial photograph or topographic map that	$\Box$ S	□F
also includes the following: section corners, township and range, and a north arrow.		
55. Is this application to enlarge an existing reservoir?	$\square$ Y $\square$ N	$\Box$ F
a. If yes, what is the water right number for the existing reservoir?		□F
56. Is the place of storage located on-stream?	$\square$ Y $\square$ N	□F
a. If no, explain the conveyance means to and from the off-stream place of storage and any losses that may occur with that conveyance.	□ A	□F
57. What is the capacity of the proposed place of storage or the existing place of storage after it is enlarged? Use bathymetry data, survey, or engineering plans for capacity. Submit the data source used with this form. In lieu of these data sources, use the following equation: Surface Acres x Maximum Depth (FT) x 0.5 (0.4-0.6 depending on side slope) = Capacity (AF)	□А	□F
58. Will the place of storage include primary and/or emergency spillways? Preliminary design specifications for primary and emergency spillways must be included with application submittal (ARM 36.12.113).	$\square$ Y $\square$ N	□F
59. Will the place of storage be lined?	$\square$ Y $\square$ N	□ F
60. What is the annual net evaporation of water from the place of storage using the standards in ARM 36.12.116(1)? Gridded net evaporation layer is available from DNRC upon request.		□F
61. Is the place of storage capacity calculated to be greater than 50 acre-feet?	$\square$ Y $\square$ N	□F
a. If yes, have you made an application to the DNRC Water Operations Bureau for a determination of whether the dam or reservoir is a high-hazard dam?	$\square$ Y $\square$ N	□F

Project-Specific Questions: Ditch-Specific Questions

62. Does the proposal include at least one conveyance ditch? If yes, answer question 63 and, for each ditch, answer question 64.	$\square$ Y $\blacksquare$ N	$\Box$ F
If no, this section is complete, and you can skip to question 65.		



63. Submit a Ditch Map that shows every ditch conveying water for the proposed project. Label the ditch name(s), POD(s), the POU(s), and the ditch measurement locations (requested in question 64.c). The map should be created on an aerial photograph or topographic map with the following: section corners, township and range, and a north arrow.					□S	□F
_	h, answer the following. If there	e is more than one conveyance	ditch, use an Additional Ditch	Sheet		
for each additional converge a. What is the ditch						
a. What is the ditch	name:					□F
	nce water will be carried by the do not include segments within		le segments between the POD a	and	□ A	□F
characteristics wi	ne set of ditch measurements, we the DNRC to determine the minical eled with the 2-digit measurem	mum number of ditch measure	ements. Include the location of		□S	□F
ID#	Width (FT)	Depth (FT)	Slope (%)	Dat	te of Measure	ement
	I					
	ble Manning's n value? List the mation with the Department.	e factors used for estimation. If	You do not know this value, pl	lease	□ A	□F
e. What type of soil	s compose the proposed convey	rance ditch? For lined ditches,	write "lined" instead.		□ A	□F
f. Are other water r	ghts conveyed by the conveyar	nce ditch?			$\square$ Y $\square$ N	□F
i. If yes,						
1. V	What are the water right number	s?			□ A	□F



2. What is the sum of the flow rates (GPM or CFS) for water rights conveyed?	□ A	□F
3. Provide a map with your best estimate of where the existing POUs begin for the other water rights conveyed by the conveyance ditch for all POUs between the proposed POD and your proposed POU. Create map on an aerial photograph or topographic map that also includes the following: section corners, township and range, and a north arrow.	□S	□F
Project-Specific Questions: Water Marketing		
65. Does the proposal include water marketing? If yes, please answer the questions in this section (questions 66 to 71). If no, this section is complete, and you can skip to question 72.	□Y■N	□F
66. Identify the flow rate (GPM or CFS) and volume (AF) of water that will be marketed.		□F
67. Will the marketed water return to the source?	$\square$ Y $\square$ N	□F
a. Explain how this determination was made.	□ A	□F
68. For what purpose(s) will the marketed water be used?	□ A	□F
69. How will you control or limit access to the water?	□ A	□F
70. Do you have contracts for the entire volume and flow rate sought?	$\square$ Y $\square$ N	□F
71. Provide a service area map. Create map on an aerial photograph or topographic map and shows the following: general service area boundary, section corners, township and range, and a north arrow.		□F



### **Non-Mandatory Questions for Criteria Analysis**

The following questions are not mandatory. They should be discussed in the Preapplication Meeting, but do not need to be filled out before the Preapplication Meeting Form is determined to be complete.

Adverse Effect

Questions, Narrative Responses, and Tables	Check- boxes
72. Do you have evidence that water is legally available in the proper flow rate, volume, and timing?	■ Y □ N
73. If water is not found to be legally available for part or all the proposed period of diversion, what is the plan to address this with the permitting process?  Reduce flow rate to meet legally available quotient; or, purchase mitigation water to subsidize.	□ A
74. Describe your plan to ensure that existing water rights will be satisfied during times of water shortage.  Reduce flow rate to meet legally available quotient; or, purchase mitigation water to subsidize.	□ A
75. Explain how you can control your diversion in response to call being made.  Each diversion is a groundwater well and can be either powered down, or the system is equipped with variable frequency drives that will allow control of flow rates.	□ A
76. Are you aware of any calls that have been made on the source of supply or depleted surface water source?	□Y■N
a. If yes, explain.	□ A
77. Does a water commissioner distribute water or oversee water distribution on your proposed source or depleted surface water source?	□Y■N
Adequate Diversion Means and Operation	
78. Provide a diagram of how you will operate your system from the point of diversion to the place of use.	$\square$ S
79. Describe specific information about the capacity of the diversionary structure(s). This may include, where applicable: pump curves and total dynamic head calculations, headgate design specifications, and dike or dam height and length.  Submersible pump information will be submitted with application	□ A

80. Is the diversion capable of providing the full amount requested through the period of diversion?	■ Y □ N
	$\Box$ A
applicable: ditch capacity and/or pipeline size and configuration.	
Well drop pipe is 4-inch diameter feeding to a 6-inch diameter distribution line passing through heat exchange,	
discharging again to 6-inch lateral line to injections wells.	
82. Describe any losses related to conveyance.	$\Box$ A
The system is closed from the pump to the injection well with no net loss.	
83. Is the conveyance infrastructure capable of providing the required flow and volume and any losses?	■ Y □ N
84. Does the proposed conveyance require easements?	□Y■N
a. If yes, explain.	$\Box$ A
85. Describe any places of storage, including whether drainage devices will be installed, and provide preliminary designs, if available.	$\Box$ A
Preliminary designs will be required at application submittal.	_ /1
86. Describe specific information about how water is delivered within the place of use. This may include, where applicable, the range of	□ A
flow rates needed for a pivot and output and configuration of sprinkler heads.	
The system is closed from the pump to the injection well	
	<u> </u>
	■ Y □ N
	■ Y □ N
	$\Box$ A
Injection wells	

89. Provide a plan of operations.	$\Box$ A
This will be included with the application	
90. Can the plan of operations deliver the flow rate and volume for the beneficial use being requested?	$\blacksquare$ Y $\square$ N
91. Do you have any plans to measure your diversion and use?	■ Y □ N
a. If yes, describe the plan and the type of measurements you will take.	$\Box$ A
The system is equipped with a flow meter / volumizer	

# Beneficial Use

92. Why is the requested flow rate and volume the amount needed for the purpose?	$\square$ A
Demand is based on cooling demands of building. The maximum flow rate is based on the peak cooling day demands	
and will only be required during short-term periods of record temperature.	
93. Does the Department have a standard for the purposes for which water is used? Department standards can be found in ARM	□Y■N
36.12.112.	
a. If yes, does the proposed beneficial use fall within Department standards?	$\square$ Y $\square$ N
94. If no standard, or if proposed beneficial use falls outside of Department standards, explain how the use is reasonable for the purpose.	$\Box$ A
The purpose is to provide geothermal cooling capacity for a commercial building and is designed as a non-consumptive open-loop	
well system with extraction and injection wells returning 100 percent of water back to source aquifer.	
95. Will your proposed project be subject to DEQ requirements for a public water supply (PWS) system or Certificate of Subdivision	□Y■N
Approval (COSA)?	
a. If yes,	
i. Have you researched or consulted with DEQ regarding those requirements?	$\square$ Y $\square$ N
96. Are you proposing to use surface water for in-house domestic use?	□Y■N
a. If yes, does a COSA exist for the proposed place of use?	$\square$ Y $\square$ N
i. If yes, please submit the COSA.	$\Box$ S
ii. If no, have you researched or consulted with DEQ regarding their requirements?	$\square$ Y $\square$ N

# Possessory Interest

97. Do you have possessory interest, or the permission of the party with possessory interest, of the proposed place of use? Proof of possessory interest or permission of the party with possessory interest is required at application submittal.	■ Y □ N
a. If no, explain.	□ A

#### PREAPPLICATION MEETING AFFIDAVIT & CERTIFICATION

"We attest that the information on this form accurately describes the proposed project discussed during the preapplication meeting and that the items marked for follow-up will require the applicant to provide additional information before the form is deemed complete."

"Applicant acknowledges that any information provided by the Department during the preapplication is preliminary and subject to change."

"Applicant acknowledges that if the follow-up information provided to the Department substantially changes the proposed project, for example in a way that alters which sections of the form are applicable or which technical analyses are required, or who is to complete the technical analyses, the applicant will need to schedule a new preapplication meeting so that the department can identify any additional information necessary for completion of the technical analyses (ARM 36.12.1302(3)(c))."

Upon Department receipt of the completed form (within 180 days following the meeting), the Department reserves the first five days of the 45-day period in ARM 36.12.1302(4) or (5) to return the form to the applicant if:

- 1 the completed form does not include all necessary follow-up information identified in the meeting, OR
- 2 the completed form is not adequate for the Department to proceed with technical analyses, OR
- 3 the applicant has elected to complete technical analyses and has not submitted each piece of technical analysis required, OR
- 4 the applicant has substantially changed the details of the proposed project, such as in a way that alters which sections of the form are applicable, which technical analyses are required, or who is to complete the technical analyses.

If the Department returns the form to the Applicant within these five days due to reasons 1-3 above, the Applicant can use the balance of their 180-day period in ARM 36.12.1302(4) or (5) to gather the remaining follow-up information needed. If there is no time remaining in the 180-day period, the Applicant can submit a written request for a new preapplication meeting, pursuant to ARM 36.12.1302(2). Even if there is still time remaining, the Applicant can choose to schedule a new preapplication meeting. The Department shall transfer the \$500 payment received to the new preapplication meeting, or refund the payment to the Applicant if the Applicant desires. If the Department returns the form to the Applicant within these five days due to reason (4) above, the Applicant must submit a written request for a new preapplication meeting, pursuant to ARM 36.12.1302(2). The Department shall transfer the \$500 payment received to the new preapplication meeting, or refund the payment to the Applicant desires.

Matthew Engel	2/11/2025
Applicant Signature	Date
Applicant Signature	Date
Lyra Reynolds	2/11/2025
Department Signature	Date



PROJECT NUMBER THINKM01 DRILLING COMPANY Bridger
PROJECT NAME Barnard Geotherm DRILLER Tyler Sampson

CLIENTBarnard
START DATE 10/08/24

END DATE

MP ELEVATION FT AMSL SCREENED INTERVAL FT115-215 DRILLING COMPANY Bridger Drilling
DRILLER Tyler Sampson
DRILL RIG Foremost DR 24

**DRILLING METHOD** Dual Wall Rotary **CHECKED BY** J Rose

TOTAL DEPTH OF BORING FT 225.00

 ${\color{red}\textbf{COORDINATES}}\ ,$ 

COORD SYS

SURFACE EL. (ft AMSL)

WELL TOC (ft)

LOGGED BY Pat Thomson
DEPTH TO WATER FT

**TOTAL WELL DEPTH FT** 215

BOREHOLE DEPTH (ft) 225.00 SURFACE COMPLETION GROUT Bentonite

BOREHOLE DIAMETER (in) CASING TYPE Steel FILTER PACK 10/20 Sand

SCREEN TYPE Stainless Steel Continuous wire w SEAL TYPE Bentonite

#### COMMENTS

Depth (ft)	Sample ID	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
_			ML	SILT		E
- - - - - 5			CL	SILTY CLAY, (CL), tan brown, to medium stiff		- - - - - - - - - - - - - - - - - - -
_ _ 10						-10
			GW	SANDY GRAVEL, (GW), well graded, to wet	–Bentonite	_ _ _ _ _ _
- 15 - - - - -						15     
- 20 20 						
25 25 						- 25 - - - - -
- 30 30						
- 35 		0.000	ML	GRAVELLY SILT, (ML), tan orange, to stiff	Natural Backfill	35    
40			MI	CANDY CILT (MI) coff to me discons shift		40 
45 45			ML	SANDY SILT, (ML), soft to medium stiff		
L_50		ag is intended for	ML	GRAVELLY SILT, tan orange, to stiff		F0



TEC	HNOL	OGIES			_		
Depth (ft)	Sample ID	Graphic Log	nscs	Material Description		Well Diagram	EL. (ft AMSL)
55					### Color		-55
60							
65 					(100 mm)		- 
- 70 - - - - - 75							70    75
80					\$3000 \$3000		80
- - - - - - 85			SW	GRAVELLY SAND, (SW), medium to coarse grained, with silt		Natural Backfill	- - - - 85
90							90
95 - - - -					2000 C C C C C C C C C C C C C C C C C C		- - 95
- - 100					10000000000000000000000000000000000000		-100
105  							
110							-110
_ 115 _		00000	GW-GM	SILTY GRAVEL, (GW), medium to coarse grained, gray	1		115 -



	TUNOL	OGIES				
Depth (ft)	Sample ID	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
		000000000000000000000000000000000000000		brown, with sand, dense		
-		0000				-
E		0000000				E
- 120		0000				_ 120
F 120		00000				F-120
F						F
F						F
F		0000				F
F 405		00000				105
<u> </u>		000000				125
F		0 $0$ $0$ $0$ $0$				
F		10000				F
F						-
Ė						F
130		00000				-130
<b> </b>		0 0 0 0				
<b> </b>						
<b> </b>						
E		00000				E
_ 135		200000000				135
Ŀ						E
E			N 41	CDAVELLY CILT ton with sond		E
E		19. 180 p.	ML	GRAVELLY SILT, tan, with sand		E
F						F
<del>-</del> 140						-140
F		19/19/06				-
F		P. 1 9 0 0 0 0				_
F						F
Ė.		0. 100 00				<u> </u>
145		1. 400.0				-145
-						- ''
<b> </b>						<u> </u>
<b> </b>		9. 180 P.				
<b> </b>		\$600\$\$600\$\$	GP	GRAVEL, coarse grained, gray green, with sand, dense		
150		0.00.30.00.30				- 150
F .00						E
E		64885668866				
L		£2000 £2000				
L		62862866				
- - 155		0.0000000000000000000000000000000000000				_ 155
F 133		86000860008 6400000000000000000000000000				-133
E		5-003-0003-0				E
E						E I
E		020000000000000000000000000000000000000				<u> </u>
_ _ 160						_ 160
F 100		60000000000000000000000000000000000000				- 100
E						E
E		£2556556				E l
E						E !
165		66666666666666666666666666666666666666				165
165		6-22 30 20 20 30 30 30 30 30 30 30 30 30 30 30 30 30				-165
F						F
F		2.00 3.00 0.00 0.00 0.00 0.00 0.00 0.00				F !
F			ML	GRAVELLY SILT, tan brown, some clay		F
F 470		19 1000		<b>,</b>		F 470
170						-170
F						F .
F		19.700 p.3				<b> </b>
F						<b> </b>
F						L
175		19. 18/0 Pig				-175
ļ.						<u> </u>
Ė.						<u> </u>
E		19/16/06/				<u> </u>
F		P. 19 10 . 3				<u> </u>
180						-180
E						E
<u> </u>		11900				<u> </u>



	T N O L	OGIES			I	
Depth (ft)	Sample ID	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
- - - - - - - - - - - - -						- - - 185 - - -
190 			GW-GM	GRAVEL, medium to coarse grained, with sandy silt		- 190  
- - - 195 - -						- - 195 - -
						- - 
205 						
- - 210 - - -			GW-GM	SANDY GRAVEL, coarse grained, with silt		- 
215 215 						- 
- - 220 - - - -					Natural backfill	
- 005					1887-887-887 1887-887-887 1900-90-00 30-01	- 005
<del>225</del>				Termination Depth at: 225.00 ft.		-225 - - - - - - -
230  						230
- - - 235 - -						- - 235 - -
- - - 240 - -						- - - 240 - -
- - - - 245 - - -						- - - 245 - - -



**PROJECT NUMBER** THINKM01 **DRILLING COMPANY** Bridger Drilling **COORDINATES** -111.086637, 45.729356 PROJECT NAME Barnard Geotherm **DRILLER** Tyler Sampson **COORD SYS CLIENT**Barnard **DRILL RIG** Foremost 24 SURFACE EL. (ft AMSL) 4,608 **START DATE** 05/20/24 **DRILLING METHOD** Dual Wall Rotary WELL TOC (ft) -2.5 **END DATE** 06/03/24 **CHECKED BY** Pat Thomson LOGGED BY Pat Thomson MP ELEVATION FT AMSL 4610.5 TOTAL DEPTH OF BORING FT 255.00 **DEPTH TO WATER FT** 12.37 **SCREENED INTERVAL FT**182-202 **TOTAL WELL DEPTH FT** 202.0 **BOREHOLE DEPTH (ft)** 255.00 **SURFACE COMPLETION** Well Install **GROUT** bentonite **BOREHOLE DIAMETER (in)** 8 **CASING TYPE** Steel FILTER PACK Natural gravel and gravel pack SCREEN TYPE 6-inch telescoping stainless steel SEAL TYPE bentonite

#### COMMENTS

Depth (ft)	Graphic Log	nscs	Material Description	Well Diagram  El. (ft AMSL)
-				4610
E 0				
-		CL	TOPSOIL	
5		CL-ML	CLAYEY SILT, (CL-ML), low plasticity, pale orange, few coarse rounded gravel, dry to moist, soft, blocky	4605
- - - - -		GW-GM	SILTY GRAVEL, (GW-GM)	4600
10			SIETT SIGNEE, (STY SIN)	
- - - - - - 15				4595
- - - - - 20				4590
- 20 				natural 4585
25  				silty-sandy-gravel
- - - 30				
35				4575
_ _ _ _ _ _				4570
- 40 - - - - - -				4565
_ _ 45 _ _				



Depth (ft)	Graphic Log	nscs	Material Description		Well Diagram	EL. (ft AMSL)
- 50				2.8		- 4560 - - - -
	0000					-
55	00000000					- 4555 - - - -
	2000			× ×		- - - - 4550
60	100000					- 4550
	00000					- - - - 4545
65						- - - -
				× ×		- - - 4540
70						- - - -
	1 000 1			2,8		- - - 4535
75						
	00000					- 4530 
80				× ×	natural silty-sandy-gra	vel-
						- - 4525
85	00000					- - - -
00						- - 4520 - -
90		CL-ML	SILTY CLAY, (CL-ML), medium plasticity, pale orange to tan, with silt, to wet, to medium stiff, homogeneous			
95						- 4518 - - -
						-
100						- 4510 - - - -
				× ×		- - - - 4505
105		SC	CLAYEY SAND, (SC), medium to coarse grained, subrounded, loose to medium dense  SANDY GRAVEL, (GW), coarse grained, light tan and,			
			some silt, dense to very dense			4500
110						_ _ _ _
						- - - 4495



TECH	NOLOGIE	<u> </u>			
Depth (ft)	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
_ _ 115 _ _					- - - - -
_ _ _ 120 _		GW	SILTY GRAVEL, (GW), coarse grained, dark brown to gray, with sand, to dense		4490 
- - - - - 125	00000				4485 - - - - - -
 130					4480
_ _ _ _ _ 135					- 4475   
- - - - - - 140					4470 4470 
_ _ _ _ _ 145		СН	GRAVELLY SILT, (CH), low plasticity, tan, with clay, medium stiff to stiff	natural	
_ _ _ _ _ 150			Sun to Sun	silty-sandy-gravel	- 4460   
_ _ _ _ _ _ _ 155					4455
_ _ _ _ _ 160		СН	GRAVELLY SILT, (CH), low plasticity, light tan, with clay, to medium stiff		- - - - 4450 - - -
_ _ _ _ _ _ _ _ _ 165					- - - - 4445 - - -
- - - - - - - - - - - - - - - - - - -					- - 4440 
					- - - - 4435
- 175      					- - - - 4430
100		SW	GRAVELLY SAND, (SW), coarse grained, well graded,		-



TECH	INOLOGIE	S			
Depth (ft)	Graphic Log	sosn	Material Description	Well Diagram	EL. (ft AMSL)
<del>- 100</del> -			subrounded, pink to olive, trace silt, dense to very dense		_
E	20000				_ _ 4425
E	00000				- 4425 -
185	000000				_
Ē					_
Ė	00000				4420
_ _ 190					_
F 100	00000			natural silty-sandy-gravel	- 
E				Siny sainty gravel	_
Ē	00000				_ 4415 _
195	0000				_
E	0000000				_
-	00000				_ _ 4410
F					_
<u> </u>	2000				_
		CL	SILTY CLAY		_ _ _
-		CL	SILIT CLAT		4405 
_ _ 205					_
Ē					_
E					_ _ 4400
E					_ 1100
210					
Ē					_
					4395
_ 215					_
- 210					_
E					4000
Ė					4390
220		SC	SILTY SAND, (SC), tan to light brown, with medium to		_
E		30	coarse subrounded gravel		_
E					_ _ 4385
F				washed gravel	_
225					
					_ _
E					_ 4380 _
230		00.014	CANDY OR WELL WILL IN LOUIT LORANGING		_
E	000	GP-GM	SANDY GRAVEL with interbedded SILT and GRAVELLY SILT with CLAY, bed thicknesses 2-3 feet. Mixed water		_
Ē			production.		_ 4375
	0000				
_ 235 _					_
F	0.000				_
E					4370
					_
E					_
E					_ _ 4365
E	19. 1000				-
245					Ē



EL. (ft AMSL) **Graphic Log** Depth (ft) Well Diagram **Material Description** uscs 4360 250 -washed gravel 4355 Termination Depth at: 255.00 ft. 4350 - 260 4345 - 265 4340 \_ \_ 270 4335 - 275 4330 - 280 4325 - 285 4320 - 290 4315 295 4310 - 300 4305 305 4300 310



PROJECT NUMBER THINKM01DRILLING COMPANY Bridger DrillingCOORDINATES -111.0874, 45.72986PROJECT NAME Barnard GeothermDRILLER Tyler SampsonCOORD SYS

CLIENTBarnardDRILL RIG Foremost 24SURFACE EL. (ft AMSL) 4,608START DATE 06/07/24DRILLING METHOD Dual Wall RotaryWELL TOC (ft) -3.1

END DATE 06/10/24CHECKED BY Pat ThomsonLOGGED BY Pat ThomsonMP ELEVATION FT AMSL 4611.1TOTAL DEPTH OF BORING FT 260.00DEPTH TO WATER FT 12.82SCREENED INTERVAL FT205-230TOTAL WELL DEPTH FT 232

BOREHOLE DEPTH (ft) 260.00 SURFACE COMPLETION Well Install GROUT bentonite

BOREHOLE DIAMETER (in) 8 CASING TYPE steel FILTER PACK natural gravel and gravel pack

SCREEN TYPE 6-inch telescoping stainless steel SEAL TYPE bentonite

#### COMMENTS

			T .	T		
Depth (ft)	Graphic Log	nscs	Material Description		Well Diagram	EL. (ft AMSL)
_						_ 4610
0		CL-ML	TOPSOIL  CLAYEY SILT, (CL-ML), light orange, some coarse rounded			
- - - - - 5 - -			gravel, dry to moist, soft to medium stiff, homogeneous			4605      
E						4600
10		GW	SANDY GRAVEL, (GW), medium to coarse grained, well graded, rounded, gray, dry to wet, medium dense to dense			_ _ _ _ _ _
- - - - - 15						_ 4595 _ - - - -
20						- - - 4590
- 20 					natural silt-sand-gravel	_ _ _ _ 4585
25 25 					backfill	
30						4580     
- - - - - 35	0000000	CL-ML	CLAYEY SILT, (CL-ML), low plasticity, pale orange, with coarse rounded gravel, medium stiff to stiff			4575 
						_ 4570 
- 40     						- - - - 4565
- - 45 -			nmental net gesteehnigel nurneses			



Depth (ft)	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
- - - - 50 - -					4560 - - - - 4555
_ _ 55 _		GM	SILTY GRAVEL, (GM), medium to coarse grained, rounded, with clayey sand, to wet		-
- - 60 					- 4550      
- - 65					- 4545 
- - - - 70					4540
- - - - - 75					- - 4535 - - - - -
- - - - - - - - - - - - - - - - - - -				natural -silt-sand-gravel backfill	- - - 4530 - - - - -
- - - - - - - - - - - - - - - - - - -					- 4525 
- - - - - - - -					- 4520 - - - - - - -
- - - - - - - - - -	00.00 00				- 4515 - - - - - - - -
100 					4510 - - - - - - - - -
_ _ _ 105 _		GW	SANDY GRAVEL, (GW), medium to coarse grained, subrounded, with silt, to wet, dense to very dense		- - - - - - - - - - - - - - -
_ _ _ 110					- - - 4500 - - -



Depth (ft)	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
 115 					
120					- 4490 - - - - - - -
125 					- 4485    
130 		GP	SILTY GRAVEL, (GP), medium to coarse grained, subrounded, some clay		- 4480 
135 135					4475
- 140 					4470
145 145 				natural silt-sand-gravel backfill	- 4465 
150					- 4455
155					- 4455 
160 160 	0.000 000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.000 0.				- 4445
165 		GW-GM	SILTY GRAVEL, (GW-GM), medium to coarse grained, subrounded, gray to tan, with clay, to dense		- 4440
170 					- 4440  - - - - - - - - - - - - - - - -
 175 					- 4433 



	NOLOGIE	S			
Depth (ft)	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
180	20,000				E
_ - - - - - - - - - - - - -					- 4425 
E					- - - - 4420
- - 190 -	1001)004				-  -  -  -  -
195					- 4415  - -
E	00000				_
200	000000	GW	SANDY GRAVEL, (GW), coarse grained, well graded, subrounded, gray to dark gray, with silt, to very dense		- 4410 - - - - -
205				natural	4405
	000000			-silt-sand-gravel backfill	4400
210					- - - - - - - - - - -
_ _ 215 _					
220					- - - 4390 - - - -
- 005					- - - 4385 -
- 225 - - - - - - -					4380
230					4275
235		GM	SILTY GRAVEL, (GM), medium to coarse grained, subrounded, gray to light brown, with clay, to wet, to dense		- 4375 - - - - - -
_ _ _ _ _ 240			, 5 , 5 , 5 , 5 , 5 , 5 , 5 , 5 , 5 , 5	Filter Pack	4370
- - - - - - - - 245					- - - 4365 - -



	<u>NOLOGIE</u> I				
Depth (ft)	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
				–Filter Pack	4360
255 					4355 - - - - - -
260			Termination Depth at: 260.00 ft. Target depth		- - 4350 - -
265			Terminateri Bepar at. 200.00 k. Target depar		- - - - - - - - - - - - - - -
270					4340 
					- 4335 - - - - - -
280					4330
285					4325
- - - - - - - - - - - - - - - - - - -					- 4320  - - - - -
					- 4315    
300					4310 4310 
305					4305
310					- 4300    



**PROJECT NUMBER THINKM01** PROJECT NAME Barnard Geotherm **CLIENT**Barnard

**START DATE** 08/29/24 END DATE 08/29/24 MP ELEVATION FT AMSL DRILL RIG Foremost DR 24 **DRILLING METHOD** Dual Wall Rotary **CHECKED BY** J Rose

**DRILLER** Tyler Sampson

**DRILLING COMPANY** Bridger Drilling

TOTAL DEPTH OF BORING FT 340.00

**COORD SYS** SURFACE EL. (ft AMSL) WELL TOC (ft) LOGGED BY Pat Thomson **DEPTH TO WATER FT** 15.00 **TOTAL WELL DEPTH FT** 280

COORDINATES ,

**SCREENED INTERVAL FT**160-280

BOREHOLE DEPTH (ft) 340.00 **BOREHOLE DIAMETER (in)** 8

**SURFACE COMPLETION** Sand

**GROUT** Bentonite **CASING TYPE** Steel FILTER PACK 10/20 Filter sand SCREEN TYPE Stainless Steel continuous wrappe SEAL TYPE Bentonite

#### COMMENTS

Depth (ft)	Sample ID	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
5				TOPSOIL		5
10     15	Ž	¥	SP-SC	GRAVELLY SAND, (SP-SC), light brown to tan, with clayey silt, with clay, wet, medium dense	-Bentonite	
						- - - - 20
- - - - - 25 - -						- - - - - - - - - - - - - - - - - - -
- - - - - - - - - - - - - - - - - - -						- - 30 - - - - - -
35					Natural Backfill	- 35 - - - - - -
- 40  - - - -						
- 45 						



E Depth (ft)	Sample ID	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
- - - - - - - - - - - - - - - - - - -						55
						- - - - - - - - - - - - -
- - - 65 - - -						- - 65 - - - -
- - 70 - - -						
- - 75 - - - - -						- 75 - - - - - - - - -
80 80 					Natural Backfill	
- - - - - - - - - - - - -						- - - - - - - - - - - -
- 90 						
- 95 			GP-GM	SILTY GRAVEL, light brown to gray, with sandy silt, silty clay, dense		
- 100 - - - - - - - -						
- 105     						- - - - - - - - - - - - - - -
- 110 						
_ _ 115 _		or is intended for an				-115



	TO NOL	OGIES				
Depth (ft)	Sample ID	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
- - - - - - - - - - - - - - - - - - -						- - - - - - - - - - - - - - - - - - -
- - 125 - -						_ 125 _ - -
130			ML	GRAVELLY SILT, (ML), with sand		
- - 135 - - - - -			GW	GRAVEL, (GW), with sand	Natural Backfill	
- 140 140 						
- - 145 - - - - - -						- 145 - - - - - -
- - 150 - - - - - -			ML	SANDY SILT, tan to brown		
155 155  _ _ _ _ _						
- - 160 - - - - -						
_ 165 _ 165 		0.000	GW	SANDY GRAVEL, (GW), coarse grained, dark gray to		- 165   
- - 170 - - - - -			SP-SM	olive  GRAVELLY SAND, with sandy silt		- 170    
- - 175 - - - - - - -			J. JIVI	O. U. V. ELLI O'NYD, WILLI SERICY SIIL		- 175     
_ _ 180 _						- 180  



	I	OGIES				Т
Depth (ft)	Sample ID	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
=		0. 6.00.				
185 185 			SW	GRAVELLY SAND, (SW), coarse grained, gray to brown, dense		- 185  
- - - 190 - - -						- 
- - 195 - -			ML	GRAVELLY SILT, (ML), tan brown		- - 195
200 			GW	SANDY GRAVEL, (GW), coarse grained, gray to brown, dense		-200
205 						
210 			ML	GRAVELLY SILT, (ML), with silt, and clay		210
_ 215		0 0 0 0	GW	SANDY GRAVEL, (GW)		215
- - - - 220			GW	SANDT GIVAVEE, (GW)		220
			ML	SANDY SILT, (ML) SANDY GRAVEL, and		225
- - - - - 230				,		230
235 		>000	ML	SILT, with sand		
240 240 						-240
- 245 245 			GP-GM	SANDY GRAVEL, with silt		



		0 G T E S			W 11 D:	ASL)
Depth (ft)	Sample ID	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
250 						- 250 
255						- - 255
260			GM	Silty Gravel		
265						
- - 270 - - -						
275			GW	Well Graded Gravel		
280 			CL	CLAYEY SILT, (Lean Clay with Sand) brown, with sand,		
285				stiff to hard		
- - 290 - -						
- - 295 - - - -					Natural Backfill	- 295   
300					### ##################################	
305					Dev S	
310						
ا مرح		<u> </u>		t geotechnical nurnoses		age 5 of 6



#### **BORING AND WELL CONSTRUCTION LOG IN - 1**

	<u>HNOL</u>	UGIES	1	T	I	
C Depth (ft)	Sample ID	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
320						-310
- - - 325 -					Natural	- - 325 - -
330					Backfill	- - 330
- - 335 - -						- 335 - -
340				Termination Depth at: 340.00 ft.		- - - - - - - - - -
345						_ _ 345 _ _ _ _
- - - - 350 - -						- - 350
- - - 355 -						- - 355
- - - 360						- - 
- - - - 365 - -						- - 
370						
375						
380						- - - 380

## **Submittal Data**

PROJECT:	UNIT TAG:	QUANTITY:
	TYPE OF SERVICE:	
REPRESENTATIVE:	SUBMITTED BY:	DATE:
ENGINEER:	APPROVED BY:	DATE:
CONTRACTOR:	ORDER NO.:	DATE:



### 300S200-5

Submersible pumps in stainless steel. EN 1.4301 (AISI 304). EN 1.4401 (AISI 316). EN 1.4539 (AISI 904L). Typical application: Ground water, Irrigation, Mining, Fountain, Off-shore etc.

Product photo could vary from the actual product

5

Conditions of Service					
Flow:	300 US gpm				
Head:	150 ft				
Efficiency:	%				
Liquid:	Water				
Temperature:	68 °F				
NPSH required:	19.22 ft				
Specific Gravity:	1.000				


Pump Data	
Liquid temperature range:	5 140 °F
Product number:	14B70005

Motor Data


Main frequency: 60 Hz


20

P2 = 15.8 HP NPSH = 19.22 ft



# Submittal Data





#### Materials:

Impeller: Stainless steel Impeller: AISI 304 Impeller: EN 1.4301



Company name: Northwest Pipe Fittings Inc.

Created by: Scott Bond Phone: 4062520142

**Email:** sbond@northwestpipe.com

**Date:** 10/14/2024

#### Count | Description

1 **300S200-5** 

Product No.: 14B70005
Pump without motor

Multi-stage submersible pump for raw water supply, groundwater lowering and pressure boosting. The pump is suitable for pumping clean, thin, non-agressive liquids without solid particles or fibers.

horizontal and vertical installation.

The pump is fitted with a built-in non-return valve.

Liquid:

Pumped liquid: Water
Liquid temperature range: 5 .. 140 °F
Selected liquid temperature: 68 °F
Density: 62.29 lb/ft³

Technical:

Pump speed on which pump data are based: 3450 rpm

Actual calculated flow: 300 US gpm
Rated flow: 317 US gpm

Resulting head of the pump: 150 ft
Rated head: 177.2 ft

Approvals: CULDWUS,CCSAUS

Approvals for drinking water: PROP65

Curve tolerance: ISO9906:2012 3B

Return valve: YES

Materials:

Pump: Stainless steel

EN 1.4301 AISI 304 Stainless steel

Impeller: Stainless steel
EN 1.4301

AISI 304

Installation:

Maximum operating pressure: 870.23 psi
Maximum outlet pressure: 104.43 psi
Type of connection: NPT(F)
Size of connection: 3 inch
Motor diameter: 6 inch
Minimum borehole diameter: 6.1 in

Electrical data:

Motor flange design: Grundfos
Power (P2) required by pump: 20 HP

Others:

Minimum efficiency index, MEI ≥: -.-DOE Pump Energy Index CL: 0.92
Net weight: 37.9 lb
Gross weight: 43.7 lb
Shipping volume: 1.13 ft³
Country of origin: US

Custom tariff no.: 8413.70.2004



NPSH = 19.22 ft

Company name:

e: Northwest Pipe Fittings Inc.

Created by: Phone:


Scott Bond 4062520142


Email:

sbond@northwestpipe.com

**Date:** 10/14/2024









Country of origin:

Custom tariff no.:

Value Description General information: Product name: 300S200-5 Product No.: 14B70005 EAN: 5700391744167 Price: \$ 5123 Technical: Pump speed on which pump data are based: 3450 rpm Actual calculated flow: 300 US gpm Rated flow: 317 US gpm Resulting head of the pump: 150 ft Rated head: 177.2 ft Stages: 5 Number of reduced-diameter impellers: NONE CULDWUS,CCSAUS Approvals: Approvals for drinking water: PROP65 Curve tolerance: ISO9906:2012 3B Model: В Return valve: YES Materials: Stainless steel Pump: Pump: EN 1.4301 Pump: **AISI 304** Impeller: Stainless steel Impeller: EN 1.4301 Impeller: **AISI 304** Installation: Maximum operating pressure: 870.23 psi Maximum outlet pressure: 104.43 psi Type of connection: NPT(F) Size of connection: 3 inch Motor diameter: 6 inch Minimum borehole diameter: 6.1 in Liquid: Pumped liquid: Water Liquid temperature range: 5 .. 140 °F 68 °F Selected liquid temperature: Density: 62.29 lb/ft3 **Electrical data:** Motor flange design: Grundfos Power (P2) required by pump: 20 HP Others: Minimum efficiency index, MEI ≥: DOE Pump Energy Index CL: 0.92 Net weight: 37.9 lb Gross weight: 43.7 lb Shipping volume: 1.13 ft<sup>3</sup>

US

8413.70.2004

Company name: Northwest Pipe Fittings Inc.


Scott Bond Created by: Phone: 4062520142

Email:

P2 = 15.8 HP NPSH = 19.22 ft

sbond@northwestpipe.com

10/14/2024



#### **FOLLOW-UP PAGE**

Applicant will provide all responses to questions marked for follow-up on a separate document entitled "Follow-up Responses" with the question number labeled. Answer questions in the same format as the form. For responses in the form of checkboxes, write "Y", "N", or "S". Constrain narrative responses to the specific question as is asked on the form; do not respond to multiple questions in one narrative. Label units in narrative responses and tables. Tables must have the exact headings found on the form. Questions that require items to be submitted to the Department may be marked "S" when the required item is attached to the Preapplication Meeting Form. Label all submitted items with the question number for which they were submitted. The Applicant may not alter the Preapplication Meeting Form signed at the Preapplication Meeting. Instead, the Applicant must use the Amended Responses procedure defined below. Do not include additional information for questions not marked for follow-up here; instead include any additional information pursuant to the process for amending responses defined below.

Questions marked for follow-up 30 31.a. 32 - all



#### AMENDED RESPONSES PAGE

The Applicant may not alter the Preapplication Meeting Form signed at the Preapplication Meeting or the Follow-up Page. If a response has changed to a question answered at the preapplication meeting, the Applicant can provide a new response in a separate document entitled "Amended Responses" with the question number labeled. Answer questions in the same format as the form. For responses in the form of checkboxes, write "Y", "N", or "S". Constrain narrative responses to the specific question as is asked on the form; do not respond to multiple questions in one narrative. Label units in narrative responses and tables. Tables must have the exact headings found on the form. Questions that require items to be submitted to the Department may be marked "S" when the required item is attached to the Preapplication Meeting Form. Label all submitted items with the question number for which they were submitted. The Applicant will mark all question numbers with an amended response in the table below and note for each question whether the response will replace the response given at the preapplication meeting or will provide additional information to consider in conjunction with the response given at the preapplication meeting. The Applicant will return the "Amended Responses" document with the "Follow-up Responses" document and the signed Preapplication Meeting Form.

*Ouestions with amended responses* 

#### FOLLOW-UP PAGE AFFIDAVIT & CERTIFICATION

"I/we attest that this preapplication meeting form, follow-up page, and amended responses page accurately portray my proposed project. I am aware that my application for this project will not qualify for a discounted filing fee and expedited timelines if upon submittal of the application to the department, I change any element of the proposed application from the preapplication meeting form and follow-up materials (ARM 36.12.1302(6)(a))."

to the	5/1/25
Applicant Signature	Date
Applicant Signature	Date
"We confirm that the preapplication form and follow-up information are adequate for the Department to proceed v 36.12.1303. Or, if the applicant has elected to complete technical analyses, we confirm they have submitted each p on the proposed project and the Department is able to proceed with the scientific credibility review (ARM 36.12.1).	piece of technical analysis required based
Department Signature	Date
Department Signature	Date



**Certificate Of Completion** 

Envelope Id: 2E0A5725-97EB-44BB-B807-D53B406EFBBE

Subject: Complete with Docusign: 600P\_41H\_30165312\_BarnardConstruction\_PreappMeetingForm.pdf

Source Envelope:

Document Pages: 33 Signatures: 2 **Envelope Originator:** Initials: 0 Certificate Pages: 5 Lyra Reynolds

AutoNav: Enabled

Envelopeld Stamping: Enabled

Time Zone: (UTC-07:00) Mountain Time (US & Canada)

1539 11th Avenue Helena, MT 59601 Lyra.Reynolds@mt.gov

Status: Completed

IP Address: 161.7.117.90

**Record Tracking** 

Status: Original Holder: Lyra Reynolds Location: DocuSign

2/11/2025 4:10:08 PM Lyra.Reynolds@mt.gov Security Appliance Status: Connected Pool: StateLocal

Storage Appliance Status: Connected Pool: Montana Dept of Natural Resources &

Conservation

Location: DocuSign

**Signer Events** 

Lyra Reynolds

lyra.reynolds@mt.gov

Montana Department of Natural Resources and Conservation

Security Level: Email, Account Authentication

(None)

Signature **Timestamp** 

> Sent: 2/11/2025 4:14:36 PM Viewed: 2/11/2025 4:15:02 PM Signed: 2/11/2025 4:15:14 PM

Signature Adoption: Pre-selected Style Using IP Address: 161.7.117.90

**Electronic Record and Signature Disclosure:** 

Not Offered via DocuSign

Matthew Engel

matthew.engel@barnard-inc.com

In Person Signer Events

Security Level: Email, Account Authentication

(None)

Matthew Engel

Lyra Reynolds

Signature Adoption: Pre-selected Style Using IP Address: 66.9.182.124

Signed using mobile

Sent: 2/11/2025 4:15:18 PM Viewed: 2/11/2025 4:37:13 PM Signed: 2/11/2025 4:37:32 PM

Sent: 2/11/2025 4:15:18 PM

Viewed: 2/11/2025 4:38:09 PM

**Electronic Record and Signature Disclosure:** 

Accepted: 2/11/2025 4:37:13 PM

ID: 2f3356a3-6b74-4c81-a89c-21b00363072b

Signature **Timestamp** 

**Editor Delivery Events Status Timestamp** 

**Agent Delivery Events Status** Timestamp

**Intermediary Delivery Events Status Timestamp** 

**Certified Delivery Events Status Timestamp** 

**Carbon Copy Events Status Timestamp** 

COPIED

Pat Thomson

pthomson@waterenvtech.com

Senior PM

Security Level: Email, Account Authentication

(None)

**Electronic Record and Signature Disclosure:** 


Carbon Copy Events	Status	Timestamp			
Not Offered via DocuSign					
Witness Events	Signature	Timestamp			
Notary Events	Signature	Timestamp			
Envelope Summary Events	Status	Timestamps			
Envelope Sent	Hashed/Encrypted	2/11/2025 4:14:36 PM			
Certified Delivered	Security Checked	2/11/2025 4:37:13 PM			
Signing Complete	Security Checked	2/11/2025 4:37:32 PM			
Completed	Security Checked	2/11/2025 4:37:32 PM			
Payment Events	Status	Timestamps			
Electronic Record and Signature Disclosure					

#### Form 600-P - Follow-Up Items


#### **Questions Marked for Follow-Up:**


Questions, Narrative, Responses, and Tables	Response
2. Provide a map created on an aerial photograph or topographic map that shows the following: section corners, township and range, a north arrow, all proposed points of diversion labeled with a unique POD ID number, all proposed places of use, all proposed conveyance structures, all proposed places of storage, and places of use for all overlapping water rights.	Attached
30. Provide the Aquifer Testing Addendum (Form 600-ATA). This form will be required	Submitted:
before the Preapplication Meeting Form is deemed complete.	See below
31. Have you submitted a completed Form 633 to DNRC for review?	Submitted:
	See below
32. Do you have a map with the location of each well/pit labeled and, if available, with the GWIC ID?	Attached


- 2. A site map with Township, Range, Section corners and north arrow, and all labelled points of diversion, conveyance line and injection wells is provided on the attached figure.
- 30. Form 600-ATA was submitted on March 4, 2025 for a completion review. The review was completed by DNRC and response provided on March 7, 2025.
- 31. Form 633 was also submitted to DNRC on March 4, 2025. The review resulted in a request for completion of Form 653 variance request.
  - Form 653 was submitted to DNRC on March 7, 2025. DNRC provided a variance grant letter to the applicant on April 14, 2025 (attached).
- 32. Consistent with item 2. above, the attached well map provides points of diversion, conveyance, and injection wells including associated GWIC IDs.











## THE MONTANA DEPARTMENT OF NATURAL RESOURCES AND CONSERVATION

**GOVERNOR GREG GIANFORTE** 



DNRC DIRECTOR AMANDA KASTER

DNRC 2273 Boot Hill Ct, STE 110 Bozeman, MT 59715 406-586-3136

April 14, 2025

Barnard Construction Co., Inc 701 Gold Avenue Bozeman, MT 59715

Subject: Variance Request dated March 7, 2025, for Permit Preapplication 41H 30165312

Dear Applicant:

This letter is to inform you that your request for an aquifer testing requirement variance from the Aquifer Testing Requirements under ARM 36.12.121 for proposed Permit Application No. 41H 30165312 has been granted. Multiple DNRC staff reviewed this request, and the aquifer test information has been fully reviewed. Based on these reviews, I grant the variance request in your letter dated March 7, 2025. In addition to this general granting of the aquifer testing variance, the specifics being granted are outlined below.

The variance is granted from the following aquifer testing requirements (ARM 36.12.121):

- 3(a) Pumping must be maintained throughout the duration of the test. The rate may not depart from the average pumping rate by more than +/- 5%.
- 3(g) Background groundwater levels in the production well and observation well(s) must be monitored at frequent intervals for at least two days prior to beginning the aquifer test according to Form No. 633.
- 3(h) Groundwater levels in the production and/or observation well(s) must be reported with 0.01-foot precision according to the schedule specified on Form No. 633.
- 3(e)(iii) The testing procedures for a minimum of eight-hour drawdown and yield test performed on any production well must follow (a), (d), and (h).

In summary, the Department is able to grant variances from ARM 36.12.121(3(a)), 36.12.121(3(e(iii))), 36.12.121(3(g)), and 36.12.121(3(h). Granting of variances does not mean a water right will be granted. Please contact the Bozeman Regional Office if you have any questions.

Thank you,

Kerri Strasheim

Regional Manager

**Bozeman Water Resources Office** 

Water Resources Division

Cc, via email: Pat Thomson, Consultant

pthomson@waterenvtech.com



# 600P\_41H\_30165312\_BarnardConstruction\_Pre appMeetingForm\_signed

Interim Agreement Report

2025-05-01

Created: 2025-05-01

Ву: Patrick Thomson (pthomson@waterenvtech.com)

Status: Archived

Transaction ID: CBJCHBCAABAAO1--rc7RMp6aKnSWV8879K-UxoGsRguM

#### Agreement History

Agreement history is the list of the events that have impacted the status of the agreement prior to the final signature. A final audit report will be generated when the agreement is complete.

## "600P\_41H\_30165312\_BarnardConstruction\_PreappMeetingFor m\_signed" History

Document created by Patrick Thomson (pthomson@waterenvtech.com) 2025-05-01 - 4:29:35 PM GMT

## **Montana Department of Natural Resources and Conservation**



#### Receipt

04/30/25 12:47 PM MST

**WR#** : 41H 30165312 **Transaction Id** : 10661568738

Payment Type : Credit/Debit Card

Description	Price	Quantity	Amount
Water-Filing Fees (All Forms)	\$500.00	1	\$500.00
Surcharge			\$20.00
TOTAL			\$520.00

#### **Billing Information**

WATER & ENVIRONMENTAL TECHNOLOGIES PATRICK THOMSON 480 E. PARK BUTTE, MT 59701 4064900329 pthomson@waterenvtech.com

Thank you for your payment!

**Montana Department of Natural Resources and Conservation** 



# REQUEST FOR PREAPPLICATION MEETING

ARM 36.12.1302(2) (Revised 01/2024)

#### **Instructions**

Use this optional form to submit a written request for a preapplication meeting, as required in ARM 36.12.1302(2) for applicants electing to complete a preapplication meeting with the department prior to submitting an application for a beneficial water use permit or change in appropriation right pursuant to §85-2-302, MCA. Use additional sheets as necessary.

Submit this form to the appropriate regional office; see contact information on the last page of this form.

For Department Use Only

RECEIVED
14 JAN 2024
BOZEMAN WATER
RESOURCES
(rec'd via email to BOZ RO)


Date Received	
Received By	
Scheduled Meeting Date	

1.Appl	icant Name					·····			· · · · · · · · · · · · · · · · · · ·
	ng Address								·····
								Zip	
							e		
Emai	il:								
0 Dan		/:£ -4l-	4l A	-1:4\					
2. кер									
B.4						Attorney 🗌 F	Representa	ative is Other	
	ng Address								<del></del>
									<del></del>
Hom	e Phone					Other Phone	e		<del> </del>
Emai	il:								<del></del>
3. Are	you requesting	a preap	plication r	neeting	for a permit o	or change app	olication?		
	☐ Permit		Change						
4. Iden	tify the followin	g elem	ents of the	propose	ed permit or	change in app	ropriation	۱.	
a)	The flow rate ar	- nd volun	ne of water	required	· •		•		
,	Flow Rate		П GРМ	□ CFS	Volum	ne	Acre-Fee	t	
b)	The point of dive						_		
,			1/4	1/4	1/4 Section	, Township	ь Г	] N	ПЕ∏₩
						-		· _ ,	
	Lot/Tract								
								] N	
	County		· · · · · · · · · · · · · · · · · · ·						
	Lot/Tract		Block		Subdivision I	Name			<del></del>
c)	The place of use	e:							
	Acres	Lot _	Block_	1/4	1/4	1/4 Sec	, Twp	🗌 N 🗌 S, Rge _	🗆 E 🗌 W
	Acres	Lot _	Block_	1/4	1/4	1/4 Sec	, Twp		
	Acres	Lot _	Block_	1/4	1/4	1/4 Sec	, Twp		
	Acres	Lot	Block	1/4	1/4	1/4 Sec	Twp	□ N □ S. Rae	ПЕПИ



	Acres Lot	Block1/4	1/4	_1/4 Sec	, Twp	_	🗆 E 🗆
d)	The source of water:						
e)	The proposed purpose:						
f)	For a change in appropriation						
,	Type of water right	_	. , ,	_			
	Type of water right						
	Type of water right						
g)	For a change in appropriation	on right, an exp	lanation of histor	ical use of the	e right(s) pr	oposed for chang	ge:
h)	Any proposed place of stora #1 Capacity: Surface Acres Location:1/41/4 _	x Max 1/4 Sectio	Depth (feet) n, Township	x (.4 for d	ams/.5 for S, Range _	pits) = 	
	#2 Capacity: Surface Acres	x Max	Depth (feet)	x (.4 for d	ams/.5 for	pits) =	Acre-Feet
	Location:1/41/4 _	1/4 Sectio	n, Township		S, Range _		
	#3 Capacity: Surface Acres	x Max	Depth (feet)	x (.4 for d	ams/.5 for	pits) =	Acre-Feet
	Location:1/41/4 _	1/4 Sectio	n, Township	N 🔲 :	S, Range _		
i)	For applications proposing a  New Well #11/41  County  Lot/Tract Blo  Estimated Well Depth	/41/4 SecckFeet	ction, Town	ship □	N □ S, F		
	New Well #21/41 County				J N ∐ S, F	Range ∐ I	⊨ ∐ W
	Lot/Tract Blo						
	Estimated Well Depth						

W



# WORK COPY -LE



IN1 -> GWIC 335309 IN2 -> GWIC 335811

EX 1 → awic 335313 EX 2 → awic 335315 From: Pat Thomson
To: Reynolds, Lyra

**Subject:** [EXTERNAL] RE: Pre-Application Meeting Form Submittal

**Date:** Monday, May 5, 2025 12:19:31 PM

Attachments: image001.png image002.png

image002.png Figure2.pdf

#### Here you go.

From: Reynolds, Lyra <Lyra.Reynolds@mt.gov>

Sent: Monday, May 5, 2025 10:37 AM

**To:** Pat Thomson <pthomson@waterenvtech.com> **Subject:** RE: Pre-Application Meeting Form Submittal

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

#### Sounds great. Thank you!



Lyra Reynolds (they/them/she/her) | Hydrologist/Specialist

Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation

2273 Boot Hill Court, Suite 110; Bozeman, MT 59715 **DESK:** 406-556-4500 **EMAIL**: <a href="mailto:lyra.reynolds@mt.gov">lyra.reynolds@mt.gov</a>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram

[instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

**From:** Pat Thomson <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

**Sent:** Monday, May 5, 2025 10:36 AM

**To:** Reynolds, Lyra < <u>Lyra.Reynolds@mt.gov</u>>

Subject: [EXTERNAL] RE: Pre-Application Meeting Form Submittal

Hey Lyra,

Yes, you are right there is an issue with the labels. I missed the double well symbol when forwarding along. The IN-1 and IN-2 locations are correct. I'll have the figure corrected to show the GWIC ID for each new well in parentheses after the well names (i.e. EX-1 (GWIC ID: 335313), etc.) and identify the pre-existing GWIC wells as "Nearby GWIC Wells. How does that sound?

Thanks,

Pat

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov>

**Sent:** Monday, May 5, 2025 10:06 AM

**To:** Pat Thomson <a href="mailto:pthomson@waterenvtech.com"> **Subject:** RE: Pre-Application Meeting Form Submittal

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

Hey Pat-

I have a really quick question about the map that was submitted in the Preapp Follow-Up materials. I can't tell if the well points were due to a formatting issue when the map was printed or if I am getting mixed up, but it looks like the GWIC ID points of the injection wells are off of the marks for the injection wells? I assume the blue points on the follow up map (attached) are based on the well log lat-long and that is why they are different from the red points.

I made two work copies of maps you have provided, which are attached. Are the GWIC IDs next to each well location the correct number for that well?

Thank you!

-Lyra



**Lyra Reynolds** (they/them/she/her) | Hydrologist/Specialist Bozeman Water Resources Office Montana Department of Natural Resources and Conservation 2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

DESK: 406-556-4500 EMAIL: lyra.reynolds@mt.gov

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram [instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

**From:** Pat Thomson <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

**Sent:** Thursday, May 1, 2025 10:53 AM **To:** Reynolds, Lyra < Lyra.Reynolds@mt.gov>

Subject: [EXTERNAL] RE: Pre-Application Meeting Form Submittal

Here you go.

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov>
Sent: Wednesday, April 30, 2025 1:35 PM

**To:** Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a> <a href="mailto:submittal">Subject:</a> RE: Pre-Application Meeting Form Submittal

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

Hey Pat-

Would you please send me a copy of that receipt if you paid online? The payment takes a couple days to be processed in our system, but we would receipt it today as you paid the fee today. I just need confirmation of the payment.

Let me know if you have any questions.

-Lyra



**Lyra Reynolds** (they/them/she/her) | Hydrologist/Specialist Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation

2273 Boot Hill Court, Suite 110; Bozeman, MT 59715 **DESK:** 406-556-4500 **EMAIL**: <a href="mailto:lyra.reynolds@mt.gov">lyra.reynolds@mt.gov</a>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram

[instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

From: Pat Thomson < pthomson@waterenvtech.com >

**Sent:** Wednesday, April 30, 2025 12:51 PM **To:** Reynolds, Lyra <<u>Lyra.Reynolds@mt.gov</u>>

Subject: [EXTERNAL] RE: Pre-Application Meeting Form Submittal

Hey Lyra,

Sorry, I drifted past the link you had already provided – we're all good.

Thanks,

Pat

From: Pat Thomson

**Sent:** Wednesday, April 30, 2025 7:12 AM **To:** Reynolds, Lyra < lyra.reynolds@mt.gov> **Subject:** Pre-Application Meeting Form Submittal

Hey Lyra,

Attached please find the complete Pre-Application Meeting form with follow-up certification signature, and the Follow-Up responses. I wasn't able to determine how to pay the permit via the transaction portal. Is there a simple link I could follow to do this, or, is it possible to give you

#### a credit card number or similar?

Thanks for your help,

Pat



Senior Hydrogeologist

P: (406) 723-1532 C: (406) 490-0329

waterenvtech.com [waterenvtech.com]

From: Pat Thomson
To: Reynolds, Lyra

**Subject:** [EXTERNAL] RE: Pre-Application Meeting Form Submittal

**Date:** Thursday, May 1, 2025 10:50:50 AM

Attachments: image001.png image002.png

600P 41H 30165312 BarnardConstruction PreappMeetingForm Follow-Up signed.pdf

sign Audit Report.pdf

#### Hey Lyra,

I'm definitely not the most tech savvy but believe I figured out what you need and have produced the validation page.

I re-signed the original completed form, saved a certified simply selected e-sign from the menu, and produced the audit report. Hopefully this is the ticket. If not, I may need more direction.

Thanks,

Pat

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov> Sent: Wednesday, April 30, 2025 1:43 PM

**To:** Pat Thomson <pthomson@waterenvtech.com> **Subject:** RE: Pre-Application Meeting Form Submittal

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

Pat-

One more thing. The signature on page 33 appears to be a copy of a wet signature. If it was electronically signed, we need the verification of signature page that is produced by the signing application (i.e. DocuSign summary page or Adobe certified signatures).

If this is a wet signature, our office must receive the original signature for the form to be received. You may mail in the signature separately, but we cannot receive the form until we have a wet signature or a verified e-signature.

-Lyra



**Lyra Reynolds** (they/them/she/her) | Hydrologist/Specialist Bozeman Water Resources Office Montana Department of Natural Resources and Conservation 2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

DESK: 406-556-4500 EMAIL: lyra.reynolds@mt.gov

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram [instagram.com]

**From:** Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

**Sent:** Wednesday, April 30, 2025 12:51 PM **To:** Reynolds, Lyra <<u>Lyra.Reynolds@mt.gov</u>>

**Subject:** [EXTERNAL] RE: Pre-Application Meeting Form Submittal

Hey Lyra,

Sorry, I drifted past the link you had already provided – we're all good.

Thanks,

Pat

From: Pat Thomson

**Sent:** Wednesday, April 30, 2025 7:12 AM **To:** Reynolds, Lyra < lyra.reynolds@mt.gov > **Subject:** Pre-Application Meeting Form Submittal

Hey Lyra,

Attached please find the complete Pre-Application Meeting form with follow-up certification signature, and the Follow-Up responses. I wasn't able to determine how to pay the permit via the transaction portal. Is there a simple link I could follow to do this, or, is it possible to give you a credit card number or similar?

Thanks for your help,

Pat



Senior Hydrogeologist

P: (406) 723-1532 C: (406) 490-0329

waterenvtech.com [waterenvtech.com]

From: Pat Thomson
To: Reynolds, Lyra

**Subject:** [EXTERNAL] Re: Variance Request dated March 7, 2025, for Permit Preapplication 41H 30165312

**Date:** Tuesday, April 29, 2025 11:06:47 AM

Attachments: <u>image001.png</u>

great, thank you!

PThomson 406-490-0329

From: Reynolds, Lyra <Lyra.Reynolds@mt.gov> Sent: Tuesday, April 29, 2025 9:36:58 AM

**To:** Pat Thomson <pthomson@waterenvtech.com>

Subject: RE: Variance Request dated March 7, 2025, for Permit Preapplication 41H 30165312

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

You can reference the 633 and 600-ATA items in your follow-up information. For example-Follow-up Question 31: Form 633 was submitted to Department on DATE. Form 653 requesting variances was submitted to the Department on DATE. The variance grant letter is attached.

Please make sure you just address all the follow-up items. We have the 600-ATA, Form 633, and Form 653 on file so I feel ok with having you just reference them and not resubmit them.

Please include the variance grant letter as part of your follow-up to Question 31.

Thank you!

-Lyra



**Lyra Reynolds** (they/them/she/her) | Hydrologist/Specialist Bozeman Water Resources Office Montana Department of Natural Resources and Conservation 2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

DESK: 406-556-4500 EMAIL: <a href="mailto:lyra.reynolds@mt.gov">lyra.reynolds@mt.gov</a>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram

[instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

From: Pat Thomson <pthomson@waterenvtech.com>

**Sent:** Tuesday, April 29, 2025 9:30 AM **To:** Reynolds, Lyra <Lyra.Reynolds@mt.gov>

Subject: [EXTERNAL] Re: Variance Request dated March 7, 2025, for Permit Preapplication 41H 30165312

Regarding the 600-ATA and 633 items, am I able to reference a submittal date, or do these need submitting again?

Essentially, the only additions are two GWIC numbers on the well figure, and the fee.

Thanks

PThomson 406-490-0329

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov>
Sent: Tuesday, April 29, 2025 9:08:21 AM

**To:** Pat Thomson pthomson@waterenvtech.com>

Subject: RE: Variance Request dated March 7, 2025, for Permit Preapplication 41H 30165312

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

Yes! You can submit it using this link: https://opp.mt.gov/doa/opp/DNRWater/cart

Just use the "Water-Filing Fees (All Forms)" item and item cost will be \$500. Please put the Application # in the WR# section if you do choose to use the online portal.

There is a fee associated with online payment, also.

-Lyra



**Lyra Reynolds** (they/them/she/her) | Hydrologist/Specialist Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation 2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

DESK: 406-556-4500 EMAIL: <a href="mailto:lvra.revnolds@mt.gov">lvra.revnolds@mt.gov</a>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram [instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

From: Pat Thomson pthomson@waterenvtech.com>

**Sent:** Tuesday, April 29, 2025 9:06 AM **To:** Reynolds, Lyra <<u>Lyra.Reynolds@mt.gov</u>>

**Subject:** [EXTERNAL] RE: Variance Request dated March 7, 2025, for Permit Preapplication 41H 30165312

Hey Lyra,

One more question – Is is possible to submit payment through the State Transaction portal?

**From:** Pat Thomson

**Sent:** Tuesday, April 29, 2025 8:27 AM **To:** Reynolds, Lyra < Lyra.Reynolds@mt.gov >

Subject: RE: Variance Request dated March 7, 2025, for Permit Preapplication 41H 30165312

Great! Thanks for the clarification on Part B. We are getting under a timeline and I was out for a bit, and now in the field, so I am trying to avoid any hiccups.

I'll get things out to you as soon as possible.

Thanks again,

Pat

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov>

Sent: Tuesday, April 29, 2025 8:21 AM

**To:** Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

Subject: RE: Variance Request dated March 7, 2025, for Permit Preapplication 41H 30165312

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

Hey Pat-

We filled out the Preapplication Meeting Form (PMF) prior to the existence of a Part A and Part B. The PMF we completed at the February 11, 2025, meeting is just one document with follow-up questions identified at the end. I had sent you a copy of the form we completed in an email on 2/11 but have attached it to this email as well.

When you are ready to submit the form, please submit the following:

- The entire Preapplication meeting form
- All responses to follow-up items identified on page 31 of the form
- The \$500 preapplication fee
- The second signature, found on page 33 of the form

We will accept the form electronically but still require either a wet signature or a verified esignature (DocuSign or Adobe Certified). You may also send the form electronically and mail in a wet signature separately, if you prefer.

Let me know if you have any other questions!



Lyra Reynolds (they/them/she/her) | Hydrologist/Specialist

Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation

2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

**DESK:** 406-556-4500 **EMAIL**: <a href="mailto:lyra.reynolds@mt.gov">lyra.reynolds@mt.gov</a>

 $\underline{\textbf{Website}} \hspace{0.2cm} | \hspace{0.1cm} \underline{\textbf{Facebook}} \hspace{0.1cm} \underline{\textbf{[facebook.com]}} \hspace{0.1cm} | \hspace{0.1cm} \underline{\textbf{X}} \hspace{0.1cm} \underline{\textbf{(Twitter[twitter.com])}} \hspace{0.1cm} | \hspace{0.1cm} \underline{\textbf{Instagram}} \hspace{0.1cm}$ 

[instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

From: Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

Sent: Tuesday, April 29, 2025 7:43 AM

To: Reynolds, Lyra < Lyra.Reynolds@mt.gov>

Subject: [EXTERNAL] RE: Variance Request dated March 7, 2025, for Permit Preapplication 41H 30165312

Hi Lyra,

Our first run-through and I just want to be clear on what is needed to complete the submittal. I see form 600-P Part B for responses to the questions marked for follow-up – Am I to use this form, or simply a stand-alone document with specific information for those items called out on the signed 600-P? I ask, because Part B appears to apply more to amended responses rather than responses.

Thanks,

Pat

**From:** Reynolds, Lyra <<u>Lyra.Reynolds@mt.gov</u>>

Sent: Monday, April 28, 2025 8:03 AM

**To:** Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

Cc: Ellis, Kendrew < Kendrew. Ellis@mt.gov >; Strasheim, Kerri < kstrasheim@mt.gov >; Rasmussen, Derek

<<u>Derek.Rasmussen@mt.gov</u>>; Norman, Evan <<u>Evan.Norman@mt.gov</u>>

Subject: RE: Variance Request dated March 7, 2025, for Permit Preapplication 41H 30165312

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

HI Pat-

We have not received the completed preapplication meeting form nor the \$500 fee. Once we have received the completed form, with all follow-up information, and the \$500 fee, we will review the form for completeness. If the form is deemed complete, the Department will proceed with preparing the Technical Analyses.

You/the Applicant still need to return the Preapplication Meeting Form with all follow-up information identified at our February 11, 2025, meeting, along with the fee.

Please let me know if you have any questions.

-Lyra



**Lyra Reynolds** (they/them/she/her) | Hydrologist/Specialist

Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation

2273 Boot Hill Court, Suite 110; Bozeman, MT 59715 **DESK:** 406-556-4500 **EMAIL**: <a href="mailto:lyra.revnolds@mt.gov">lyra.revnolds@mt.gov</a>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram

[instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

**From:** Pat Thomson < <u>pthomson@waterenvtech.com</u>>

**Sent:** Friday, April 25, 2025 5:35 PM

**To:** Reynolds, Lyra < <u>Lyra.Reynolds@mt.gov</u>>

**Cc:** Ellis, Kendrew < <a href="mailto:Kendrew.Ellis@mt.gov">Kendrew.Ellis@mt.gov</a>; Strasheim, Kerri <a href="mailto:kstrasheim@mt.gov">kstrasheim@mt.gov</a>; Rasmussen, Derek

<Derek.Rasmussen@mt.gov>; Norman, Evan <Evan.Norman@mt.gov>

Subject: [EXTERNAL] RE: Variance Request dated March 7, 2025, for Permit Preapplication 41H 30165312

Hy Lyra,

I've been away for a bit and I'm glad to see the variance was granted. Are you able to provide a status of the pre-application form status, and has, or will the DNRC begin its technical analysis of the pumping test? Please let me know if there additional information you need from WET at this time?

Thanks,

Pat

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov>

Sent: Monday, April 14, 2025 3:30 PM

**To:** Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

Cc: Ellis, Kendrew < Kendrew. Ellis@mt.gov>; Strasheim, Kerri < kstrasheim@mt.gov>; Rasmussen, Derek

<<u>Derek.Rasmussen@mt.gov</u>>; Norman, Evan <<u>Evan.Norman@mt.gov</u>>

Subject: Variance Request dated March 7, 2025, for Permit Preapplication 41H 30165312

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

Pat-

The Department has granted an aquifer testing requirement variance from the Aquifer Testing Requirements under ARM 36.12.121 for proposed Permit Application No. 41H 30165312. Attached are the aquifer testing addendum review and the variance grant letter that were mailed to the applicant today, April 14, 2025.

Please reach out if you have any questions.

-Lyra



**Lyra Reynolds** (they/them/she/her) | Hydrologist/Specialist Bozeman Water Resources Office Montana Department of Natural Resources and Conservation 2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

**DESK:** 406-556-4500 **EMAIL**: <u>lyra.reynolds@mt.gov</u>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram [instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

From: Pat Thomson
To: Reynolds, Lyra

Cc: <u>Strasheim, Kerri</u>; <u>Norman, Evan</u>

**Subject:** [EXTERNAL] RE: Barnard Construction Preapplication Meeting Form

**Date:** Tuesday, March 4, 2025 4:01:18 PM

Attachments: image002.png image003.png

Hi Lyra,

For review, the following link provides Form 600-ATA and attachments, including the electronic Form 633 for both the 72-hr and 8-hr tests. Please let me know if you have any issues accessing the files. Thanks for your help moving things along.

Pat

Barnard [wetenvtech-my.sharepoint.com]

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov> Sent: Monday, March 3, 2025 11:23 AM

To: Pat Thomson <pthomson@waterenvtech.com>

Cc: Strasheim, Kerri <kstrasheim@mt.gov>; Norman, Evan <Evan.Norman@mt.gov>

Subject: RE: Barnard Construction Preapplication Meeting Form

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

Hi Pat-

The Form 633 and Form 600-ATA can be submitted anytime but have to be submitted before the Preapplication Meeting Form can be deemed complete. For the most efficient use of time for reviewing both forms, we recommend the Form 633 and 600-ATA be submitted prior to the Preapplication Meeting Form, follow-up information, and fee are submitted. This allows the hydrologist to review the aquifer testing information ahead of time, so if any variances are required those are identified prior to submitting the Preapp Form. Any variances must also be requested prior to deeming the Preapp form complete.

For the GWIC numbers and well logs themselves, if those were identified as follow-up questions on the Preapplication Meeting Form please submit them with the follow-up information as well.

Once the Preapplication Meeting Form, follow-up information, and \$500 fee are submitted to the office, we will take 5 business days to review the form for completeness. If the form is deemed complete, we will begin the Technical Analysis. If the form is deemed incomplete, we will return the form to the Applicant to complete the missing/inadequate information identified by the Department.

Let me know if you have any other questions.

-Lyra



Lyra Reynolds (they/them/she/her) | Hydrologist/Specialist

Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation

2273 Boot Hill Court, Suite 110; Bozeman, MT 59715 **DESK:** 406-556-4500 **EMAIL**: <a href="mailto:lyra.reynolds@mt.gov">lyra.reynolds@mt.gov</a>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram

[instagram.com]

How did we do? Let us know here: <u>Feedback Survey [forms.office.com]</u>

From: Reynolds, Lyra

**Sent:** Friday, February 28, 2025 3:05 PM

**To:** Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

Subject: RE: Barnard Construction Preapplication Meeting Form

Hi Pat-

I am going to touch base with our groundwater hydrologist, Evan, to see if he prefers to receive the well information/Form 633 prior to Preapp submittal. He is doing field work today, so I hope to have an answer to you early next week.

-Lyra



Lyra Reynolds (they/them/she/her) | Hydrologist/Specialist

Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation

2273 Boot Hill Court, Suite 110; Bozeman, MT 59715 **DESK:** 406-556-4500 **EMAIL**: <a href="mailto:lyra.reynolds@mt.gov">lyra.reynolds@mt.gov</a>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram

[instagram.com]

How did we do? Let us know here: <u>Feedback Survey [forms.office.com]</u>

**From:** Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

**Sent:** Friday, February 28, 2025 9:19 AM **To:** Reynolds, Lyra < Lyra.Reynolds@mt.gov >

Subject: [EXTERNAL] RE: Barnard Construction Preapplication Meeting Form

Good Morning Lyra,

I am waiting on GWIC numbers for two of the new wells associated with this application. Am I able to

submit the application data etc. and follow up once they are established? Or, would you prefer to have them prior to submitting data, etc.?

Thanks

Pat

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov> Sent: Wednesday, February 12, 2025 8:21 AM

**To:** Matthew Engel <<u>matthew.engel@barnard-inc.com</u>>; Pat Thomson <<u>pthomson@waterenvtech.com</u>> **Cc:** Strasheim, Kerri <<u>kstrasheim@mt.gov</u>>; Ellis, Kendrew <<u>Kendrew.Ellis@mt.gov</u>>; Rasmussen, Derek <<u>Derek.Rasmussen@mt.gov</u>>; Norman, Evan <<u>Evan.Norman@mt.gov</u>>

Subject: RE: Barnard Construction Preapplication Meeting Form

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

Thank you!

Attached is the copy with both Applicant and Department first signatures for your records.

-Lyra



**Lyra Reynolds** (they/them/she/her) | Hydrologist/Specialist Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation 2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

DESK: 406-556-4500 EMAIL: <a href="mailto:lyra.reynolds@mt.gov">lyra.reynolds@mt.gov</a>

<u>Website</u> | <u>Facebook [facebook.com]</u> | <u>X (Twitter [twitter.com])</u> | <u>Instagram [instagram.com]</u>

How did we do? Let us know here: Feedback Survey [forms.office.com]

From: Matthew Engel <matthew.engel@barnard-inc.com>

Sent: Tuesday, February 11, 2025 4:38 PM

To: Reynolds, Lyra < Lyra.Reynolds@mt.gov>; Pat Thomson < pthomson@waterenvtech.com>

Cc: Strasheim, Kerri < kstrasheim@mt.gov >; Ellis, Kendrew < Kendrew.Ellis@mt.gov >; Rasmussen, Derek

<Derek.Rasmussen@mt.gov>; Norman, Evan <Evan.Norman@mt.gov>

Subject: [EXTERNAL] Re: Barnard Construction Preapplication Meeting Form

Docusign complete. Thanks.

Matt

Sent from my Verizon, Samsung Galaxy smartphone

#### Get Outlook for Android [aka.ms]

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov> Sent: Tuesday, February 11, 2025 4:16:17 PM

**To:** Matthew Engel <<u>matthew.engel@barnard-inc.com</u>>; Pat Thomson <<u>pthomson@waterenvtech.com</u>> **Cc:** Strasheim, Kerri <<u>kstrasheim@mt.gov</u>>; Ellis, Kendrew <<u>Kendrew.Ellis@mt.gov</u>>; Rasmussen, Derek

<<u>Derek.Rasmussen@mt.gov</u>>; Norman, Evan <<u>Evan.Norman@mt.gov</u>>

Subject: RE: Barnard Construction Preapplication Meeting Form

Matt-

This has been sent for you to sign. I have sent Pat a copy of the form as well.

Let me know if you have any other questions at this time.

-Lyra



**Lyra Reynolds** (they/them/she/her) | Hydrologist/Specialist Bozeman Water Resources Office Montana Department of Natural Resources and Conservation 2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

**DESK:** 406-556-4500 **EMAIL**: <u>lyra.reynolds@mt.gov</u>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram [instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

**From:** Matthew Engel < matthew.engel@barnard-inc.com >

Sent: Tuesday, February 11, 2025 4:09 PM

To: Reynolds, Lyra <<u>Lyra.Reynolds@mt.gov</u>>; Pat Thomson <<u>pthomson@waterenvtech.com</u>>

**Cc:** Strasheim, Kerri < <a href="mailto:kstrasheim@mt.gov">kstrasheim@mt.gov">kstrasheim@mt.gov</a>; Ellis, Kendrew < <a href="mailto:kendrew.Ellis@mt.gov">kendrew.Ellis@mt.gov</a>; Rasmussen, Derek

<Derek.Rasmussen@mt.gov>; Norman, Evan <Evan.Norman@mt.gov>

**Subject:** [EXTERNAL] Re: Barnard Construction Preapplication Meeting Form

Please send via Docusign. We use something other than adobe for PDF.

Thanks.

Matt



People building for People.

#### **Matt Engel**

#### **Project Manager**

matthew.engel@barnard-inc.com

Phone: (406) 586-1995 | Cell: (406) 595-2201

701 Gold Avenue | Bozeman, MT 59715 | barnard-inc.com [barnard-inc.com]

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov>
Sent: Tuesday, February 11, 2025 3:55 PM

**To:** Pat Thomson cthomson@waterenvtech.com; Matthew Engel <matthew.engel@barnard-inc.com</pre>
Cc: Strasheim, Kerri <kstrasheim@mt.gov</pre>; Ellis, Kendrew <Kendrew.Ellis@mt.gov</pre>
; Rasmussen, Derek

<Derek.Rasmussen@mt.gov>; Norman, Evan <Evan.Norman@mt.gov>

Subject: Barnard Construction Preapplication Meeting Form

Hello-

Attached is the Preapplication Meeting Form for Barnard Construction from today's meeting. Please sign the first signature page (page 30) within 5 days. We can accept a certified e-signature (DocuSign or Adobe Certified) or an original, wet signature. If you would like to digitally sign, please let me know and I can send this via DocuSign to Matt to sign as the Applicant.

The completed Preapplication Meeting Form (PMF), all follow-up information, the second signature (page 33), and the \$500 fee must be submitted to the Bozeman Office within 180-days of the Preapplication Meeting (meeting 2/11/2025, submit by **8/10/2025**). If any variances are required, a variance request must be submitted by day 138 (by 6/29/2025). The Form 633 may be sent in prior to the PMF, but it must be submitted for the PMF to be deemed complete.

The hydraulically connected surface water information (Questions 39-41) has been filled out based on the Department's identification of the connected surface waters.

The Department will review the form for completeness within 5 business days of receipt of the fee. If the PMF is deemed complete, a technical analysis will be prepared within 45 calendar days. Once the technical analysis is returned to the applicant, the applicant has up to 180 days to submit an application (Form 600). An overview of the process is available on our website <a href="here">here</a>, and I have included a quick summary below of the path this application should follow at this time. If the project changes following the preapplication meeting or following the technical analysis, a new preapplication meeting may be required.

Preapplication Meeting Held

- Applicant has up to 180 days to return complete Preapplication Meeting Form
- Department has 5 business days to review for completeness
  - o If deemed incomplete, the form is returned to the Applicant
- Department prepares Technical Analysis within 45 days and sends to applicant
- Applicant has up to 180 days to submit Application after receipt of Technical Analysis
- Department has up to 15 business days to deem application correct and complete or issue a deficiency letter
  - o If deficiency letter is sent, applicant has 120 days to respond
  - Department has 30 days after receipt of response to determine correct and complete
- Department has 60 days to complete a Draft Preliminary Decision
- Draft PD will go to Public Comment if PD to Grant
- If no comments are received, PD is finalized, and Permit can be issued

If you have any questions as you work through completing the preapplication meeting form, please do not hesitate to contact us.

Please let me know if you would like the form sent via DocuSign for the applicant to sign the first signature page.

Best, -Lyra



**Lyra Reynolds** (they/them/she/her) | Hydrologist/Specialist Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation 2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

**DESK:** 406-556-4500 **EMAIL**: <u>lyra.reynolds@mt.gov</u>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram [instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

From: Pat Thomson
To: Reynolds, Lyra

Subject: [EXTERNAL] RE: Pre-App Request

Date: Tuesday, February 11, 2025 11:45:54 AM

Attachments: image001.png

image002.png image003.png

Hi Lyra,

The applicant does not plan to attend locally but will attend virtually for the initial part of the call. I am in the process of forwarding him the invite. His name is Matt Engel and he is the Barnard Construction project manager for the building construction.

Thanks

Pat

From: Reynolds, Lyra <Lyra.Reynolds@mt.gov>
Sent: Tuesday, February 11, 2025 11:26 AM
To: Pat Thomson <pthomson@waterenvtech.com>

Subject: RE: Pre-App Request

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

I meant to add this to my previous email. The Applicant is not required to be at the meeting, but since they are local, I just wanted to double check they would not be attending in person (if they do attend).

Thanks Pat.

-Lyra



Lyra Reynolds (they/them/she/her) | Hydrologist/Specialist

Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation 2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

**DESK:** 406-556-4500 **EMAIL**: <u>lyra.reynolds@mt.gov</u>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram

[instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

From: Reynolds, Lyra

Sent: Tuesday, February 11, 2025 11:19 AM

**To:** Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

Subject: RE: Pre-App Request

Perfect. Should we expect anyone in office today, like the Applicant?

Thank you!

-Lyra



 $\textbf{Lyra Reynolds} \ (\text{they/them/she/her}) \ | \ \text{Hydrologist/Specialist}$ 

Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation

2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

 $\textbf{DESK:}~406\text{-}556\text{-}4500~\textbf{EMAIL:}~\underline{lyra.reynolds@mt.gov}$ 

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram

[instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

From: Pat Thomson pthomson@waterenvtech.com>

**Sent:** Tuesday, February 11, 2025 11:13 AM **To:** Reynolds, Lyra <<u>Lyra.Reynolds@mt.gov</u>> **Subject:** [EXTERNAL] RE: Pre-App Request

Hi Lyra,

I do plan to attend virtually today.

Thanks,

Pat

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov > Sent: Monday, February 10, 2025 1:27 PM

**To:** Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

Subject: RE: Pre-App Request

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

Pat-

Thank you for sending this information over. I will share it with our team.

No specific need to come into the office tomorrow, a virtual meeting is just fine with us. There is a Teams Meeting link in the original invitation I sent, but I have included it in this email as well. Please use this to join the meeting if you attend virtually. Please also let us know ahead of time if you do plan to do virtual.

#### Microsoft Teams Need help? [aka.ms]

#### Join the meeting now [teams.microsoft.com]

Meeting ID: 269 796 344 044 Passcode: qh6oe7Cp

#### Dial in by phone

<u>+1 406-318-5487,,826916304#</u> United States, Billings <u>Find a local number [dialin.teams.microsoft.com]</u>

Phone conference ID: 826 916 304#

Join on a video conferencing device

Tenant key: <u>291818717@t.plcm.vc</u>

Video ID: 111 051 856 4 More info [dialin.plcm.vc]

For organizers: Meeting options [teams,microsoft.com] | Reset dial-in PIN [dialin.teams,microsoft.com]

#### Let me know if you have any questions!

-Lyra



 $\textbf{Lyra Reynolds} \ (\text{they/them/she/her}) \ | \ \text{Hydrologist/Specialist}$ 

Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation

2273 Boot Hill Court, Suite 110; Bozeman, MT 59715 **DESK:** 406-556-4500 **EMAIL**: <a href="mailto:lyra.reynolds@mt.gov">lyra.reynolds@mt.gov</a>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram

[instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

**From:** Pat Thomson <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

**Sent:** Monday, February 10, 2025 1:19 PM **To:** Reynolds, Lyra < Lyra.Reynolds@mt.gov > **Subject:** [EXTERNAL] RE: Pre-App Request

Hi Lyra,

As a matter of fact, yes. Please see following link. I worked through the meeting form and have included figures with well locations, well logs, and a pump curve for the design pumps. WET completed a step-test prior to 72-hour and 8-hour tests on two production wells. James Rose was scheduled to be in the meeting tomorrow, however, he was pulled away to the field. James completed the testing and compiled a draft of form 633 and I'm hoping to confirm them final and I will forward these forms along as soon as available.

Regarding our meeting tomorrow, do you feel there is significant benefit to meeting in your office? Given the temperatures, I'm considering calling in to the meeting.

Thanks

Pat

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov>
Sent: Monday, February 10, 2025 10:00 AM
To: Pat Thomson < pthomson@waterenvtech.com>

Subject: RE: Pre-App Request

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

Hi Pat-

In preparation for our meeting tomorrow, I was curious if you all have any additional information you would like to send along.

We are looking forward to speaking with you tomorrow at 1:00 at the Bozeman office. -Lyra



**Lyra Reynolds** (they/them/she/her) | Hydrologist/Specialist Bozeman Water Resources Office Montana Department of Natural Resources and Conservation

2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

DESK: 406-556-4500 EMAIL: lyra.reynolds@mt.gov

 $\underline{\textbf{Website}} \hspace{0.2cm} | \hspace{0.1cm} \underline{\textbf{Facebook}} \hspace{0.1cm} \underline{\textbf{[facebook.com]}} \hspace{0.1cm} | \hspace{0.1cm} \underline{\textbf{X}} \hspace{0.1cm} \underline{\textbf{(Twitter}} \hspace{0.1cm} \underline{\textbf{[twitter.com]}} \hspace{0.1cm} \underline{\textbf{)}} \hspace{0.1cm} | \hspace{0.1cm} \underline{\textbf{Instagram}} \hspace{0.1cm} \\$ 

[instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

**From:** Pat Thomson <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

**Sent:** Tuesday, January 14, 2025 11:18 AM **To:** Reynolds, Lyra <<u>Lyra.Reynolds@mt.gov</u>>

Cc: Strasheim, Kerri <kstrasheim@mt.gov>; Ellis, Kendrew <Kendrew.Ellis@mt.gov>; Rasmussen, Derek

<Derek.Rasmussen@mt.gov>

Subject: [EXTERNAL] RE: Pre-App Request

Lyra,

I plan to forward along a prepared form and will have figures included.

Thanks,

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov>
Sent: Tuesday, January 14, 2025 11:03 AM

**To:** Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

**Cc:** Strasheim, Kerri < <a href="mailto:kstrasheim@mt.gov">kstrasheim@mt.gov">kstrasheim@mt.gov</a>; Ellis, Kendrew < <a href="mailto:kendrew.Ellis@mt.gov">kendrew.Ellis@mt.gov</a>; Rasmussen, Derek

<<u>Derek.Rasmussen@mt.gov</u>> **Subject:** RE: Pre-App Request

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

Pat-

Perfect, I will get that meeting scheduled. We will plan on having you in-person but will have a remote option just in case.

We will fill out the Preapplication Meeting Form at the meeting, but if you have prepared a copy in advance, we would appreciate if you would send that over. This way we can put your information into the form we will go through, which makes the meeting run smoother.

Any maps of the proposed project are also beneficial for us as we prepare for the meeting. We ask that you send any information over as soon as it is ready, if possible.

We will see you in February.

-Lyra



Lyra Reynolds (they/them/she/her) | Hydrologist/Specialist

Bozeman Water Resources Office

Montana Department of Natural Resources and Conservation

2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

**DESK:** 406-556-4500 **EMAIL**: <u>lyra.reynolds@mt.gov</u>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram [instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

From: Pat Thomson pthomson@waterenvtech.com>

**Sent:** Tuesday, January 14, 2025 10:55 AM **To:** Reynolds, Lyra < Lyra.Reynolds@mt.gov>

Cc: Strasheim, Kerri < kstrasheim@mt.gov >; Ellis, Kendrew < Kendrew.Ellis@mt.gov >; Rasmussen, Derek

<<u>Derek.Rasmussen@mt.gov</u>>

**Subject:** [EXTERNAL] RE: Pre-App Request

Hi Lyra,

Please schedule our meeting to take place on February 11 at 1:00 pm. At this point, I plan to attend the meeting in person.

We have begun preparing the meeting form and please let me know what information you feel may be helpful prior to the meeting.

Thanks, Pat

From: Reynolds, Lyra < Lyra.Reynolds@mt.gov>
Sent: Tuesday, January 14, 2025 10:43 AM

**To:** Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

**Cc:** Strasheim, Kerri < <a href="mailto:kstrasheim@mt.gov">kstrasheim@mt.gov</a>>; Ellis, Kendrew < <a href="mailto:kendrew.Ellis@mt.gov">kendrew.Ellis@mt.gov</a>>; Rasmussen, Derek

<<u>Derek.Rasmussen@mt.gov</u>> **Subject:** RE: Pre-App Request

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

Hi Pat-

We received the attached Request for a Preapplication Meeting. We are scheduling Preapplication Meetings about 30 days from receiving the request. Below are some times we have available for this meeting:

- Tuesday February 11<sup>th</sup> @ 1:00 PM 3:00 PM
- Wednesday February 12<sup>th</sup> @ 1:00 PM 3:00 PM
- Tuesday February 25<sup>th</sup> @ 9:00 AM 10:00 AM
- Tuesday March 4<sup>th</sup> @ 9:00 AM 10:00 AM

Please let me know if you will be attending this meeting in-person or virtually.

I look forward to hearing from you.

-Lyra



**Lyra Reynolds** (they/them/she/her) | Hydrologist/Specialist Bozeman Water Resources Office Montana Department of Natural Resources and Conservation 2273 Boot Hill Court, Suite 110; Bozeman, MT 59715

DESK: 406-556-4500 EMAIL: <a href="mailto:lyra.reynolds@mt.gov">lyra.reynolds@mt.gov</a>

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram [instagram.com]

From: Pat Thomson pthomson@waterenvtech.com>

**Sent:** Tuesday, January 14, 2025 10:06 AM

**To:** Baumgardner, Shannon < Shannon.Baumgardner@mt.gov >

Cc: DNR BOZ WRD < DNRCBozemanWater@mt.gov>; Reynolds, Lyra < Lyra.Reynolds@mt.gov>

**Subject:** [EXTERNAL] RE: Pre-App Request

#### Hi Shannon - thanks for the heads up

From: Baumgardner, Shannon < Shannon.Baumgardner@mt.gov>

Sent: Tuesday, January 14, 2025 9:57 AM

**To:** Pat Thomson < <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

Cc: DNR BOZ WRD < DNRCBozemanWater@mt.gov>; Reynolds, Lyra < Lyra.Reynolds@mt.gov>

**Subject:** RE: Pre-App Request

**WARNING** - This email originated from an EXTERNAL SOURCE. Do not reply, click any link or open attachments unless you can confirm the sender. *Please report suspicious emails to itsupport* 

#### Good morning, Pat-

I no longer work in the Bozeman Regional Office and do not process preapplication meeting requests. One of the New Appropriations staff members in Bozeman can assist you. I have cc'd Lyra; she'll be able to point you in the right direction.



Shannon Baumgardner | Acting New Appropriations Program Manager

Water Rights Bureau

Montana Department of Natural Resources and Conservation

2273 Boot Hill Ct Ste 110 Bozeman, MT 59715

DESK: 406-556-4537 EMAIL: shannon.baumgardner@mt.gov

Website | Facebook [facebook.com] | X (Twitter [twitter.com]) | Instagram

[instagram.com]

How did we do? Let us know here: Feedback Survey [forms.office.com]

**From:** Pat Thomson <a href="mailto:pthomson@waterenvtech.com">pthomson@waterenvtech.com</a>>

**Sent:** Tuesday, January 14, 2025 9:24 AM

**To:** Baumgardner, Shannon < Shannon.Baumgardner@mt.gov >

**Cc:** DNR BOZ WRD < <u>DNRCBozemanWater@mt.gov</u>>

**Subject:** [EXTERNAL] Pre-App Request

Hi Shannon.

I also left you a voicemail this morning. The attached is a request for a preapplication meeting for an open-loop geothermal cooling well system in the Gallatin Valley. This project is now ready to move forward with pre-application meeting and permitting.

Thanks, Pat



Senior Hydrogeologist

P: (406) 723-1532 C: (406) 490-0329

waterenvtech.com [waterenvtech.com]

### **Variance Information**

- Variance Request Form
- WSB Variance Sheet
- Approval or Denial of Variance Request

## Variance Information



ARM 36.12.121 - Aquifer Testing Addendum (ATA) - Review

Department of Natural Resources and Conservation (DNRC) Water Sciences Bureau (WSB)

Applicant		on	
Pre-Application/Application No.	NA	Date Sent to RO	4/7/2025
Regional Office (RO)	Bozeman	WSB Staff Name	Evan Norman, Groundwater Hydrologist

This checklist identifies any deficiencies that would require a variance pertinent to Administrative Rules of Montana (ARM) 36.12.121. **Table 1** lists deficiencies that would require a variance, the recommended action and the rationale describing why the variance request could be considered appropriate. If the requirements of ARM 36.12.121 are satisfied for each item, the box will be checked next to that item indicating such.

Table 1: Deficiencies identified, recommended action and rationale from WSB.

□ No Def	□ No Deficiencies Identified					
Test Duration	Variance (ARM) (R=Requested; A=Additional)	Recommend Granting Variance Request	Rationale:			
72-hr	3(a) ⊠ R □ A	⊠ Yes □ No	Multiple times throughout the first 1,620 minutes of the aquifer testing, the measured discharged fluctuated slightly more than 5 % from the average measured discharge rate of 269.5 gpm. From 1,620 minutes until the end of the test, the pumping was maintained at a constant discharge rate and consistent drawdown was collected in both the Production and Observation Wells.			
72-hr	3(g) ⊠ R □ A	⊠ Yes □ No	The background water levels in the Production Well and Observation Well 1 were collected on two days prior to the day of aquifer testing. The water level difference in the Production Well on the day prior to the aquifer testing was 0.1 ft. The drawdown and recovery data in the Production Well and Observation Well 1 did not appear to be affected by any background level trends. The background level data collected for Observation Well 2 represented the start of the aquifer testing. However, clear interference drawdown was shown in Observation Well 2 and impacts from background levels were not recognizable.			
72-hr	3(h) ⊠ R □ A	⊠ Yes □ No	The Applicant does not follow minimum required time increment schedule for Observation Well 1 and 2 for first 60 minutes of data collection. The remainder of the data collection period fulfilled the requirements of 3(h) and is adequate for obtaining aquifer properties.			
8-hr	3(e)(iii) ⊠ R □ A	⊠ Yes □ No	During the first 16-minutes of the eight-hour drawdown and yield test, the discharge started at 225 gpm and was raised to up			



to approximately 275 gpm with an average measured discharge rate of 263.8 gpm. The discharge deviation greater than 5 % at the start of well testing is common, and the remainder of the pumping was maintained at a constant discharge rate. The requirements for drawdown at yield test under 3(e)(iii), specifically 3(d) and 3(h) were met.

 $36.12.121 \boxtimes (1) \square$  NA Aquifer testing design and procedures must follow standards procedures that are discussed in hydrogeology textbooks and professional literature.

36.12.121(2): Minimum information that must be submitted with applications, check if provided:
☑ (a) Map with labeled location of production and observation wells; and
☑ (b) ☐ NA Well logs of the production and observation wells; and
☑ (c) ☐ NA Form No. 633, in electronic format, with <i>all</i> information and data provided.
36.12.121 (3): Minimum testing procedures are as follows, check if met:
$\square$ (a) $\square$ NA Pumping must be maintained throughout the duration of the test. The rate may not depart from the average pumping rate by more than +/- 5%.
$\boxtimes$ (b) $\square$ NA The average pumping rate must be equal to or greater than the proposed flow rate if the application is for one well or if the total proposed rate for multiple wells can be obtained from a single well.
$\boxtimes$ (c) $\square$ NA The proposed pumping rate may be demonstrated by testing multiple wells as long as (e) is met by one well and the remaining flow rate is demonstrated by eight-hour drawdown and yield tests on additional production wells under (e)(ii) and e(iii).
$\boxtimes$ (d) $\square$ NA Pumping rate must be measured with a reliable measuring device and recorded with clock time according to the schedule on Form No. 633.
☑ (e) ☐ NA Minimum duration of pumping during an aquifer test must be 24 hours for a proposed pumping rate and volume equal to or less than 150 GPM or 50 AF, or 72 hours for a proposed pumping rate and volume greater than 150 GPM or 50 AF.
$\boxtimes$ (e)(i) $\square$ NA At a minimum an eight-hour drawdown and yield test is required on all new production wells.
$\boxtimes$ (e)(ii) $\square$ NA In addition to (e), if more than one new production well is proposed, at a minimum an eight-hour drawdown and yield test is required on all subsequent new production wells.
$\square$ (e)(iii) $\square$ NA The testing procedures for a minimum eight-hour drawdown and yield test performed on any production well must follow (a), (d), and (h).

 $\boxtimes$  (f)  $\square$  NA One or more observation wells must be completed in the same source aquifer as the proposed production well and close enough to the production well so that drawdown is measurable and far enough

that well hydraulics do not affect the observation well.

ARM 36.12.121-ATA-Review Pre-Application/Application No: NA Bozeman Regional Office Gallatin County



□ (g) □ NA Background groundwater levels in the production well and observation well(s) must be monitored at frequent intervals for at least two days prior to beginning the aquifer test according to the Form No. 633.
$\Box$ (h) $\Box$ NA Groundwater levels in the production and/or observation well(s) must be reported with 0.01-foot precision according to the schedule specified on Form No. 633.



#### **INSTRUCTIONS**

Use this form to request a variance from the requirements of ARM 36.12.121 or 36.12.1702, as provided for in ARM 36.12.123.

Submit this completed form to the appropriate regional office by the deadline established during the preapplication meeting or, if a preapplication meeting is not held, include this request with your filed application or as part of a deficiency response.

For Department Use Only

# RECEIVED MAR 7 2025 DNRC BOZEMAN WATER RESOURCES

Basin

Application #

Received Date

filed application or as part of a deficiency response.		Received By
Applicant Name		
Mailing Address		
City		Zip
Home Phone		
Email:		
Representative Name (if other than Applicant)		
☐ Representative is Consultant ☐ Representative is Attorney		
		sentative is Other (describe)
Mailing Address		7in
City		Zip
Home Phone Email:		one
total proposed rate for multiple wells can be  (3)(c) proposed pumping rate may be demonstrate the remaining flow rate is demonstrated by e under (e)(i)(i)  (3)(d) pumping rate must be measured with a relia the schedule on Form No. 633  (3)(e) minimum duration of pumping during an aqu volume equal to or less than 150 GPM or 50 than 150 GPM or 50 AF  (3)(e)(i) at a minimum an eight-hour drawdown an (3)(e)(ii) In addition to (e), if more than one new pr and yield test is required on all subseque (3)(e)(iii) the testing procedures for a minimum eig must follow (a), (d), and (h)  (3)(f) one or more observation wells must be comp and close enough to the production well so t do not affect the observation well	information a age pumping an the prop- obtained from ed by testing eight-hour d able measur uifer test mu o AF, or 72 h d yield test roduction we not new production we int new production draits oleted in the hat drawdow	g rate by more than +/- 5% posed flow rate if the application is for one well or if the som a single well g multiple wells as long as (e) is met by one well and drawdown and yield tests on additional production wells ring device and recorded with clock time according to just be 24 hours for a proposed pumping rate and hours for a proposed pumping rate and hours for a proposed pumping rate and volume greater is required on all new production wells let is proposed, at a minimum an eight-hour drawdown duction wells awdown and yield test performed on any production well e same source aquifer as the proposed production well with its measurable and far enough that well hydraulics
<ul> <li>☐ (3)(g) background groundwater levels in the produintervals for at least two days prior to beging</li> <li>☐ (3)(h) groundwater levels in the production and/or according to the schedule specified on Form</li> </ul>	ning the aquobservation	



Explain the specific variance you are requesting and the reason for requesting it. Also identify your proposed alternative esting methodology or aquifer test data, if applicable. Attach additional sheets if necessary.
☐ ARM 36.12.1702 Physical Surface Water Availability ☐ (1)(b) at a minimum, three measurements that reflect high, moderate, and low flows during the period of diversion ☐ (4) once monthly measurements at department-approved intervals during the proposed period of diversion
Explain the specific variance you are requesting and the reason for requesting it. Also identify your proposed alternative neasurement methodology, if applicable. Attach additional sheets if necessary.



(3)(h) Drawdown measurement frequency; Initial drawdown measurements were limited due to inadequate personnel on site to collect all measurements at the required intervals, primarily over the first 10 minutes of test. All measurements were collected at the required interval following 60 minutes of pumping and the sum of all measurements provides adequate intervals to support analysis.



Form No. 600-ATA/606-ATA (04/2024)

**Applicant Name** 

## APPLICATION FOR BENEFICIAL WATER USE PERMIT OR APPLICATION TO CHANGE A WATER RIGHT AQUIFER TESTING ADDENDUM

ARM 36.12.121

Complete this addendum if the source of water for a Beneficial Water Use Permit or Water Right Change application is groundwater. Check the box denoting the information is attached or data was collected following minimum testing procedures. On a separate document, address the required information. Attachments must be labeled as shown in the sections below (i.e., ATA.3.a).

Section 1	. Att	tachments must make specific reference to the section item shown.
VARIANC	E INF	FORMATION:
ATA.1.a		The Applicant submitted a variance request per ARM 36.12.123 for a variance from the requirements of ARM 36.12.121 and has provided a copy of the written request.
Section 2	. Att	tachments must make specific reference to the section item shown.
MINIMUM	INF	DRMATION THAT MUST BE SUBMITTED WITH APPLICATIONS:
ATA.2.a		Provide a map with labeled location of production and observation wells.
ATA.2.b		Provide well logs of production and observation wells.
ATA.2.c		Provide Form No. 633, in electronic format, with all information and data provided.
ATA.2.d		Provide a description of testing methods and quality of the aquifer test and data.
Section 3	. Att	tachments must make specific reference to the section item shown.
_	the f	TING PROCEDURES: following, if the answer is "NO" or "NA", provide information explaining why on a separate  S □ NO □ NA □ Pumping was maintained throughout the duration of the test and the r
A1A.J.a		not depart from the average pumping rate by more than 5%.
ATA.3.b	rate	S $\square$ NO $\square$ NA $\square$ The average pumping rate is equal to or greater than the proposed flow if the application is for one well or if the total proposed rate for multiple wells can be obtained a single well.
ATA.3.c	and	S  NO  NA  The proposed pumping rate was demonstrated by testing multiple we d 3.e was met by one well and the remaining flow rate demonstrated by eight-hour drawdowr d yield tests on additional production wells under 3.e.ii and 3.e.iii.
ATA.3.d		S $\square$ NO $\square$ NA $\square$ The pumping rate was measured with a reliable measuring device an orded with clock time according to the schedule on Form No. 633.


1




ATA.3.e	YES \(\bigcup \) NO \(\bigcup \) NA \(\bigcup \) The duration of pumping during an aquifer test was at least 24 hours for a proposed pumping rate and volume equal to or less than 150 gpm or 50 acre-feet, or at least 72 hours for a proposed pumping rate and volume greater than 150 gpm or 50 acre-feet.					
	<ul> <li>i. If a variance from 3.e was granted, at a minimum, eight-hour drawdown and yield tests were completed on all new production wells.</li> <li>ii. In addition to 3.e, if more than one new production well is proposed, at a minimum, eight-hour drawdown and yield tests were completed on all subsequent new production wells.</li> <li>iii. The testing procedures for a minimum eight-hour drawdown and yield test performed on any production well followed 3.a, 3.d, and 3.h.</li> </ul>					
ATA.3.f	YES \(\sigma\) NO \(\sigma\) One or more observation wells were completed in the same source aquifer as the proposed production well and close enough to the production well so that drawdown is measurable and far enough away so that well hydraulics do not affect the observation well.					
ATA.3.g	YES NO NA Background groundwater levels in the production well and observation well(s) were monitored at frequent intervals for at least two days prior to beginning the aquifer test according to Form No. 633.					
ATA.3.h	YES \( \subseteq \) NO \( \subseteq \) NA \( \subseteq \) Water levels in the production well and observation well(s) were reported with 0.01-foot precision according to the schedule specified on Form No. 633 (8-hour drawdown and yield test only need to provide water levels for drawdown; no background and recovery data are necessary).					

Form 600-ATA
ATTACHMENTS

### Attachment ATA.2.a Site Map





### Attachment ATA.2.b Well Logs

MONTANA WELL LOG REPORT Other Options

This well log reports the activities of a licensed Montana well driller, serves as the official record of work done within the borehole and casing, and describes the amount of water encountered. This report is compiled electronically from the contents of the Ground Water Information Center (GWIC) database for this site. Acquiring water rights is the well owner's responsibility and is NOT accomplished by the filing of this report.

Quarter Sections

Geocode

Return to menu

Plot this site in State Library Digital Atlas Plot this site in Google Maps

#### Site Name: BARNARD HQ WEST GEOTHERMAL EXTRACTION WELL #2 $\,$ GWIC Id: 335315

Section 1: Well Owner(s)

Section 2: Location

Section

22

1) BARNARD CONSTRUCTION COMPANY (MAIL) 701 GOLD AVE BOZEMAN MONTANA 59715 [06/14/2024] 2) BARNARD CONSTRUCTION COMPANY (WELL) ROYAL WOLF WAY BOZEMAN MONTANA 59715 [06/14/2024]

Township

Latitude

Total Depth: 232 Static Water Level: 17 Water Temperature:

Air Test \*

 $\underline{300}$  gpm with drill stem set at  $\underline{222}$  feet for  $\underline{1}$  hours. Time of recovery  $\underline{1}$  hours. Recovery water level 17 feet.

Pumping water level \_ feet.

Datum

Geomethod Longitude NAD83 -111.08713 NAV-GPS **Ground Surface Altitude Ground Surface Method** Datum Date

SE¼ SE¼

Addition Block Lot

Section 3: Proposed Use of Water GEOTHERMAL-EXTRACTION (1)

Section 4: Type of Work Drilling Method: ROTARY Status: NEW WELL

#### Section 5: Well Completion Date

Date well completed: Friday, June 14, 2024

#### Section 6: Well Construction Details

Range

05E

County

#### Borehole dimensions

From	To	Diameter
0	30	12
30	232	8

#### Casing

01S

GALLATIN

45.7295

From	То	Diameter	Wall Thickness	Pressure Rating	Joint	Туре
-2	210	8	0.025		WELDED	A53B STEEL

#### Completion (Perf/Screen)

l	F	T.	Diam	# of Openings	Size of	Description
l		207		Openings		SCREEN-TIGHT WIND STAINLESS STEEL
ı	207	232	8			SCREEN-CONTINUOUS-STAINLESS

#### Annular Space (Seal/Grout/Packer)

rrom	10	Description		
Λ	20	DENITONITE STUDDY	v	

\* During the well test the discharge rate shall be as uniform as possible. This rate may or may not be the sustainable yield of the well. Sustainable yield does not include the reservoir of the well casing

Section 7: Well Test Data

Section 8: Remarks DRILLED TO 260', BACKFILLED HOLE TO 232' WITH WASHED GRAVEL & SET SCREENS

> Section 9: Well Log Geologic Source

#### Unassigned

From	To	Description
0	20	BROWN/TAN CLAY SILT
20	25	GRAVEL
25	30	SAND & GRAVEL
30	35	CLAY
35	90	SAND & GRAVEL
90	92	CLAY
92	135	GRAVEL
135	140	GRAVEL & CLAY
140	145	GRAVEL
145	160	CLAY
160	165	GRAVEL & SAND
165	175	GRAVEL
175	180	BROWN CLAY
180	185	GRAVEL
185	190	CLAY & GRAVELS

#### **Driller Certification**

All work performed and reported in this well log is in compliance with the Montana well construction standards. This report is true to the best of my knowledge.

TYLER SAMPSON Name: Company: BRIDGER DRILLING INC License No: WWC-165

6/14/2024 Date Completed:

	Site Name: BARNARD HQ WEST GEOTHERMAL EXTRACTION WELL #2 GWIC 1d: 335315 Additional Lithology Records					
From	To	Description				
190	205	CLAY & GRAVELS				
205	208	CLAY				
208	232	GRAVEL & WATER				



**PROJECT NUMBER** THINKM01 **DRILLING COMPANY** Bridger Drilling **COORDINATES** -111.086637, 45.729356 PROJECT NAME Barnard Geotherm **DRILLER** Tyler Sampson **COORD SYS CLIENT**Barnard **DRILL RIG** Foremost 24 SURFACE EL. (ft AMSL) 4,608 **START DATE** 05/20/24 **DRILLING METHOD** Dual Wall Rotary WELL TOC (ft) -2.5 **END DATE** 06/03/24 **CHECKED BY** Pat Thomson LOGGED BY Pat Thomson MP ELEVATION FT AMSL 4610.5 TOTAL DEPTH OF BORING FT 255.00 **DEPTH TO WATER FT** 12.37 **SCREENED INTERVAL FT**182-202 **TOTAL WELL DEPTH FT** 202.0 **BOREHOLE DEPTH (ft)** 255.00 **SURFACE COMPLETION** Well Install **GROUT** bentonite **BOREHOLE DIAMETER (in)** 8 **CASING TYPE** Steel FILTER PACK Natural gravel and gravel pack SCREEN TYPE 6-inch telescoping stainless steel SEAL TYPE bentonite

#### COMMENTS

Depth (ft)	Graphic Log	nscs	Material Description	Well Diagram  El. (ft AMSL)
-				4610
E 0				
-		CL	TOPSOIL	
5		CL-ML	CLAYEY SILT, (CL-ML), low plasticity, pale orange, few coarse rounded gravel, dry to moist, soft, blocky	4605
- - - - -		GW-GM	SILTY GRAVEL, (GW-GM)	4600
10			SIETT SIGNEE, (STY SIN)	
- - - - - - 15				4595
- - - - - - 20				4590
- 20 				natural 4585
25  				silty-sandy-gravel
- - - - - - -				
				4575
_ _ _ _ _ _				4570
- 40 - - - - - -				4565
_ _ 45 _ _				



Depth (ft)	Graphic Log	nscs	Material Description		Well Diagram	EL. (ft AMSL)
- 50				9,8		- 4560 - - -
	00000					-
55	00000000					- 455
	2000					455
60	100000					- 4550 - - - -
						- - - - 454
65	00000					-
						- - - - 4540
70						-
	000					453
75	20000			8		
	000000					453
80					natural silty-sandy-gra	vel
						- - 452
85				8,8		
						- - 452
90		CL-ML	SILTY CLAY, (CL-ML), medium plasticity, pale orange to tan, with silt, to wet, to medium stiff, homogeneous	× ×		
						- - 451
95						
						451
100						
		SC	CLAYEY SAND, (SC), medium to coarse grained, subrounded, loose to medium dense			450
105	00000	GW	SANDY GRAVEL, (GW), coarse grained, light tan and, some silt, dense to very dense			
110						- 450 -
110	000000000			\$\chi		E



Depth (ft)	Graphic Log	nscs	Material Description	Well Diagram	EL. (ft AMSL)
115 115 					- - - - - - 4490
120     		GW	SILTY GRAVEL, (GW), coarse grained, dark brown to gray, with sand, to dense		- - - - - 4485
125     					- - - - - - 4480
130					- - - - - - - 4475
135 135   	000000				4470
					- - - - - - 4465
145 		СН	GRAVELLY SILT, (CH), low plasticity, tan, with clay, medium stiff to stiff	natural silty-sandy-grave	- 4460
150 150 					- - - - - - - 4455
155 					- - - - - - - - - - - - - - - - - - -
160 		СН	GRAVELLY SILT, (CH), low plasticity, light tan, with clay, to medium stiff		- - - - - - - - - - - - - - - - - - -
165 					
170					- 4440 
175 175					- 4435 - - - - - -
_ _ _ _ _		SW	GRAVELLY SAND, (SW), coarse grained, well graded,		4430



	<b>69</b>		Material Description	Well Diagram	MSL)
Depth (ft)	Graphic Log	nscs	Material Bescription	Weii Biagraiii	EL. (ft AMSL)
- 180 			subrounded, pink to olive, trace silt, dense to very dense		- - - - - 4425
- - - - - - - - - - - - - - - - - - -					- - - - - 4420
- - - - - - - - - - - - - - - - - - -				natural silty-sandy-gravel	- - - - - - 4415
- - - - - - - - - 200					- - - - - - - - - - - - - - - - - - -
- - - - - - - - - - 205		CL	SILTY CLAY		- - - - - 4405
					- - - - - - - - - - - - - - - - - - -
- - - - - - - - - - 215					- - - 4395 - -
- - - - - - - - - -					- - - - - - 4390
- 220 - - - - - - - - - -		SC	SILTY SAND, (SC), tan to light brown, with medium to coarse subrounded gravel	-washed gravel	- - - - - - 4385
_ 225 _ _ _ _ _ _ _ _					- - - - 4380
_ 230 _ _ _ _		GP-GM	SANDY GRAVEL with interbedded SILT and GRAVELLY SILT with CLAY, bed thicknesses 2-3 feet. Mixed water production.		- - - - - - - - - 4375
235 					- - - - - 4370
- 240    					- - - - - - - - - - - - - - - - - - -
_ 245					



EL. (ft AMSL) **Graphic Log** Depth (ft) Well Diagram **Material Description** uscs 4360 250 -washed gravel 4355 Termination Depth at: 255.00 ft. 4350 - 260 4345 - 265 4340 \_ \_ 270 4335 - 275 4330 - 280 4325 - 285 4320 - 290 4315 295 4310 - 300 4305 305 4300 310

MONTANA WELL LOG REPORT Other Options

This well log reports the activities of a licensed Montana well driller, serves as the official record of work done within the borehole and casing, and describes the amount of water encountered. This report is compiled electronically from the contents of the Ground

Water Information Center (GWIC) database for this site. Acmiring water rights is the well owner's responsibility and is NOT accomplished by the filling of this report.

Datum

**Quarter Sections** 

Geocode

Plot this site in Google Maps

#### Site Name: BARTIMCO PROPERTIES LLC \* WELL #2 NEXT TO CREEK GWIC Id: 304409

Section 1: Well Owner(s)

Section 2: Location

Section

1) BARTIMCO PROPERTIES LLC (MAIL) PO BOX 99 BOZEMAN MT 59771 [12/17/2019] 2) BARTIMCO PROPERTIES LLC (WELL) ROYAL WOLF BOZEMAN MT 59715 [12/17/2019]

Township

Total Depth: 72 Static Water Level: 5 Water Temperature:

Air Test \*

55 gpm with drill stem set at 58 feet for 1 hours. Time of recovery 1 hours. Recovery water level 5 feet. Pumping water level \_ feet.

\* During the well test the discharge rate shall be as uniform as possible. This rate may or may not be the sustainable yield of the well. Sustainable yield does not include the reservoir of the well casing. Section 8: Remarks

> Section 9: Well Log Geologic Source

Section 7: Well Test Data

GALLATIN Longitude Geomethod Datum Latitude 45.730019 -111.085506 NAV-GPS NAD83

22

Range

05E

Ground Surface Altitude

County

Ground Surface Method Addition Block

SE1/4 SE1/4

NELSON MEADOWS

Section 3: Proposed Use of Water

IRRIGATION (1)

01S

Section 4: Type of Work

Drilling Method: ROTARY Status: NEW WELL

Section 5: Well Completion Date

Date well completed: Wednesday, December 18, 2019

Section 6: Well Construction Details

**Borehole dimensions** 

From To Diameter 0 72 6

Casing

F	rom	То	Diameter	Wall Thickness	Pressure Rating	Joint	Туре
Г	-1.5	68.5	6	0.25		WELDED	A53B STEEL

Completion (Perf/Screen)

From	То	Diameter	# of Openings	Size of Openings	Description
68.5	72	6			OPEN HOLE

Annular Space (Seal/Grout/Packer)

	П		Cont.
From	To	Description	Fed?
0	25	BENTONITE	Y

Unassigned

Date

Lot

From	To	Description	
0	10	CLAY & SAND	
10	27	COBBLES & GRAVEL	
27	68	CLAY BOUND GRAVELS	
68	72	COBBLES & GRAVELS	

#### **Driller Certification**

All work performed and reported in this well log is in compliance with the Montana well construction standards. This report is true to the best of my knowledge.

CURT SAMPSON Name: BRIDGER DRILLING INC Company:

License No: WWC-560 Date Completed: 12/18/2019

### Attachment ATA.2.c Form 633

### Attachment ATA.2.d Aquifer Testing Methods

#### Introduction

Water and Environmental Technologies (WET) conducted and evaluated two aquifer pumping tests for newly completed geothermal extraction wells to support a water-use application request. The wells are part of an open-loop geothermal system at the ThinkOne, Barnard Construction, office building site on Royal Wolf Way, Bozeman, Montana.

The geothermal extraction wells are in the southwest corner of Township 01S, Range 05E, Section 22 (**Figure 2**). The site is adjacent to the frontage road on the north side of Interstate 90 in Gallatin County, Montana. When completed the geothermal system will consist of at least four wells, two-injection wells and the two tested extraction wells completed in the valley Tertiary sand and gravel aquifer. The anticipated groundwater pumping rates for the extraction wells is 275 gpm each (550 gpm combined) to support the buildings heating and cooling system. The pumping tests determined local aquifer hydrologic characteristics, wells efficiencies, and potential drawdown interference between the two pumping wells.

**Table 1.** Wells at the Barnard Construction, ThinkOne site. Location coordinates are in WGS84 datum (MAP XX).

·	Latitude	Longitude	Screened	
Well	(decimal degrees)	(decimal degrees)	interval ft	Total depth ft
Extraction Well #1	45.72943	-111.08654	182-202	212
Extraction Well #2	45.72966	-111.08709	212-232	232
Parkway irrigation well	45.730	-111.08548	Open hole	72

#### **Wells Construction**

Two geothermal extraction wells, (Extraction Well #1 and Extraction Well #2) were drilled and completed for the ThinkOne office building in May and June of 2024 (Figure MAP). Both boreholes were drilled 8.8-inches in diameter to 255 ft through relatively-clean fluvial sand and gravel layers interlayered with silt-and-clay-filled sand and gravels.

#### **Extraction Well #1 Construction**

Extraction Well #1 (EX-1) was backfilled from 255 ft to 202 ft. An 8-inch steel casing was set to 182 ft and a 6.89-inch telescoping well screen was installed from 182-202 ft (20 ft) at a water-producing gravelly-sand. The static-water level measured prior to pumping testing was 16.06 ft (includes a 2.5 ft stickup) (12.86 ft below ground level (bgl)). This well was pumped for the 8-hour pumping test and used as observation well #1 for the 72-hour test.

#### **Extraction Well #2 Construction**

Extraction Well #2 (EX-2) was backfilled with gravel from 255 ft to 232 ft. The 8-inch steel casing was set at 212 ft and the 6.89-inch diameter well screen was installed from 212 to 232 ft (20 ft) in a water producing sandy-gravel. The static-water level prior to the pumping tests was 15.92 ft (includes a 3.1 ft stickup) (12.82 ft bgl). This well was pumped for the 72-hour pumping test and used as observation well #1 for the 8-hour test.

#### **Parkway Irrigation Well**

The parkway irrigation well is north of the test wells across Royal Wolf Way (Figure map). The parkway well was monitored as a second observation well (OBS2) to monitor groundwater levels for both the 72-hour and the 8-hour pumping tests. Completion information for the parkway well (GWIC ID: 304409) was obtained from the Montana Bureau of Mines and Geology, Ground Water Information Center database (MBMG-GWIC, 2024). The irrigation well was completed in 2019 with 6-inch diameter steel casing to 72 feet below ground level (bgl) and completed in sand and gravel as an open hole with no screen (Figure log). The well is located within 50 ft of Cattail Creek. Prior to the pumping tests the static-water level in the parkway well on July 22, 2024, was 7.61 feet (ft), with a stickup of 2.33 ft (5.28 ft bgl).

#### **Pumping Tests**

Geothermal Extraction Wells EX-1 and EX-2 were used alternately as pumping wells or observation wells for two aquifer pumping tests. The parkway irrigation well (GWIC ID 304409), was monitored for both pumping tests. The extraction wells are spaced 163 ft apart. The irrigation well is 340 ft northeast from EX-1 and 428 ft from EX-2.

For the duration of the tests, WET staff measured water levels in all three wells at designated time intervals, monitored and recorded the pumping rate, and adjusted discharge flow in an attempt to maintain a constant 275 gallons per minute (gpm). Water levels were measured using water-level tapes that supplemented measurements from Insitu LevelTroll 400 unvented water-level transducers set in each well accompanied by an Insitu BaroTroll, barometric pressure logger.

Discharge for the pumping tests was measured with a Blue-White Brand F-300 flow meter attached to the 4-inch PVC discharge pipe near the well. Discharge water was routed from the well through a 4-inch pipe into a 6-inch diameter aluminum irrigation pipe that extended 650 feet east to where the water was discharged into north flowing Cattail Creek.

#### **Background water levels**

Background water levels were measured in the extraction wells following well completion and for one day prior to the initial 72-hour test and continuously between the 72-hour test and subsequent 8-hour test. Groundwater levels remained stable through the monitored periods.

#### **Step-Drawdown Pumping Test**

A step-drawdown pumping test was conducted on EX-2 on 7/22/24 to determine the optimum pumping rate for the constant-rate tests. The well was pumped for one hour at 175 gpm, 250 gpm, and at 275 gpm. The 275-gpm pumping rate from each well is the expected operating maximum rate for the geothermal system.

After one hour of pumping at 275 gpm the water level in EX-2 began to stabilize, suggesting the aquifer and the well-screen design did not interfere with the flow rate and laminar flow continued to enter the well screen. Based on results from the step-drawdown test, the pumping rate for the 72-hour pumping test was set at 275 gpm.

#### **Extraction Well #2, 72-Hour Pumping Test**

The 72-hour constant rate pumping test was conducted from July 23 through July 26, 2024, with water-level recovery monitoring continuing until July 29, 2024. The pumping well for this test was EX-2 with observation wells EX-1 (OBS1) and the parkway irrigation well (OBS2) (Figure 2). The test proceeded without interruption for 72-hours. Water levels were measured in each of the three monitored wells.

At the end of the 72-hour test the pump was shut off and the recovering water levels continued to be recorded by the transducers. The first one hour of recovery from the pumping well (EX-2) was also measured manually.

The water level measurements are reported on the included DNRC 633 form for the 72-hour pumping test.

#### **Extraction Well #1, 8-Hour Pumping Test**

WET conducted the 8-hour pumping test in EX-1 on August 12, 2024. WET personnel monitored water levels and pumping rates in EX-1, observation wells EX-2 and the parkway irrigation well (**Figure map**). Water levels measured in the monitored wells are in the included DNRC form 633 for the 8-hour pumping test.

#### **Data Quality**

All data quality is considered to be valid and useful. Pumping flow rates during the 72-hour test were generally maintained at the target flow rate. However, there was an approximate five-hour period during the first 12 hours when the flow was approximately 7.8 percent outside the average rate without an adjustment. Following a meeting between site personnel, the flow was then generally maintained within the five percent requirement.

### Excel File Placeholder

The Form 633 spreadsheets are available outside of the application file.

For **pending applications**, excel files available upon request from the regional office.

For **scanned applications**, excel files available in a separate FileNet link.

Please contact the regional office for more information.